

Apr 20 - 18:7

**INVESTIGATIONS
OF THE
HISTORIC SOUTH RIVER
WOOD DISTILLATION/CHARCOAL
PLANT SITE**

FINAL

MARCH 1992



Ontario

**Environment
Environnement**

INVESTIGATION OF THE
HISTORIC SOUTH RIVER
WOOD DISTILLATION/CHARCOAL
PLANT SITE
FINAL

Prepared For:

Waste Management Branch
Ontario Ministry of the Environment

Prepared By:

CH2M Hill Engineering Ltd.

MARCH 1992



Cette publication technique
n'est disponible qu'en anglais.

Copyright: Queen's Printer for Ontario, 1992
This publication may be reproduced for non-commercial purposes
with appropriate attribution.

PIBS 1817

EXECUTIVE SUMMARY

CH2M HILL ENGINEERING LTD. has conducted a study of the historic South River Wood Distillation/Charcoal plant site. The primary objectives of the study were to establish the physical extent of contamination in soil, lake sediment, surface water and groundwater, and to identify existing health and environmental impacts. The scope was later expanded to include the location of a former disposal area for buried tar pond waste.

The field investigation included a surface mapping program, a preliminary diving inspection in nearby Forest Lake, a subsurface drilling and soil sampling program, and a well installation and groundwater sampling program.

The Village of South River is situated on a flat sand plain. This sand plain extends under the former plant site, and also forms the local water supply aquifer. The municipal water supply wells are located 300 m southwest of the former plant site.

Groundwater contaminated with high levels of polycyclic aromatic hydrocarbons (PAHs), phenolic compounds, and benzene, toluene, xylenes and ethyl benzenes (BTXE) is present under the former tar pit area in the north-central area of the site (Figure 3). This contamination is not laterally extensive as groundwater samples taken less than 100 m away from this area are not contaminated.

No PAH, phenolic, or BTXE contamination was detected in a sample from the South River Municipal Well #2.

In the central area of the site, soil contamination appears to be limited to the areas of a former tar pond and the oven house/holding tank house buildings (Figure 2). Areas of tar contamination exist on ground surface. Evidence of soil contamination in the subsurface was limited to strong odours.

Tar contamination exists on the bottom of Forest Lake in the near-shore area adjacent to the site. Lake sediments in this area are contaminated with high levels of PAHs. No significant contamination of the lake water was detected.

No significant vertical or horizontal hydraulic gradients were measured in the groundwater underneath the former plant area. Under these conditions, only slow groundwater movement is occurring across the site. The low horizontal hydraulic gradients make it difficult to determine the direction of groundwater flow underneath the site. The results of a two-dimensional groundwater flow model indicate that the site area likely lies within the capture zone of the municipal wells. The travel time for the observed contaminated groundwater under the former tar pond area to migrate to the municipal wells was predicted to be on the order of 25 years or longer.

Buried tar pond waste was found in three shallow trenches in the southwest area of the property, about 60 metres from the South River municipal wells. The wastes were buried above the water table.

Three primary exposure pathways for release of onsite contaminants have been identified. These are:

- (i) migration of contaminated groundwater to the municipal wells.
- (ii) direct contact with tars, soils, and lake sediments,
- (iii) aquatic biota uptake of contaminants from lake sediments.

Typical remedial alternatives have been reviewed for each pathway.

Recommendations for further action have been made and include:

- (i) A more extensive diving inspection/sediment sampling program in Forest Lake, and a program of bioassay (lethality) tests of lake sediment samples.
- (ii) a groundwater monitoring program using the South River municipal wells, 3 existing monitor well nests, 2 proposed new well nests, and 1 proposed new shallow well. (Figure 7).
- (iii) restricted access to the subject property

Remedial action, if any, for tar-contaminated surface soils and lake sediments should be evaluated after completion of the lake sediment investigation described in (i) above. Site decommissioning, according to MOE guidelines, should be undertaken before any development of this property proceeds.

CONTENTS

Page

EXECUTIVE SUMMARY	i
1 INTRODUCTION	1
1.1 Background on Project	1
1.2 Scope of Work and Objectives	1
2 METHOD	4
2.1 Field Investigation	4
3 SITE DESCRIPTION	6
3.1 Historical Description	6
3.2 Geology	7
3.3 Hydrogeology	9
3.3.1 The South River Water Supply Wells and Aquifer	9
3.3.2 Groundwater flow Under the Site Area	11
3.3.3 Groundwater Flow Between the Site and the Municipal Wells	14
4 EXTENT OF CONTAMINATION	16
4.1 Forest Lake	16
4.1.1 Lake Sediment	16
4.1.2 Lake Water	20
4.2 Soil Samples	23
4.3 Groundwater	27
4.3.1 Municipal Wells	27
4.3.2 Onsite Monitor Wells	28
4.4 Chemical Characterization of Wood Tar Found Onsite	29
5 POTENTIAL IMPACTS OF CONTAMINATION	33
5.1 Identification of Exposure Pathways	33
5.2 Impact on Municipal Wells	33
5.3 Contact with Contaminated Soils and Sediments	40
5.4 Aquatic Biota Uptake of Contaminants From Lake Sediments	40
6 REMEDIAL ACTION	41
6.1 Remediation of Contaminated Groundwater	41
6.2 Remediation of Contaminated Soil	42
6.3 Remediation of Contaminated Lake Sediments	43
7 ADDENDUM: INVESTIGATION OF BURIED TAR POND WASTE	44
7.1 Field Investigation and Results	44
7.2 Potential Impacts of Buried Waste	45

CONTENTS (cont'd)

	<u>Page</u>
8 CONCLUSIONS	47
9 RECOMMENDATIONS	49
10 REFERENCES	51

APPENDIXES

A FIELD INVESTIGATIONS	
B METHOD OF LABORATORY ANALYSIS AND QA/QC METHODS	
C BOREHOLE LOGS AND WELL CONSTRUCTION DETAILS	
D SLUG TEST RESULTS	
E CHEMICAL ANALYSES	
F DESCRIPTION OF THE GROUNDWATER MODEL	
G GRAIN SIZE ANALYSES	
H SUMMARY OF CCME GUIDELINES	
I ANALYTICAL RESULTS, GROUNDWATER SAMPLES FROM MUNICIPAL WELLS #1 AND #2, NOVEMBER 1989	
J CHEMICAL ANALYSES OF SOIL SAMPLES FROM BURIED TAR POND WASTE AREA, JUNE 1991	

TABLES

	<u>Page</u>
1 Water Level Elevations	12
2 Hydraulic Conductivity of the Sand Aquifer	14
3 Summary of Compounds Found in Lake Sediment Samples (ppb)	17
4 Summary of Compounds Detected in Groundwater and Surface Water Samples (ppb)	21
5 Summary of Compounds Detected in Soil Samples (ppb)	24
6 Summary of Compounds Detected in Tar Samples (ppb)	30
7 Calculated Retardation Factors for Selected Organic Compound	39
8 Summary of Compounds Detected in Soil Samples from Buried Tar Pond Waste	46

FIGURES

	<u>Page</u>
1 Location of the Former Wood Distillation/Charcoal Plant, South River	2
2 1908 Plant Layout, South River Wood Distillation/Charcoal Plant	(in back pocket)
3 Site Plan and Cross Section Location, Historic South River Wood Distillation/Charcoal Plant	(in back pocket)
4 Air Photograph of Plant Site, 1969	8
5 Location of Buried Bedrock Valley, South River Area	10
6 Geological Cross Section of the Site Area	(in back pocket)
7 Extent of Soil Contamination and Water Level Elevation Map (in back pocket)	
8 Model Simulation Domain and Grid	34
9 Model Steady State Groundwater Flow Domain	36
10 Well Capture Zone: 25 years	37
11 Well Capture Zone: 50 years	38

Section 1

INTRODUCTION

1.1 BACKGROUND ON PROJECT

In November 1988, the Ontario Ministry of the Environment (MOE) released an inventory of former industrial plant sites in Ontario producing or using coal and related tars (Intera Technologies Ltd., 1988). Forty-four sites were identified. For each site, the inventory documented general site characteristics and any preliminary indications of the presence of onsite wastes.

A major MOE program is now underway to more fully investigate the potential impacts that these sites may have on human health and the environment. The program is aimed at determining the need for remedial action at individual sites.

The former South River Wood Distillation/Charcoal Plant (Figure 1) was identified by the inventory as a former producer of wood tars and related wastes. Wastes including tars were found onsite.


In November 1989, the MOE initiated an investigation of the South River property. The primary concern on this site is the proximity of the former plant area to municipal water wells. Buried wastes on the plant property may impair the water quality of the wells. Another concern is the potential impact this site may have on a nearby lake. The site is located on the shore of Forest Lake.

1.2 SCOPE OF WORK AND OBJECTIVES

On November 9, 1989, the Ontario Ministry of the Environment issued a Request for Proposal (RFP) entitled 'Investigation of the Historic South River Wood Distillation/Charcoal Plant Site'. The objectives of this study, as outlined in the RFP, are as follows:

- i) To establish the physical extent of waste, contaminated soils, sediments, surface water, and groundwater onsite and offsite.
- ii) To identify existing impacts on public health and the environment and, where necessary, develop recommendations to mitigate or prevent these impacts.

The specific concerns with respect to the site were further detailed in the RFP as follows:



scale 1:25,000

Figure 1: Location of the Former Wood Distillation/Charcoal Plant, South River

1. To determine the presence and extent of tar waste including other related by-products on the plant site, including the area adjacent to the South River (i.e. Forest Lake).
2. To determine the chemical characteristics of waste found at the site and close to the shore.
3. To determine the extent and degree of groundwater contamination associated with the wastes.
4. To determine the impact of contaminated groundwater on the South River (i.e. Forest Lake), and on the municipal well to the southwest. This will require characterization of the municipal aquifer in the area.
5. To determine the presence and extent of any waste related to the operation of the plant in Forest Lake and in the municipal aquifer.
6. To determine the impact on the surface water quality of Forest Lake from any waste found on the bottom of the lake.

After completion of the original field investigation, the scope of the project was expanded to include an investigation of previously buried tar pond wastes in unmarked, shallow disposal trenches on the property.

Section 2 METHOD

2.1 FIELD INVESTIGATION

The field investigation included a surface mapping program, a diving inspection in Forest Lake, a subsurface drilling and soil sampling program, and a well installation and groundwater sampling program. Detailed information on the field methods is presented in Appendix A.

A map of the site area was prepared using a reconnaissance survey and air photographs.

A preliminary diving inspection was conducted in Forest Lake, along one transect line located close to the shoreline adjacent to the former plant site. The bottom of the lake was examined for any visible tar and tar seepages into the surface water within the active sediment zone. Lake sediment and lake water samples were collected. Selected samples were analyzed chemically for polycyclic aromatic hydrocarbon compounds (PAHs) and phenolic compounds (Phenolics).

A drilling/soil sampling program was completed over the area of the former plant site. A total of nineteen boreholes were drilled. The boreholes were drilled in order to assess the presence of subsurface wastes, and to characterize the geological materials underneath the site.

Soil samples obtained during drilling were described in the field. Selected samples were analyzed chemically for PAHs and Phenolics. Four soil samples were submitted for grain-size analysis. Two soil samples were submitted for analysis of the organic carbon content.

A total of nine monitor wells were installed in selected boreholes. The monitor wells were placed so as to provide groundwater level measurements across the site, and to assess the chemical quality of groundwater underneath the site. The rationale for the placement of the wells is as follows:

i) **Upgradient (Background)**

- assess groundwater quality upgradient of the former plant site

ii) **Along the Bank of Forest Lake**

- determine the impact of potential plant wastes, (thought to exist along the bank) on groundwater quality

iii) **Across the Site**

- determine the impact of the former plant operation on groundwater quality by creating a profile across the site from Forest Lake to the municipal wells located to the southwest of the remnant foundation structures
- determine the potential for aqueous phase contaminants to migrate vertically through the assumed impermeable clayey deposits beginning at 20 metres below ground surface.

The groundwater level (i.e depth to water table) was measured in all onsite monitor wells and in an observation well adjacent to the South River municipal wells. The water level in the lake was also measured. All measurements were "tied in" by a survey to a common reference elevation.

Groundwater samples from seven onsite monitor wells and from one of the municipal wells were collected and chemically analyzed for benzene, toluene, xylene, and ethylbenzene (BTXE), PAHs and Phenolics.

Samples of the waste tar were collected from ground surface onsite and from the lake bottom close to shore. Tar samples were chemically analyzed for PAHs, Phenolics, and BTXE.

Section 3 SITE DESCRIPTION

3.1 HISTORICAL DESCRIPTION

The former wood distillation/charcoal plant (see Figure 1) is located on the east side of the town of South River, close to Ottawa Avenue. The site is situated on the shore of Forest Lake. The South River municipal wells (Wells #1 and #2) are about 300 m to the southwest of the site.

The wood distillation plant was used to make wood chemicals such as acetic acid, acetone, methyl alcohol, creosote oils and wood tars. From 1903 to 1954 the facility was operated as a wood distillation plant by the Standard Chemical Company Ltd. Beaver Charcoal, a division of Charcoal Supply and Sales of Ontario Ltd. operated the plant to make charcoal from 1955 to 1967.

The products of the wood distillation plant were formed by combustion and distillation processes. Wood was placed by hand, or later via rail "buggies", into brick or steel and brick ovens. The wood was then burned in the absence of air, and the gaseous products of the combustion were collected and condensed into tar and alcohols ("raw liquor"). The wood residue was charcoal.

After burning, the charcoal was placed in air-tight iron charcoal coolers. Once cooled, charcoal was moved to storage areas.

The raw liquor was pumped to holding tanks. Originally, the liquor was likely further refined by onsite distillation into alcohols, acids, oils and a tar residual. Lime and sulphuric acid were likely used to produce acetic acid from the raw acids. Acetate was an intermediate product in this process. The hot tar residual was cooled and pumped to tar tanks or pits for storage. Records of the Ontario Water Resources Commission indicate that by 1964, the raw liquor was trucked to chemical plants in the United States for refinement.

CH2M HILL has prepared detailed site plans using a 1908 fire insurance plan, and air photographs from 1929, 1969 and 1987 (see Figures 2 and 3 in map pocket). Figure 2 has been prepared to show the following:

- i) The facilities as of 1908, which includes coal sheds, oven house, holding tank house, storage tanks, lime house, storage buildings, oil store house and acetate storage area.
- ii) The South River (i.e. Forest Lake) adjacent to the site.

A tar pit was known to exist on the property in 1977 (Intera Technologies Limited, 1988). A 1969 air photograph shows the tar pit located 20 or 30 m from the shore of Forest Lake, in the north-central area of the site (Figure 4).

In 1978, the area onsite, close to the lake shore, including the tar pit, was excavated under MOE direction (MOE, personal communication). Liquid waste was removed from the site by CPW Disposal Ltd. of Barrie, Ontario. Contaminated soil was excavated and re-buried onsite in three shallow trenches in the western part of the property as shown on Figure 3.

Presently, the site is vacant with only remnants of the former plant (i.e. rubble and foundations). To the west of the site on Ottawa Avenue are residential houses. To the south and southwest are several commercial businesses. Figure 3 shows the current features of the site, including:


- i) locations of foundations and rubble from former buildings
- ii) tar visible on the ground surface
- iii) locations of monitor wells and boreholes emplaced for this study.
- iv) location of the municipal water supply wells southwest of the site.

Development of this property for recreational and residential use has been under consideration since 1977 (Intera Technologies Ltd., 1988).

In November 1989, the MOE obtained samples of raw (i.e. untreated) water from the South River Municipal Wells #1 and #2, and a sample of treated water from Well #2. The water samples were analyzed for inorganic and organic samples including major ions, metals, total phenolics, microbiological parameters, and a range of organic compounds. The results are included in Appendix I. It is pertinent to note that the concentration of total phenolic compounds in each water sample was less than 0.6 ppb, indicating no detectable contamination by phenolic compounds. As well, there was no detectable contamination by any of the other tested organic parameters.

3.2 GEOLOGY

The South River area is located in the physiographic region known as the Number 11 Strip (Chapman and Putnam, 1984). This region is characterized by sand, silt and clay deposits which infill the hollows between bedrock knobs and ridges.



SCALE 1:3700

Figure 4: Air Photograph of Plant Site, 1969

The village of South River is situated on a flat sand plain. The plain is composed of deltaic sands which were deposited by streams entering glacial Lake Algonquin. The sand plain was formed during the recession of the Wisconsin Glacier (Chapman and Putnam, 1984).

Underlying the sand plain, and outcropping to the north and south of the village, is Precambrian granite and gneiss bedrock.

A buried bedrock valley runs underneath the village (Figure 5). The buried valley trends east-west, is approximately 1 km wide, and presumably extends underneath Forest Lake. The depth to bedrock is up to 85 m in the deepest parts of the buried valley. The overburden filling the valley is up to 60 m of clay, silt, sand and boulders, overlain by up to 25 m of primarily fine to coarse sand. The location of the buried valley was defined using local water well records (Geo-Environ, 1978) and geophysical resistivity surveys conducted in 1977 by the MOE (unpublished report, MOE files).

The area of the former plant site and the municipal wells is underlain by at least 20 m of well sorted, fine to coarse sand. The log of a test well in the vicinity of the municipal water supply wells indicates that this clean sand is underlain by a clayey sand (Geo-Environ, 1978). Figure 6 is a geological cross section of the site area. The location of the cross-section is shown on Figure 3.

Boreholes drilled on the former plant site confirmed that the site is underlain by at least 20 m of sand. The borehole logs are presented in Appendix C. The sand is relatively homogeneous, showing little variation between boreholes or with depth. The sand is fine to coarse grained and well sorted. Grain size analyses are presented in Appendix G. The sand has a low organic matter content, as is indicated by an organic carbon content (f_{oc}) of approximately 0.0003 (Appendix E).

3.3 HYDROGEOLOGY

3.3.1 THE SOUTH RIVER WATER SUPPLY WELLS AND AQUIFER

The sand plain in the area of the Village of South River forms the local water supply aquifer. The aquifer is an unconfined, or water-table aquifer.

The sand aquifer follows the east-west trend of the buried bedrock valley. In the centre of the bedrock valley, near the location of the municipal water supply wells, the aquifer is over 20 m thick. The aquifer is hydraulically connected to Forest Lake, meaning that water can move relatively freely between the lake and the aquifer.

Pumping tests conducted between 1978 and 1983 (Geo-Environ, 1978; Geo-Environ, 1983; Morrison Beatty Ltd., 1981) indicate the following aquifer characteristics:




Figure 5: Location of Buried Bedrock Valley, South River Area

Transmissivity: $3.5 \times 10^{-2} \text{ m}^2/\text{s}$
Specific Yield: 0.02 to 0.1

Presently, one of the South River municipal wells is pumped intermittently at approximately 20 L/s. Operation is switched between Well #1 and Well #2 from day to day. In August 1990, the operating well was typically turned on and off once every one or two hours. From September 1989 to August 1990, the South River municipal wells pumped a total of 141,434 m^3 of water (Township Office, personal communication). Water pumpage was highest in late summer and fall, and lowest in winter.

3.3.2 GROUNDWATER FLOW UNDER THE SITE AREA

Water level elevations in the onsite monitor wells were measured in August 1990. Water level measurements were also made in an observation well near the municipal water supply wells, and in Forest Lake. The results are presented in Table 1. Water levels recorded on August 30, 1990 are also recorded on Figure 7. (The August 30th lake water level in Forest Lake was estimated by assuming a similar change in the elevation of the water table and of the lake level between August 20 and August 30).

The water table under the study area was between 4 and 5 m below ground surface in August 1990. These water levels were not observed to fluctuate in response to pumpage of the municipal wells. However, continuous water level monitoring over a period of at least one day, on at least one onsite monitor well, is needed to confirm this observation.

The horizontal hydraulic gradient (ie. slope of the water table) across the plant site was essentially zero. In other words, the difference in groundwater elevation from place to place across the site was on the order of a few centimetres. These small differences may be partly the result of imprecision associated with the field measurements. Based on these measurements, it is not possible to determine a direction of groundwater flow underneath the site. However, the negligible horizontal hydraulic gradient indicates that, at the time of observation, there was very little horizontal groundwater movement across the site.

No vertical hydraulic gradient was measured at any of the three well nests onsite. This indicates that at the time of observation there was no significant upward or downward component of groundwater flow underneath the site.

The water level in Forest Lake was essentially the same as the water table elevation underneath the former plant site. This indicates very little movement of water into or out of the lake via the sand aquifer underneath the site was occurring at the time of observation.

The hydraulic conductivity, or permeability, of the sand aquifer in the study area was estimated using three methods: pumping test analysis, hydraulic response (slug) tests, and grain size analysis of soil samples. The results are presented in Table 2. The

Table 1
WATER LEVEL ELEVATIONS

Well	Ground Elevation *	Meas. Pt Elevation *	August 17, 1990		August 20, 1990		August 30, 1990	
			Depth to Water	Water Elevation *	Depth to Water	Water Elevation *	Depth to Water	Water Elevation *
MWN1A	99.03	99.76	4.22	95.52	4.22	95.52	4.29	95.47
MWN1B	99.35	100.03	4.49	95.54	4.49	95.54	4.56	95.47
MWN2A	99.66	100.54	4.89	95.65	4.89	95.65	4.96	95.58
MWN2B	99.67	100.51	4.87	95.64	4.86	95.65	4.93	95.58
MWN3A	99.54	100.34	4.70	95.64	4.71	95.63	4.77	95.57
MWN3B	99.44	100.39	4.75	95.64	4.75	95.64	4.82	95.57
MWS1	99.54	100.34	4.69	95.65	4.69	95.65	4.76	95.58
MWS2	99.29	100.17	4.68	95.49	4.68	95.49	4.75	95.42
MWS3	99.91	100.59	4.96	95.63	4.96	95.63	5.03	95.56
TW5-78	100.05	100.66	-	-	-	-	4.94	95.72
Forest Lake				95.65	-	(estimated - 95.65)		(estimated 95.58)

* All elevations referenced to floor of pump house, Municipal Well #1, which was arbitrarily assigned an elevation of 100.00 m.

values calculated from slug tests represent the low end of the range of values of hydraulic conductivity of the subsurface materials around the monitor wells. At many monitor wells, slug tests were not successful due to the high hydraulic conductivity of the materials at these locations, causing the immediate recovery of the water level during the test. The average hydraulic conductivity was estimated to be 2×10^{-3} m/s. This value is typical of a clean sand deposit (Freeze and Cherry, 1979), and indicates a relatively high permeability.

Table 2
HYDRAULIC CONDUCTIVITY OF THE SAND AQUIFER

Location	Hydraulic Conductivity (m/s)	Method of Calculation
MWN3A	9×10^{-5}	Slug Test ¹
MWN1B	2×10^{-4}	Slug Test ¹
MWS2	8×10^{-4}	Slug Test ¹
MWN2A	3×10^{-4}	Slug Test ¹
BHS4 (2.5-3.0 m)	1×10^{-2}	Hazen ²
MWS1 (1.7-2.2 m)	4×10^{-3}	Hazen ²
BHS9 (4.0-4.5 m)	1×10^{-2}	Hazen ²
Area of Municipal Wells	2.2×10^{-3}	Pumping Tests ³
<p>NOTES:</p> <p>¹See Appendix D. Analysis by the method of Bouwer and Rice, 1976</p> <p>²See Appendix G. Analysis by the method of Hazen (Freeze and Cherry, 1979).</p> <p>³From Geo-Environ Ltd, 1978; Geo-Environ Ltd, 1983; and Morrison Beatty Ltd., 1981.</p>		

Because the sand aquifer has a high permeability, groundwater can move relatively quickly through this aquifer if a significant hydraulic gradient exists. However, as discussed above, the vertical and horizontal hydraulic gradients across the site are very small. This means that, under the observed water level conditions, only slow groundwater movement is occurring across the site. However, increased pumping of the municipal wells could induce groundwater movement from the site area to the wells.

3.3.3 GROUNDWATER FLOW BETWEEN THE SITE AND THE MUNICIPAL WELLS

The water table elevation at well TW5-78, close to the municipal wells, was measured several times on August 30, 1990. The water level in this well fluctuated in response to pumping of the municipal wells. When the municipal wells were not operating, the water level elevation rose to 95.72 m above reference. About two minutes after Well

#1 began pumping (at approximately 20 L/s), the water level in TW5-78 had dropped by 0.42 m.

Based on these measurements, when the municipal wells are not pumping, normal groundwater flow in the study area appears to be in a northeast direction, ie. from the area of the municipal wells to the area of the plant site and the lake. However, when either municipal well is pumping, this flow direction is reversed, at least in the vicinity of the municipal wells.

The low horizontal hydraulic gradients underneath the former plant site make it difficult to determine the direction of groundwater flow underneath the site. In August 1990, the flow of groundwater under the site was very slow. However, the sand aquifer has a high permeability. This means that if the hydraulic gradient toward the pumping wells was increased, (for instance by an increase in pumpage or a decrease in precipitation), there is the potential that significant groundwater flow from the site to the wells will result.

The observed groundwater flow patterns in the study area may change with changes in precipitation, river stage, or pumping rates of the municipal wells. It is pertinent to note that conditions in August 1990, (low precipitation, high pumping rates) would result in a larger drawdown cone around the municipal wells than would occur at other periods during the year. Nevertheless, regular monitoring of the water levels in onsite and offsite wells, and in the lake, would help to confirm the direction of groundwater flow in the vicinity of the site.

Section 4

EXTENT OF CONTAMINATION

4.1 FOREST LAKE

4.1.1 LAKE SEDIMENT

Significant areas of the lake bottom adjacent to the site were found to be covered in tar. The extent of visually identified tar contamination in Forest Lake is shown in Figure 7. There were no visually identified areas of ongoing tar seepage into the lake.

The physical appearance of the tar, and its location overlying the lake bottom sediments, suggests that the tar was deposited in the lake by overland transport. There was no visible evidence that tar had entered the lake via upward movement through the lake sediments.

The tar on the surface of the lake bottom occurred as a stiff to crumbly "crust", up to 5 cm in thickness. In the central part of the tar-contaminated area, a fluid, sticky tar was also present underneath the tar "crust". The fluid tar, up to 10 cm in depth, was moderately viscous and more dense than water. Both types of tar were dark brown in colour and had a strong "wood smoke" odour.

Outside the tar-covered area, most lake-sediment samples were classified as exhibiting traces of contamination ("TC"). The sediment often contained cinders and usually had a distinct wood smoke odour.

The results of chemical analyses of selected lake-sediment samples are presented in Appendix E and summarized in Table 3. The field classification of samples (NC, TC, or VC) was compared to the results of chemical analysis. The comparison can be summarized as follows:

"VC" samples:	high concentrations of PAHs, similar to or greater than PAH concentrations in tar samples.
"TC" samples:	most samples show significant levels of PAHs.
"NC" samples:	similar level of PAH contamination to TC samples.

None of the lake sediment samples contained detectable levels of phenolic compounds. Phenolics have moderately high solubilities in water and were likely leached out of the lake sediment samples by the lake water.

The lake sediment core sample (1+60 core), collected from 5 to 10 cm below the sediment surface, is not significantly contaminated with PAHs.

Table 3 SUMMARY OF COMPOUNDS FOUND IN LAKE SEDIMENT SAMPLES (ppb)										Page 1 of 3	
Sample	0+00	0+40	1+20	1+60	2+00	2+40	2+80	Lab Blank	Defect Limit *		
Field Classification	NC	TC	TC	core TC	TC	VC	VC				
Compound											
Phenolics (Coal Tar Acids)											
Phenol	<	<	<	<	<	<	<	<	8.0		
o-Cresol	<	<	<	<	<	<	<	<	8.0		
m-Cresol	<	<	<	<	<	<	<	<	8.0		
p-Cresol	<	<	<	<	<	<	<	<	8.0		
2,6-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
2,5-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
2,4-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
3,5-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
2,3-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
3,4-Dimethyl phenol	<	<	<	<	<	<	<	<	8.0		
Resorcinol	<	<	<	<	<	<	<	<	8.0		
PAHs											
Naphthalene	194	248	10.2	17.6	776	39000	59100	<	24.0		
Acenaphthylene	67.2	<	7.7	<	66.0	13400	<	<	9.6		
Acenaphthene	45.1	<	<	15.5	139	16300	23800	<	9.6		
Fluorene	127	70.6	5.6	22.4	285	68500	97100	<	9.6		
Phenanthrene	362	134	36.0	10.3	842	50100	70700	<	3.2		
Anthracene	94	30.8	9.90	<	165	24800	6790	<	4.8		
Fluoranthene	536	117	78.4	13.6	975	14900	20000	<	8.0		
Pyrene	672	127	89.9	<	1060	28100	37800	<	8.3		

Table 3 SUMMARY OF COMPOUNDS FOUND IN LAKE SEDIMENT SAMPLES (ppb)										Page 2 of 3
Sample	0+00	0+40	1+20	1+60	2+00	2+40	2+80	Lab Blank	Detect. Limit*	
Benzo(a)anthracene	256	38.4	40.8	<	399	<	10300	<	33.6	
Chrysene	281	47.5	42.4	<	405	<	11100	<	33.6	
Benzo(b)fluoranthene	280	35.8	43.5	<	370	<	<	<	22.4	
Benzo(k)fluoranthene	225	25.6	34.8	<	265	<	<	<	22.4	
Benzo(a)pyrene	214	25.1	35.5	<	319	<	4800	<	19.2	
Indeno(1,2,3-cd)pyrene	258	24.7	37.1	<	292	<	<	<	24.0	
Dibenz(ah)anthracene	35.9	<	<	<	19.7	<	<	<	19.2	
Benzo(ghi)perylene	234	19.5	29.3	<	224	<	<	<	19.2	
Total PAHs	3881	944	501	79	6602	255100	341940			
BNA (Including PAH repeats)										
Naphthalene	193	290	7.16	18.1	687	39800	70100	<	1.6	
Acenaphthylene	70.9	<	5.52	<	50.8	9250	<	<	3.2	
Acenaphthene	63.2	<	<	14.0	163	20900	31600	<	3.2	
Fluorene	190	112	7.90	31.5	425	132000	207000	<	3.2	
Phenanthrene	430	164	40.5	10.2	993	68800	98500	<	1.6	
Anthracene	96.2	29.6	7.62	<	156	30700	46800	<	1.6	
Fluoranthene	519	92.3	71.3	5.73	924	16200	21200	<	1.6	
Pyrene	557	107	74.7	10.3	850	24500	32600	<	1.6	
Benzo(a)anthracene	214	33.0	30.2	<	344	<	9100	<	1.6	
Chrysene	253	41.8	32.2	<	377	<	9600	<	17.6	
Benzo(b)fluoranthene	277	35.2	40.2	<	381	<	<	<	3.2	
Benzo(k)fluoranthene	238	27.1	38.8	<	306	<	<	<	1.6	
Benzo(a)pyrene	195	25.4	34.1	<	336	<	7040	<	1.6	

Table 3

SUMMARY OF COMPOUNDS FOUND IN LAKE SEDIMENT SAMPLES (ppb)

Page 3 of 3

Sample	0+00	0+40	1+20	1+60	2+00	2+40	2+80	Lab Blank	Detect. Limit*
Indeno(1,2,3-cd)pyrene	237	218	407	<	305	<	<	<	1.6
Dibenz(a,h)anthracene	319	<	<	<	316	<	<	<	1.6
Benzo(a)perylene	305	36.3	33.5	<	323	<	<	<	1.6
Camphene	<	<	<	118	<	<	<	<	368
2-methylnaphthalene	353	437	107	13.2	1140	156000	24900	<	3.2
1-methylnaphthalene	215	227	882	13.2	908	110000	17400	<	3.2
Biphenyl	100	166	<	7.51	149	23000	35200	<	3.2
Benzybutylphthalate	568	44.5	72.4	35.7	26.6	4750	<	<	3.2
Di-n-butylphthalate	88.3	113	95.9	79.7	81.4	<	1650	0.26	3.2
Perylene	82.2	9.18	12.2	296	123	<	<	<	1.6

* The following samples have higher detection limits:

2+40 184 x higher

2+80 60 x higher

Concentrations in ppb

N/A not analyzed

All laboratory analysis of compounds in the lake sediment samples are reported on a "wet-weight" basis. Regulatory guidelines are reported on a "dry-weight" bases. As a result, there is a slight underestimation of the compound concentrations with respect to guidelines. For example, assuming a soil moisture content of 20 percent by weight, "wet-weight" concentrations must be multiplied by 1.25 to give the equivalent "dry-weight" concentration. These discrepancies in concentration units are not expected to be significant when compared to the uncertainties associated with the sediment sampling process. No adjustment has been made to convert "wet-weight" to "dry-weight" measurements.

There are few regulatory guidelines for acceptable concentrations of PAHs in lake sediments. The Great Lakes Science Advisory Board has developed a guideline maximum concentration of benzo(a)pyrene in lake sediment of 1000 ppb, (CCME, 1989). One lake sediment sample (2+80) exceeds this guideline. The MOE adopted a site-specific guideline for a site near Port Stanley, Ontario, for total PAH in creek sediment (CANVIRO Consultants, 1988). A total PAH concentration of 35,000 ppb was used to delineate sediment requiring remediation. Two samples (2+40 and 2+80) contained total PAH concentrations which exceeded this guideline.

The draft Ontario Provincial Sediment Quality Guidelines (SQG) list a Lowest Effect Level (LEL) and Severe Effect Level (SEL) for total PAH in sediments (Persaud et al, 1990). The SEL is given as 11,000 μg per g of organic carbon. Assuming a total organic carbon (TOC) concentration in the sediments of 5 percent, the SEL is 550,000 ppb. Samples 2+40 and 2+80 contain total PAHs at levels close to this value. Given the uncertainty in the sediment TOC, these samples are considered to be at the SEL. The LEL is given as 2,000 ppb. Samples 0+00, 2+00, 2+40, and 2+80 contain total PAHs which exceed the LEL. According to the SQG, the sampled sediments will impair sediment use by benthic organisms, and are slightly to highly contaminated.

According to the above, lake sediment in the immediate area of the visible tar contamination in Forest Lake is significantly contaminated with PAHs.

4.1.2 LAKE WATER

Lake water samples were collected at two locations: off-shore near MWN1 (location #1), and off-shore near MWS1 (location #2). These locations are shown on Figure 3. The analyses of these samples are given in Table 4.

No significant contamination of the lake water was detected. No parameter was measured at concentrations exceeding drinking water criteria (Table 4). Trace levels of Cresols and Dimethyl phenols were detected in one sample. There are no applicable drinking water criteria for these compounds. Parameters analyzed were PAHs, Phenolics, and BNA compounds (see Appendix E).

Table 4 SUMMARY OF COMPOUNDS DETECTED IN GROUNDWATER AND SURFACE WATER SAMPLES (ppb)														Page 1 of 2
Compound	MWN1A	MWN1B	MWN2A	MWN2B	MWN3A	MWS1 Repeat	MWS2 Repeat	Forest Lake #1	Forest Lake #2	Munic. Well #2	Travel Blank	Lab Blank	DeL Limit*	Water Quality Notes
BTXE														
Benzene	215	<	<	<	<	<	<	<	<	<	<	<	0.4	5 a
Toluene	570	<	<	<	<	<	<	<	<	<	<	<	0.7	24 b
m&p Xylene	330	<	<	<	<	<	<	<	<	<	<	<	0.6	300 h'
Ethyl benzene	210	<	<	<	<	<	<	<	<	<	<	<	2.6	2.4 b
o Xylene	155	0.5	<	<	<	<	<	<	<	<	<	<	0.4	300 h'
Phenolics (Coal Tar Acids)														
Phenol	638	0.35	0.53	0.68	0.29	0.20	0.23	0.38	0.26	0.21	0.22	<	0.07	2 c"
o-Cresol	1820	0.62	0.07	0.33	<	<	<	0.14	<	<	<	<	0.07	2 c"
m-Cresol	(2000)	0.14	<	0.42	<	<	<	0.28	<	<	<	<	0.07	2 c"
p-Cresol	(3700)	0.19	0.12	0.28	<	<	<	0.14	<	<	<	<	0.07	2 c"
2,6 Dimethyl phenol	5520	1.47	<	<	<	<	<	<	<	<	<	<	0.07	2 c"
2,5 Dimethyl phenol	3420	<	<	0.11	<	<	<	0.09	<	<	<	<	0.07	2 c"
2,4 Dimethyl phenol	5750	<	<	0.11	<	<	<	0.11	<	<	<	<	0.07	2 c"
3,5 Dimethyl phenol	4360	2.54	<	0.16	<	<	<	0.25	0.53	<	<	<	0.07	2 c"
2,3 Dimethyl phenol	1450	<	<	<	<	<	<	<	<	<	<	<	0.07	2 c"
3,4 Dimethyl phenol	1180	<	<	0.08	<	<	<	<	<	<	<	<	0.07	2 c"
Resorcinol	199	<	<	<	<	<	<	<	<	<	<	<	0.07	2 c"
PAHs														
Naphthalene	10.5	4.14	0.039	0.035	0.030	<	0.038	0.060	<	0.032	0.078	<	0.015	0.2 d
Acenaphthene	<	0.32	<	<	<	<	<	<	<	<	<	<	0.006	20 c
Fluorene	<	0.38	<	<	<	<	<	<	<	<	<	<	0.006	
Fluoranthene	<	<	<	<	<	<	<	0.008	0.010	<	<	<	0.005	0.1 f
Pyrene	<	<	<	<	<	<	<	0.008	0.010	<	<	<	0.005	0.2 d

Table 4

SUMMARY OF COMPOUNDS DETECTED IN GROUNDWATER AND SURFACE WATER SAMPLES (ppb)

Page 2 of 2

Compound	MWN1A	MWN1B	MWN2A	MWN2B	MWN3A	MWS1	MWS1 Repeat	MWS2 Repeat	Forest Lake #1	Forest Lake #2	Munic. Well #2	Travel Blank	Lab Blank	DCL Limit*	Water Quality Notes
BNA (including PAH repeats)															
Naphthalene	10.6	3.56	<	<	<	<	<	<	<	<	<	<	<	0.01	0.2 d
Acenaphthene	<	0.25	<	<	<	<	<	<	<	<	<	<	<	0.02	20 c
Fluorene	<	0.44	<	<	<	<	<	<	<	<	<	<	<	0.02	
Fluoranthene	<	<	<	<	<	<	<	<	<	<	<	<	<	0.01	0.1 f
Pyrene	<	<	<	<	<	<	<	<	<	<	<	<	<	0.01	0.2 d
Phenol	1470	0.49	8.45	0.92	0.58	0.31	0.31	0.86	0.67	0.52	0.44	0.34	<	0.06	2 c*
2,4-Dimethylphenol (18000)		2.00	0.44	0.56	<	<	<	<	0.73	<	<	<	<	0.08	2 c*
2-Methylnaphthalene	3.05	<	0.03	0.02	<	<	<	<	0.02	<	<	<	<	0.02	
1-Methylnaphthalene	2.55	1.88	<	<	<	<	<	<	<	<	<	<	<	0.02	
Total Diphenylamine	<	0.04	0.14	0.04	<	<	<	<	<	<	<	<	<	0.02	
Biphenyl	<	0.64	<	<	<	<	<	<	<	<	<	<	<	0.02	
Benzylbutylphthalate	<	0.93	1.16	1.05	0.48	0.67	0.44	0.49	0.23	0.30	0.12	0.33	<	0.02	
Di-n-butylphthalate	9.77	0.38	0.43	0.28	0.26	0.47	0.29	0.23	0.51	0.66	0.47	0.21	0.26	0.02	

* Detection limit for MWN1A is 100x higher

All concentrations in ppb

Water Quality Limits:

- a - Health and Welfare Canada (1987), Maximum Allowable Concentration
- b - Health and Welfare Canada (1987), Aesthetic Objective
- c - Ontario Ministry of the Environment (1984), Maximum Desirable Concentration
- d - CCME; (1989), Guideline A
- e - USEPA Ambient Water Quality Criteria (CCME, 1989)
- f - Quebec criteria A (CCME, 1989)

NOTES:

* - limit applies to total xylenes

" - limit applies to total phenols

Small areas of surface tar contamination were identified over the central portion of the site. These areas are shown on Figure 7. This tar had a stiff, sticky to crumbly consistency, a dark brown colour, and a strong "wood smoke" odour. The tar was typically found from ground surface to depths of up to 5 cm below ground surface.

Of the eleven boreholes drilled onsite, only three boreholes encountered subsurface material which appeared contaminated. The locations of the boreholes are shown on Figure 7. These were:

- | | |
|-------|--|
| MWN1A | Located in the area of the former tar pond (See Figure 3). At a depth of 17 m below surface, the sand had a strong odour. |
| BHS7 | Located northeast of the former oven house (See Figure 2). At a depth of 3.5 m below surface, there were streaks of black sand and a distinct odour. |
| BHS11 | Located west of the former holding tank house (Figure 2), in the centre of the site. At a depth of 2 m to greater than 4 m below surface, the sand had a strong odour. |

The results of chemical analyses of selected soil samples are presented in Table 5. The results were compared to the field classification of samples. This comparison can be summarized as follows:

"TC/VC" samples:

PAH contamination is present. Several PAH compounds are found at concentrations which exceed CCME criteria A, indicating that the soil is "slightly contaminated" (Appendix H). No PAH compounds exceed CCME criteria B. No Phenolic compounds were detected.

"NC" samples:

PAH compounds were detected only at "background" levels. No PAH compound was found at concentrations exceeding CCME criteria A, and the samples can be considered uncontaminated. No Phenolic compounds were detected.

Soil contamination delineated during the drilling program was limited to the central area of the plant site, close to the former tar pit and the oven house/holding tank house buildings. Evidence of contamination in the subsurface was limited to strong odours. None of the boreholes onsite intersected soil which contained free-phase oil or tar.

Table 5 SUMMARY OF COMPOUNDS DETECTED IN SOIL SAMPLES (ppb)									Page 1 of 3
Sample	BHS6 (3.5m)	BHS7 (2m)	BHS11 (3.5m)	MWN3B (5m)	MWN3A (17m)	Lab Blank	Detect. Limf	Conc. Limf	
Field Classification	NC	TC	TC/VC	NC	NC				
Compound*									
PAHs									
Naphthalene	<	234	82.8	<	<	<	24	50,000 a	
Acenaphthylene	<	54.8	19.6	<	<	<	9.6		
Acenaphthene	<	74.1	11.4	<	<	<	9.6		
Fluorene	<	288	21.8	<	<	<	9.6		
Phenanthrene	7.18	456	119	12.0	12.6	<	3.2	50,000 a	
Anthracene	<	156	23.1	<	<	<	4.8		
Fluoranthene	<	300	118	<	<	<	8.0		
Pyrene	18.5	498	151	27.3	32.8	<	8.3	100,000 a	
Benzo(a)anthracene	<	176	53.9	<	<	<	33.6	10,000 a	
Chrysene	<	208	66.1	<	<	<	33.6		
Benzo(b)fluoranthene	<	189	70.0	<	<	<	22.4	10,000 a	
Benzo(k)fluoranthene	<	115	51.7	<	<	<	22.4	10,000 a	
Benzo(a)pyrene	<	148	44.0	<	<	<	19.2	10,000 a	
Indeno(1,2,3-cd)pyrene	<	183	54.4	<	<	<	24.0	10,000 a	
Dibenzo(a,h)anthracene	<	25.3	<	<	<	<	19.2	10,000 a	
Benzo(ghi)perylene	<	173	50.4	<	<	<	19.2		
BNA (including PAH repeats)									
Naphthalene	<	200	87.5	<	<	<	1.6	50,000 a	
Acenaphthylene	<	33.3	9.55	<	<	<	3.2		
Acenaphthene	<	83.2	11.6	<	<	<	3.2		

Table 5 SUMMARY OF COMPOUNDS DETECTED IN SOIL SAMPLES (ppb)										Page 2 of 3
Sample	BHS6 (3.5m)**	BHS7 (2m)	BHS11 (3.5m)	MWN3B (5m)	MWN3A (17m)	Lab Blank	Detect Limit	Conc. Limit		
Field Classification	NC	TC	TC/VC	NC	NC					
Compound*										
Fluorene	<	388	20.0	<	<	<	3.2			
Phenanthrene	5.06	481	122	9.50	15.2	<	1.6	50,000 a		
Anthracene	<	148	16.4	<	<	<	1.6			
Fluoranthene	<	268	100	<	<	<	1.6			
Pyrene	12.4	376	108	23.1	28.0	<	1.6	100,000 a		
Benzo(a)anthracene	<	143	42.7	<	<	<	1.6	10,000 a		
Chrysene	<	173	57.4	<	<	<	17.6			
Benzo(b)fluoranthene	<	149	60.6	<	<	<	3.2	10,000 a		
Benzo(k)fluoranthene	<	123	58.3	<	<	<	1.6	10,000 a		
Benzo(a)pyrene	<	129	38.0	<	<	<	1.6	10,000 a		
Indeno(1,2,3-cd)pyrene	<	132	43.0	<	<	<	1.6	10,000 a		
Dibenzo(ah)anthracene	<	30.8	<	<	<	<	1.6	10,000 a		
Benzo(ghi)perylene	<	180	54.4	<	<	<	1.6			
2-Methylnaphthalene	<	1520	134	<	<	<	3.2			
1-Methylnaphthalene	<	693	105	<	<	<	3.2			
Biphenyl	<	139	16.4	<	<	<	3.2			
Benzybutylphthalate	28.6	69.7	30.9	15.9	50.4	<	3.2			
Di-n-butylphthalate	43.3	115	49.2	45.5	59.3	0.26	3.2			
Perylene	<	42.4	11.5	<	<	<	1.6			
Phenolics (Cool Tar Acids)										
o-cresol	<	<	<	<	<	<	8.0			

Table 5
SUMMARY OF COMPOUNDS DETECTED IN SOIL SAMPLES (ppb)

Sample	BHS6 (3.5m)	BHS7 (2m)	BHS11 (3.5m)	MWNA3B (5m)	MWNA3A (17m)	Lab Blank	Detect. Limit	Conc. Limit
Field Classification	NC	TC	TC/VC	NC	NC			
Compound*								
m-cresol	<	<	<	<	<	<	8.0	
p-cresol	<	<	<	<	<	<	8.0	
2,6-Dimethyl phenol	<	<	<	<	<	<	8.0	
2,5-Dimethyl phenol	<	<	<	<	<	<	8.0	
2,4-Dimethyl phenol	<	<	<	<	<	<	8.0	
3,5-Dimethyl phenol	<	<	<	<	<	<	8.0	
2,3-Dimethyl phenol	<	<	<	<	<	<	8.0	
3,4-Dimethyl phenol	<	<	<	<	<	<	8.0	
Resorcinol	<	<	<	<	<	<	8.0	

*all concentrations in ppb
depth below ground surface

Concentration Limits:
a - CCME; (1989) Value C (Level at which contamination is significant)

Examination of air photographs, the onsite reconnaissance survey, and the drilling/soil sampling program did not locate any disposal areas onsite where contaminated soil, excavated from the former pond, was buried in the subsurface. However, information made available by the MOE subsequent to the field investigations suggested that the disposal area may have been located in the western part of the property (i.e. west or southwest of BH56, Figure 3), outside the area of the preliminary site investigation. Further field investigation was conducted and the results are described in an addendum to this report (Section 7).

In the area of MWN1, near the former tar pit location, contamination appeared at depth. Examination of the cross-section (Figure 6) shows that the contaminated soil is probably located very close to the bottom of the sand aquifer. Flowing sand conditions prevented the installation of deeper boreholes in this location, so the exact location of the interface between the sand aquifer and the underlying clayey sand unit could not be confirmed.

It is possible that dense liquid tar and related products have moved downward through the sand aquifer in the area of the former tar pit. There may be liquid tar pooling at the bottom of the aquifer in this location. This tar pool may have migrated horizontally a short distance by gravity flow along the base of the sand aquifer. This could explain why MWN1 encountered soil contamination only at depth.

Alternatively, it is possible that contamination in the area of the former tar pond is only present as dissolved, or aqueous-phase, contamination in the groundwater and contamination adsorbed on to the soil particles.

Two soil samples from MWN3, taken from 5 m and 17 m below ground surface, were submitted for chemical analysis. There was no significant difference in PAH or Phenolics content between the two samples (Table 5). These results indicate that, at this location, there is no variation in PAH and Phenolic contamination with depth.

4.3 GROUNDWATER

4.3.1 MUNICIPAL WELLS

Municipal Well #2 was sampled on August 16, 1990. The results of chemical analysis are given in Table 4. Parameters analyzed were PAHs, Phenolics, BTXE, and Base/Neutral/Acid Extractable Compounds (BNA) (see Appendix H).

Low concentrations (below applicable drinking water standards) of Phenol, Naphthalene, Benzybutylphthalate and Di-n-Butylphthalate were detected in the sample from Well #2. However, these compounds were also detected in the travel blank sample. The detection of these compounds does not conclusively indicate their presence in the groundwater taken from Well #2.

4.3.2 ONSITE MONITOR WELLS

Samples of groundwater from all wells except MWN3B and MWS3 were submitted for chemical analysis. The results are presented in Table 4, and can be summarized as follows:

- MWN1A Located in the area of the former tar pond, at a depth of about 18 m below ground surface. Groundwater at this location was contaminated with PAHs, Phenolics, and BTXE. Benzene was found at levels over the Canadian Maximum Acceptable Concentrations for drinking water (MAC). Toluene and xylenes exceeded Canadian Aesthetic Objectives for drinking water (AO). Total phenols exceeded MOE Maximum Desirable Concentration for drinking water (MDC). Naphthalene exceeds CCME guidelines A and B. In addition, water from this well had a strong chemical odour, and the water foamed as it came into contact with the atmosphere. Two weeks after well purging, foam was still present on the water surface in the well.
- MWN1B Located in the area of the former tar pond, at a depth of about 8 m below ground surface. Groundwater at this location contained detectable levels of xylene, PAHs, and Phenolics. Only naphthalene and total phenols were found in concentrations exceeding guidelines (CCME guideline A and MOE, MDC, respectively). Water from this well had a distinct odour, and the water foamed as it came into contact with the atmosphere.
- MWN2A Located in the central area of the site, south of the former oven house/acetate storage house, at a depth of about 18 m below surface. All measured parameters except total phenols were detected at concentrations below the applicable drinking water standards. Repeat analyses of phenol gave concentrations of 0.5 and 8 ppb. 8 ppb exceeds the Ontario MDC of 2 ppb for phenols. The poor repeatability of the analyses means there is considerable uncertainty in the phenol concentration at this location.
- MWN2B Located in the central area of the site, south of the former oven house/acetate storage house, at a depth of about 8 m below surface. All measured parameters except total phenols were detected at concentrations below the applicable drinking water standards. Total phenolics were found to exceed the MOE, MDC of 2 ppb.
- MWN3A, MWS1, MWS2 Water samples from these wells were uncontaminated. No significant levels of PAHs, Phenolics or BTXE were measured.

Groundwater in the area of the former tar pond was found to be contaminated. The areal extent of groundwater contamination appears to be quite limited since wells only 100 to 150 m away from MWN1 produce uncontaminated water. Nevertheless, it is important to note that high levels of contamination are present in the water supply aquifer, and this contamination is only 300 m from the municipal wells.

In the tar pond area, groundwater contamination appears to be more severe at depth in the aquifer. As was discussed in Section 4.2, this pattern of contamination at depth may be caused by the presence of pools of liquid tar existing at the base of the aquifer.

4.4 CHEMICAL CHARACTERIZATION OF WOOD TAR FOUND ONSITE

Wood tar was found onsite, both on the ground surface and on the lake bottom adjacent to the former plant property. Three samples of tar were collected and submitted for chemical analysis: tar from ground surface near MWN1, tar "crust" from the lake bottom, and liquid tar from the lake bottom. The results are presented in Appendix E and summarized in Table 6.

Tar samples were dark brown in colour, sticky, denser than water, and were viscous to solid. They had a very strong odour.

In general, the tar is characterized by high levels of PAHs, BTXE and certain other volatile organic chemicals, and phenolic compounds. The phenolic compounds, which are relatively water-soluble, appear to be leached out of the tar collected from the lake bottom.

The tar samples have high concentrations of some volatile organic chemicals (BTXE, methylene chloride, methyl ethyl ketone, and chloroform). These chemicals are found in concentrations of approximately 1000 to 30000 ppb. These compounds are common constituents of solvents and cleaning agents, which likely was their source.

The tar samples also contain high concentrations of PAHs. In the "fluid" tar collected from the lake bottom, PAHs are found in concentrations of approximately 1000 to 10000 ppb. These levels exceed the CCME Guideline B for soil samples (Appendix H). In the tar "crust" collected from the lake bottom, and in the tar from ground surface, PAHs are found in concentrations of approximately 2000 to 40000 ppb. These concentrations exceed the CCME criteria B and in many cases, the CCME criteria C for soil samples. This signifies that the tar samples have a high level of contamination (see Appendix H).

The tar sample collected from ground surface contained high levels of phenolic compounds. The concentration of phenolics ranged from about 50000 to 1350000 ppb (50 to 1350 ppm). The tar samples collected from the lake bottom had lower or non-detectable levels of phenolics. This is presumably due to dissolution of the relatively water-soluble phenolic compounds.

Table 6 SUMMARY OF COMPOUNDS DETECTED IN TAR SAMPLES (ppb)					Page 1 of 3
Compounds	Tar on Ground Surface near MW1	Tar on Lake Bottom near 2+40 (tar "crust")	Tar on Lake Bottom near 3+60 (fluid tar)	Lab. Blank	Detect. Limit *
VOCs					
Methylene Chloride	3360	N/A	3300	<	1.8
Methyl Ethyl Ketone	7260	N/A	4700	<	1.1
Chloroform	1620	N/A	1750	1.2	0.4
Benzene	3380	N/A	<	<	0.4
Toluene	25800	N/A	1060	<	0.7
m&p Xylene	28750	N/A	5130	<	0.6
o Xylene	22700	N/A	2880	<	0.4
Ethyl Benzene	17450	N/A	2100	<	2.6
Phenols (Cool Tar Acids)					
Phenol	278000	<	<	N/A	8.0
o-Cresol	214000	<	<	N/A	8.0
m-Cresol	414000	<	<	N/A	8.0
p-Cresol	385000	<	<	N/A	8.0
2,5-Dimethyl phenol	75300	<	<	N/A	8.0
2,4-Dimethyl phenol	110000	<	<	N/A	8.0
3,5-Dimethyl phenol	45700	<	614	N/A	8.0
3,4-Dimethyl phenol	99100	<	855	N/A	8.0
Resorcinol	64600	<	<	N/A	8.0
PAHs					
Naphthalene	22300	40000	8840	<	24
Acenaphthylene	<	14300	1740	<	9.6
Acenaphthene	<	17200	2530	<	9.6

Table 6 SUMMARY OF COMPOUNDS DETECTED IN TAR SAMPLES (ppb)						Page 2 of 3
Compounds	Tar on Ground Surface near MW/1	Tar on Lake Bottom near 2+40 (tar "crust")	Tar on Lake Bottom near 3+60 (fluid tar)	Lab. Blank	Detect Limit *	
Fluorene	34000	72200	8280	<	9.6	
Phenanthrene	<	57000	<	<	3.2	
Anthracene	<	27900	<	<	4.8	
Fluoranthene	5870	17000	<	<	8	
Pyrene	12000	115000	2020	<	8.3	
Benzo(a)anthracene	<	95600	<	<	33.6	
Chrysene	<	8080	<	<	33.6	
Benzo(b)fluoranthene	<	<	<	<	22.4	
Benzo(k)fluoranthene	<	<	<	<	22.4	
Benzo(a)pyrene	<	<	<	<	19.2	
Indeno(1,2,3 cd)pyrene	<	<	<	<	24	
Dibenzo(ah)anthracene	<	<	<	<	19.2	
Benzo(ghi)perylene	<	<	<	<	19.2	
BNA (including PAH repeats)						
Naphthalene	26400	47200	7770	<	1.6	
Acenaphthylene	<	14200	1910	<	3.2	
Acenaphthene	<	24700	3570	<	3.2	
Fluorene	45800	152000	13500	<	3.2	
Phenanthrene	33600	82500	<	<	1.6	
Anthracene	<	37500	<	<	1.6	
Fluoranthene	10500	19000	<	<	1.6	
Pyrene	12200	29000	1530	<	1.6	
Benzo(a)anthracene	<	8000	<	<	1.6	

Table 6
SUMMARY OF COMPOUNDS DETECTED IN TAR SAMPLES (ppb)

Compounds	Tar on Ground Surface near MWNI	Tar on Lake Bottom near 2+40 (for "crust")	Tar on Lake Bottom near 3+60 (fold tar)	Lab. Blank	Detect Limit *
Chrysene	<	9000	<	<	17.6
Benzo(b)fluoranthene	<	<	<	<	3.2
Benzo(k)fluoranthene	<	<	<	<	1.6
Benzo(a)pyrene	<	<	<	<	1.6
Indeno(1,2,3-cd)pyrene	<	<	<	<	1.6
Dibenzo(ah)anthracene	<	<	<	<	1.6
Benzo(ghi)perylene	<	<	<	<	1.6
o-Cresol	1350000	<	<	<	1.6
m-Cresol	1300000	<	<	<	1.6
p-Cresol	1100000	<	<	<	1.6
2-methylnaphthalene	65100	186000	28800	<	3.2
1-methylnaphthalene	47800	13400	19500	<	3.2
Biphenyl	<	26800	37000	<	3.2
Benzybutylphthalate	44200	3700	<	<	3.2
Di-n-butylphthalate	<	<	<	0.26	3.2
Perylene	<	<	<	<	1.6

N/A: not analyzed

All concentration in ppb

* Detection Limits:

Tar on lake bottom near 2+40: 500 x those listed for VOC

Tar on lake bottom near 3+60: 500 x those listed for VOC

Tar on surface near MWNI: 144 x those listed for phenolics and PAH

Tar on lake bottom near 2+40: 112 x those listed for phenolics and PAH

Tar on lake bottom near 3+60: 21 x those listed for phenolics and PAH

Section 5

POTENTIAL IMPACTS OF CONTAMINATION

5.1 IDENTIFICATION OF EXPOSURE PATHWAYS

Three primary exposure pathways for release of the onsite contaminants have been identified. These are:

- i) Groundwater migration to the municipal wells
- ii) Direct contact with contaminated tars, soils, and lake sediments
- iii) Aquatic biota uptake of contaminants from contaminated lake sediments

Each of these pathways is discussed separately in the following sections.

5.2 IMPACT ON MUNICIPAL WELLS

The presence of municipal water supply wells only 300 m from the site has created a concern that onsite groundwater contamination may eventually move towards these wells. From the available field data it is difficult to assess whether the site area presently lies within the capture zone of the municipal wells. The capture zone of a pumping well is defined as the entire recharge area of the well. At any point within the capture zone, groundwater will eventually flow towards the pumping well.


CH2M HILL ENGINEERING LTD. has used a groundwater computer model in order to help determine if groundwater contamination will eventually be drawn towards the municipal wells. Details of the model can be found in Appendix F.

The computer code selected for the model was "Flowpath", developed by Waterloo Hydrogeologic Software. Flowpath simulates a 2-dimensional aquifer in the plan view. The model calculates the distribution of water levels in the aquifer (hydraulic head), and the direction and velocity of groundwater flow in the aquifer. In addition, the model calculates the flow paths of groundwater "particles" placed anywhere within the aquifer.

The aquifer properties which are input into the model are: hydraulic conductivity, porosity, and aquifer thickness. Other input parameters include infiltration from the ground surface and pumping rates of wells.

The model simulation domain is shown in Figure 8. The edges of the aquifer were taken to be: Forest Lake on the northeast and east; the boundary of the bedrock valley on the south and the southwest; and an arbitrary boundary on the west, far from

Figure 8:
Model Simulation Domain and Grid



the site and pumping wells.

The steady-state groundwater flow regime calculated by the model is shown in Figure 9. There is regional groundwater flow in a northerly direction, ie. towards the lake. Superimposed on this regional flow pattern is the effect of the municipal well. A "drawdown cone" is evident around the well, where groundwater flows towards the well.

The 25 year and 50 year capture zones of the well are illustrated in Figures 10 and 11. The 25 year capture zone includes the area of the former plant site. In other words, groundwater from the boundary of the former plant site is calculated to reach the municipal wells in about 25 years. The 50 year capture zone includes the area where contaminated groundwater is known to exist (near the location of the former tar pit). The model calculates that groundwater from this area will reach the municipal wells in approximately 50 years.

The results of the model indicate that, under current conditions, the site area is likely to lie within the capture zone of the municipal wells. However, the model indicates a travel time of 25 to 50 years for groundwater now underneath the site to travel to the municipal wells. The municipal wells have presently been in operation for about 10 years. Model simulations indicate that groundwater underneath the former tar pit area would only travel 50 to 200 m towards the municipal wells in the first 10 years of pumping. This is not inconsistent with the observed limited extent of groundwater contamination underneath the site.

Contaminants in groundwater may not travel at the same velocity as the groundwater itself. The transport of a contaminant may be slowed, or "retarded", by processes such as adsorption to soil, chemical transformations, or biodegradation. The transport rate of a contaminant relative to the groundwater velocity is expressed by **R**, the retardation factor.

Typically, for organic compounds such as PAHs, adsorption to soil is the dominant mechanism affecting the speed at which the compound is transported in groundwater. In this case, **R** can be estimated as follows:

$$R = 1 + (d/n)K_d$$

$$\text{and } K_d = f_{oc} * K_{oc}$$

where

- K_d is the distribution coefficient
- f_{oc} is the fraction of organic carbon in the soil. Analyses of this parameter in two soil samples are presented in Appendix E.
- K_{oc} is the organic carbon partitioning coefficient, a parameter which has been measured for many organic compounds.
- d is the bulk density of the soil
- n is the porosity of the soil

Figure 9:
Model Steady-State Groundwater Flow Solution




Figure 10:
Well Capture Zone: 25 years





Figure 11:
Well Capture Zone: 50 years



Retardation factors for several of the organic contaminants found in waste at the site have been calculated, and are presented in Table 7.

Table 7 CALCULATED RETARDATION FACTORS FOR SELECTED ORGANIC COMPOUNDS			
Compound	log K_{oc}	K_d	R
Phenol	1.23 - 1.43	.006	1.03
Benzene	1.69 - 2.00	.021	1.10
Naphthalene	2.74 - 3.52	0.40	3.0
Benzo(a) pyrene	5.60 - 6.29	264	1321
NOTES: K_{oc} = Organic carbon partitioning coefficient. Values from Montgomery and Welkom. (1990). K_d = Distribution coefficient R = Retardation factor - porosity assumed to be 0.3 - bulk density assumed to be 1.5 - fraction of organic carbon = .0003 (Appendix E)			

Phenol has the lowest retardation factor, at a value of 1.03. This value indicates that phenol will travel at about the same velocity as the groundwater. Benzo(a)pyrene has the highest retardation factor, at a value of 1321. This indicates that benzo(a)pyrene will travel roughly 1300 times slower than the groundwater.

Examination of the retardation factors shows that phenol will probably travel at the same speed as the groundwater, and will likely be transported towards the pumping wells at a greater effective velocity than other, more retarded contaminants. For this reason, all discussion of contaminant transport assumes a transport velocity equal to the speed of groundwater flow, such as would be the case for phenol. It is important to note that contaminated groundwater reaching the municipal wells will be diluted by the uncontaminated groundwater drawn from other parts of the capture zone. For example, the arrival of phenol at the municipal wells will not necessarily correspond to unacceptable levels of phenol in the municipal water supply. It is difficult to estimate if or when unacceptable levels of contamination will occur at the municipal wells. Therefore, the effect of dilution of contaminants at the well has not been considered in the previous discussions. Also, these estimates of contaminant transport velocities do not include the mitigating effect of natural biodegradation of the contaminants in the subsurface. This may result in conservative (i.e. underestimated) predictions regarding the length of time for contaminants to impact the water supply wells.

In summary, groundwater contamination found in the water supply aquifer under the former plant site area is likely to eventually degrade the water quality of the municipal wells. Phenols and other compounds are present in the contaminated groundwater in concentrations exceeding drinking water criteria. Mobil contaminants, such as phenol, are likely to migrate to the municipal wells in 25 to 50 years. Other, less mobile contaminants are expected to arrive at the wells following phenol arrival.

5.3 CONTACT WITH CONTAMINATED SOILS AND SEDIMENTS

A high potential exists for direct human contact with the wood distillation/charcoal plant wastes at the site. There are surface exposures of tar over the central area of the site and tar present on the lake bottom adjacent to the site (Figure 7). There is unrestricted access to the site and to the lake shore via tracks coming from Ottawa Avenue. There is evidence onsite that the area is occasionally used for recreation (camping, motor-bike trails, raspberry picking). Forest Lake is occasionally used for recreational purposes such as canoeing. It should also be noted that the presence of old building foundations and piles of rubble from former buildings may pose a hazard to people travelling over the site area.

Access to the site presents a risk to human health by direct contact with hazardous materials or physical hazards.

5.4 AQUATIC BIOTA UPTAKE OF CONTAMINANTS FROM LAKE SEDIMENTS

The sediments on the lake bottom adjacent to the site are slightly to highly contaminated with PAHs. Chronic exposures to low concentrations of PAHs in water, food, or sediments may produce effects such as: reduced survival, behavioral changes, impaired reproduction, or cancer induction in aquatic organisms (Environmental Research and Technology, 1984).

Concern has been expressed that PAHs may bio-accumulate to toxic levels in aquatic biota. When the aquatic biota enter the food chain this has significance to both human and animal health (NRC, 1983).

Little quantitative data is available on the impact of PAHs on aquatic biota, and there are few regulatory guidelines for PAH levels in lake sediments. However, given the high concentrations of PAHs associated with some of the lake sediment samples, impairment to the aquatic ecosystem in Forest Lake is probable.

Section 6

DISCUSSION OF GENERAL REMEDIAL ACTION ALTERNATIVES

The overall objective of any remedial action is to mitigate health or environmental impacts resulting from the presence of wastes originating from the plant site. Cost-effectiveness of the remedial action is an important factor.

In Section 5 of this report, three primary exposure pathways for release of contaminants were identified. Typical remedial alternatives for each of these cases are discussed in the following sections.

6.1 REMEDICATION OF CONTAMINATED GROUNDWATER

A number of remedial measures to address contaminated groundwater were considered which include the following:

- i) no action
- ii) monitoring of groundwater quality in wells located between the municipal wells and the former tar pit area. Further action to be taken if and when contamination approaches the municipal wells
- iii) "pump and treat" with onsite treatment of groundwater
- iv) "pump and treat" with offsite treatment of groundwater
- v) installation of in situ hydraulic barriers around contaminated groundwater

The "no action" option is not acceptable as human health remains at risk.

Option (ii) is acceptable. This option should include installing new well nests to increase the coverage of the monitor well network. Sampling and chemical analysis of groundwater from the monitor wells should be performed semi-annually.

This alternative will be cost-effective in the short term. However, if contamination is found to be moving toward the municipal wells, the remaining remedial alternatives must be re-evaluated and the costs of remediation may increase greatly. Under present conditions the contaminated groundwater onsite is not expected to impact the municipal wells for a significant length of time, on the order of 25 years. However, any change in groundwater flow patterns, such as increases in pumping rates, could result in contamination reaching the municipal wells in a shorter period of time. Changes in groundwater flow patterns could also result from re-development of the site.

Options (iii) and (iv) are acceptable. However, these options are likely to be relatively expensive. This level of effort may not be necessary as contaminated groundwater does not appear to currently be moving offsite at a significant rate.

Option (v) is not acceptable at this time. Conventional hydraulic barriers, such as sheet piling or injected grout curtains, have not been proven to be effective hydraulic barriers in high permeability materials such as the sand aquifer below the study area. Other conventional methods, such as slurry walls, are likely to cause a significant disruption of onsite groundwater flow during installation procedures. This may lead to offsite migration of groundwater contamination. Given the uncertainties associated with hydraulic barrier technology at this time, this option may not eliminate risk to human health and, therefore, is unacceptable. New technologies in hydraulic containment may be available in the future. If a re-evaluation of groundwater remedial strategies is done in the future, option (v) should also be re-evaluated.

6.2 REMEDIAL ACTION OF CONTAMINATED SOIL

According to CCME guidelines (Appendix H), remedial action need only be considered for the tar-contaminated areas on the ground surface. The remedial measures considered include the following:

- i) no action
- ii) cover exposed tar-contaminated areas with soil and grass
- iii) excavation and burial of tar-contaminated soil onsite
- iv) excavation and removal of tar-contaminated soil
- v) excavation and onsite treatment of tar-contaminated soil

The "no action" option is not acceptable as human health remains at risk.

Option (ii) and (iii) are acceptable. This option would prevent direct contact with contaminated soil and tar, but will likely cause continued or further contamination of groundwater. This option must be considered in conjunction with an appropriate groundwater remediation scheme. In the case of onsite burial, pits lined with clay and/or synthetic liners may be appropriate. These liners may decrease the amount of groundwater contamination resulting from waste burial. However, these liners are unlikely to eliminate further groundwater contamination.

Option (iv) is acceptable. Although the amount of contaminated soil and tar is relatively small, this option is likely to be expensive. Contaminated materials must be shipped to a treatment disposal facility. Correct protocols must be observed for the transport, treatment and disposal of hazardous waste.

Option (v) is acceptable. Several methods of onsite treatment may be appropriate, including bio-remediation (i.e. land farming) or portable slurry bio-reactors. The waste residue may be disposed onsite or in a municipal waste facility, depending on the degree of success of the treatment. The cost-effectiveness of this option will vary with the treatment technology selected. The scope of this report does not include an investigation of onsite treatment technologies. This option must include a feasibility study to select an appropriate technology.

6.3 REMEDIATION OF CONTAMINATED LAKE SEDIMENTS

A significant amount of tar is present on the lake bottom near shore. The sediments on the lake bottom adjacent to the site are highly contaminated with PAHs. Regulatory guidelines (outlined in Section 4.1.1) indicate that remedial action may be required for lake sediments in the immediate area of visual tar contamination on the lake bottom. The remedial actions which were considered included:

- i) no action
- ii) excavation of contaminated material and burial onsite
- iii) excavation, removal and disposal of contaminated material
- iv) excavation and onsite treatment of contaminated material

The "no action" alternative (i) is not acceptable. Human health remains at risk because there is a significant possibility that persons using Forest Lake for recreational purposes may come into contact with tar on the lake bottom. As well, there may be adverse impacts on aquatic biota.

Option (ii) is acceptable. This option would prevent direct contact with contaminated sediments and tar, but will likely cause further contamination of groundwater. Burial in pits lined with clay or synthetic liners may be appropriate, as discussed in Section 6.2.

Option (iii) is acceptable. However, this option is likely to be expensive. Excavation of materials from the lake is possible as the water depth over the contaminated area is generally less than 1 m. Excavated materials will likely need to be de-watered to some extent before storage and/or transport can occur. Contaminated materials must be shipped to a treatment facility. Correct protocols must be observed for the transport and treatment of hazardous waste.

Option (iv) is acceptable. Possible methods are discussed in Section 6.2. Dewatering of excavated material may not be necessary before treatment, depending on the method of treatment.

Section 7

ADDENDUM: INVESTIGATION OF BURIED TAR POND WASTE

7.1 FIELD INVESTIGATION AND RESULTS

In April 1991, a second field investigation was conducted in the southwest portion of the former South River Wood Distillation/Charcoal plant site, to confirm the location of disposal trenches containing buried tar pond waste.

During a site reconnaissance visit, representatives of CH2M HILL ENGINEERING LTD., and the MOE North Bay office, met with the contractor responsible for the original excavation of the disposal trenches. A shallow test pit program was conducted to confirm the location and nature of the buried tar pond waste.

The disposal trenches were confirmed to be approximately 60 metres northeast of the South River municipal wells. The tar pond waste was buried in 3 parallel trenches, each approximately 6 metres wide and 1 metre deep. The lengths of the trenches ranged from 37 metres to 77 metres. The locations of the trenches are marked on Figures 3 and 7.

The disposal trenches had been excavated into the sand deposit which underlies the entire site. Waste was buried in the unsaturated zone, with the bottom of the disposal trenches located about 2 to 4 metres above the water table.

The tar pond waste had been mixed with sand prior to burial. The buried waste had a distinct odour, and consisted of damp, black-stained sand containing traces of brick fragments, metal pipe, and other construction wastes. Sand immediately underneath the buried waste was not visibly contaminated but had a distinct wood-tar odour. Samples of both the buried waste and of the underlying sand were taken by CH2M HILL.

Sample locations are shown on Figure 3 and samples are described below:

<u>Sample</u>	<u>Description</u>
A	Trench 1; depth 1 m; black-stained sand, strong odour
B	Trench 1; depth 2 m; brown sand, moderate tar odour (taken from below the buried waste)
C	Trench 3; depth 0.5 m; black, hard tar waste, very strong odour
D	Trench 2; depth 1.0 m; black, hard tar waste, very strong odour
E	Trench 2; depth 2.0 m; black sand, tar odour

Samples A, B, D and E were analyzed for PAHs and phenolic compounds (Appendix J) and the results are summarized in Table 8. Sample A, from within trench 1, contained low levels of PAHs at concentrations exceeding CCME guideline A but far below guideline C. Sample B, from below trench 1, shows no significant PAH or phenolic compound contamination.

Samples D and E, from within trench 2, contain significant levels of PAHs and phenolic compounds. In sample E, two parameters approach or exceed CCME guideline C: phenanthrene and naphthalene.

7.2 POTENTIAL IMPACTS OF BURIED WASTE

The primary exposure pathway for release of contaminants from the disposal trenches is through groundwater migration to the municipal wells. However, presently there is no detectable contamination in groundwater samples from the municipal wells.

It is likely that infiltrating precipitation is leaching soluble contaminants from the buried waste and transporting this aqueous-phase contamination to the shallow groundwater. The plume of contaminated groundwater underlying the trenches is likely very limited in vertical extent, i.e. the plume probably extends less than 1 metre vertically downward from the watertable.

The results of the groundwater model (Section 5.2) indicate that, under current conditions, the disposal trenches lie within the two-year capture zone of the municipal wells. However, no contamination had been detected in groundwater samples from the municipal wells. This is true even for relatively mobile contaminants such as phenol and benzene (see Table 4). The most probable explanations for the lack of detectable contamination in the municipal wells are (i) aerobic biodegradation of groundwater contamination prior to reaching the municipal wells, or (ii) dilution of groundwater contamination at the municipal wells. The installation of a groundwater monitor well located between the municipal wells and the disposal trenches (as shown on Figure 7) will confirm the nature of the groundwater quality in the area of the buried tar pond wastes.

Table 8
SUMMARY OF COMPOUNDS DETECTED IN SOIL SAMPLES from Burled Tar Pond Waste (ppb)

Sample Compound	A Trench 1-1 m	B Trench 1-2 m	D Trench 2-4 m	E Trench 2-2 m	Lab Blank	Detect. Limit	Conc. Limit
PAHs							
Naphthalene	417	<	71.34	45900	<	40	50,000 a
Acenaphthylene	<	<	<	<	<	80	
Acenaphthene	<	<	<	<	<	80	
Fluorene	<	<	40.20	18,200	<	80	
Phenanthrene	400	<	28400	85,200	<	40	50,000 a
Anthracene	414	<	1,3000	49000	<	40	
Fluoranthene	141	<	4840	4670	<	40	
Pyrene	274	<	8130	1220	<	40	100,000 a
Benzo(a)anthracene	67.6	<	1990	5420	<	40	10,000 a
Chrysene	<	<	1750	5060	<	440	
Benzo(b)fluoranthene	<	<	2230	<	<	80	10,000 a
Benzo(k)fluoranthene	<	<	**	<	<	40	10,000 a
Benzo(a)pyrene	<	<	1340	<	<	40	10,000 a
Indeno(1,2,3 cd)pyrene	<	<	<	<	<	40	10,000 a
Dibenz(a,h)anthracene	<	<	<	<	<	40	10,000 a
Benzo(g,h,i)perylene	90.0	<	<	<	<	40	
2-Methylnaphthalene	1210	<	15100	90900	<	80	
1-Methylnaphthalene	1140	<	10900	55500	<	80	
Phenolics							
Phenol	<	<	<	61500	<	240	
o-cresol	<	<	<	<	<	40	
m-cresol	<	<	<	8800	<	40	
p-cresol	<	<	<	9010	<	40	
2-Chlorophenol	<	<	<	<	<	120	
Biphenyl	<	<	785	10400	<	80	
2,4-Dimethyl phenol	<	<	<	<	<	320	

*all concentrations in ppb

** Benzo(b) and (k) fluoranthene co-eluted, therefore result is reported as a total

Concentration Limits:

a - CCME (1989) Value C (level at which contamination is significant)

Section 8

CONCLUSIONS

The conclusions of this report are based on the geological and hydrogeological characterizations discussed previously. Other conditions between and beyond the areas of the investigation, or at times other than during the investigation, may differ from those encountered. This may become apparent during future investigations, at which time the interpretations and recommendations made in this report may be re-evaluated.

The conclusions of this report are:

Tar contamination exists on ground surface in the immediate area of the former wood distillation/charcoal plant buildings.

Tar contamination exists on the bottom of Forest Lake in the near-shore area adjacent to the site. Lake sediments in this area are contaminated with high levels of PAHs.

No significant contamination of the lake water was detected. No parameter was detected at concentrations exceeding drinking water criteria.

No PAH, phenolic, or BTXE contamination was detected in a water sample from the South River Municipal Well #2.

Groundwater contaminated with high levels of PAHs, BTXE, and phenolic compounds is present under the former tar pit area in the north-central area of the site. This contamination is not laterally extensive as groundwater samples taken less than 100 m away are not contaminated.

In the central area of the site, soil contamination in the subsurface appears to be limited to the areas of the former tar pit, and the oven house/holding tank house buildings. In these areas, evidence of contamination in the subsurface was limited to strong odours. None of the boreholes onsite intersected soil which contained free-phase oil or tar.

Soil and groundwater contamination at a depth of 20 m below ground surface in the area of the former tar ponds suggests that there may be pools of liquid tar existing at the base of the aquifer in this location.

No significant vertical or horizontal hydraulic gradients were measured in the groundwater underneath the site. Under these conditions, only slow groundwater movement is occurring across the site. The low horizontal hydraulic gradients make it difficult to determine the direction of groundwater flow underneath the site.

Buried tar pond waste was located in the southwest area of the property, about 60 metres from the South River municipal wells. Tar contaminated sand, placed in three disposal trenches, was buried in the unsaturated zone above the watertable.

Three primary exposure pathways for release of the onsite contaminants have been identified. These are: groundwater migration to the municipal wells, direct contact with contaminated tars, soils, and lake sediments, and aquatic biota uptake of contaminants from lake sediments. Typical remedial alternatives have been reviewed for each pathway.

Section 9 RECOMMENDATIONS

Recommendations for further investigations, and preliminary recommendations for remedial action are outlined in this section.

Recommendations for further investigation are outlined as follows:

- The results of the preliminary lake sediment survey show that Forest Lake sediments are significantly contaminated with wood tar. According to the draft Ontario Provincial Sediment Quality Guidelines, (SQG), further testing is required to define the environmental impact of this contamination. This should include an additional lake sediment sampling program, with samples submitted for analysis of total PAHs, organic carbon (TOC) and for bioassay (lethality) tests as outlined in the SQG.

The extent of lake sediment contamination must also be further defined in order to facilitate remedial action. A more extensive diving inspection is required to map the horizontal and vertical (eg. sediment depth) extent of tar contamination. The diving inspection should follow a series of transect lines, perpendicular to the shoreline and extending outward into the lake. The inspection should cover the entire lake front area of the property and extend southeast to the Ottawa Avenue bridge.

- As a result of information made available subsequent to the original field investigation, buried tar pond wastes were discovered in a location 60 metres from the South River municipal wells. However, samples of groundwater from the municipal wells contained no detectable tar contamination. The installation and monitoring of one new shallow monitor well is recommended to monitor groundwater quality in the area near the buried waste. The proposed location of the new well between the buried waste and the municipal wells, is shown on Figure 7.

Preliminary recommendations for remedial action are outlined as follows:

- Restricted access to the former plant property is recommended in order to minimize direct contact with contaminated soil or physical hazards. This may be accomplished by installing fences or signs.
- Implementation of a groundwater monitoring program is also recommended. This should include installation of two new well nests, located to the west and to the southeast of MWN3 and one new shallow well near the disposal trenches. The locations of the proposed new wells are shown in Figure 7. The concentration of phenol and BTXE in MWN1, MWN2,

MWN3, the two new well nests, and the new shallow well should be regularly monitored.

- The preferred remedial action alternative to mitigate the impact of tar-contaminated material at ground surface is excavation and disposal offsite. Remedial action should be deferred, and re-evaluated after the detailed lake sediment study.
- The level of remedial action required to mitigate the impact of tar contaminated lake sediments will be defined by the detailed lake sediment survey and bioassay testing program outlined above.
- Site decommissioning, according to the Ontario MOE decommissioning guidelines (MOE, 1989), should be undertaken before any development of this property proceeds.

Section 10

REFERENCES

1. Bouwer, H., and R. C. Rice. A slug test method for determining hydraulic conductivity of unconfined aquifers with completely or partially penetrating wells, *Water Resources Research*, Vol. 12, no. 3, pp. 423-428. 1976.
2. Canadian Council of Ministers of the Environment (CCME). Interim Guidelines for PAH Contamination at Abandoned Coal Tar Sites, 1989.
3. Canviro Consultants. PAH Sediment Contamination in Kettle Creek, Port Stanley: Site Investigations and Remedial Alternatives. Unpublished report for the Ontario Ministry of the Environment, 1988.
4. Chapman L.J., and Putman, D.F. The Physiography of Southern Ontario - Third Edition, Ministry of Natural Resources, 1984.
5. Environmental Research and Technology. Handbook on Manufactured Gas Plant Sites, prepared for Utility Solid Waste Activities Group, Superfund Committee, 1984.
6. Freeze, R.A., and J.A. Cherry. Groundwater, Prentice-Hall Inc., Englewood Cliffs, New Jersey, 1979.
7. Geo-Environ Limited. Test Drilling Program, Village of South River, Ministry of the Environment Water Works Project No. 5-0255. Unpublished report for Northern Well Drilling Ltd., 1978.
8. Geo-Environ Limited. Well Construction Project, Village of South River, Ministry of the Environment Project No. 7-0011. Unpublished report for Northern Well Drilling Limited, 1983.
9. Health and Welfare Canada. Guidelines for Canadian Drinking Water Quality, Fourth Edition, 1989.
10. Montgomery, J.H. and Welkom, L.M. Groundwater Chemicals Desk Reference. Lewis Publishers Inc., Chelsea, Michigan, 1990.
11. Morrison Beatty Limited. Report on Well construction, Village of South River, District of Parry Sound. MOE Project No. 7-0011, Contract No. W1. Unpublished report for G. Hart and Sons, 1981.

12. National Research Council (NRC). Polycyclic Aromatic Hydrocarbons in the Aquatic Environment: Formation, Sources, Fate and Effects on Aquatic Biota, NRCC No. 18981, 1983.
13. Ontario Ministry of the Environment. Water Management - Goals, Policies, Objectives and Implementation Procedures of the Ministry of the Environment. Revised May 1984.
14. Ontario Ministry of the Environment. Guidelines for the Decommissioning and Cleanup of Sites in Ontario, February 1989.
15. Ontario Ministry of Natural Resources. Water Quantity Resources of Ontario. G. Lyons Litho Ltd., 1984.
16. Persaud, D., Jaagumagi, R. and Hayton, A. 1990. The Provincial Sediment Quality Guidelines: Draft, Water Resources Branch, Ontario Ministry of the Environment, July 1990.

Appendix A

FIELD INVESTIGATIONS

Appendix A

FIELD INVESTIGATION

A.1 SITE MAPPING

A site map was prepared by the pace and compass method. A 15 m grid was laid out over the central area of the site. Boreholes, monitor wells, building foundations, and other surface features were mapped during a walk survey. Small-scale air photographs were later used to complete the site map.

A.2 DRILLING/SOIL SAMPLING INVESTIGATION

The subsurface drilling investigation was undertaken between August 7, 1990 and August 20, 1990. A total of 19 boreholes were completed. Eleven shallow boreholes were drilled to the water table, between 4 and 5 metres below ground surface. Three boreholes were drilled to a depth of 9 metres below ground surface and were subsequently completed as shallow monitor wells. Three pairs of shallow and deep boreholes (9 and 19 metres below ground surface respectively) were drilled and subsequently completed as nests of shallow and deep monitor wells.

A track-mounted B-57 drill rig with hollow-stem augers was used to advance and sample borehole locations (Figure 3). Drilling procedures were complicated by sand flowing into the hollow stem of the augers. During drilling, this problem was minimized by filling the augers with water in order to force sand out the bottom of the augers.

Soil samples were obtained from borehole BH1 using a continuous sampler. All other borehole samples were obtained using a split-spoon sampler, which was more suitable to the "flowing sand" conditions. Split-spoon samples were taken at intervals of 0.76 m (2.5 ft.). Borehole soil samples were logged in the field, and placed in either plastic bags or glass jars. The samples were classified based on physical examination in the field as follows:

NC - No evidence of contamination by wood tar or related products

TC - Trace contamination by wood tar or related products based on colour

VC - Visual contamination with wood tar or related product

Field personnel placed selected soil samples into glass containers, which were stored in refrigerated coolers prior to submission to CANVIRO Analytical Laboratories Ltd. (CALL). Samples were selected to include one each of soils classified as NC, TC, and VC. Soil samples were analyzed for polycyclic aromatic hydrocarbons (PAHs) and phenolic compounds.

Between borehole locations, the augers and samplers were cleaned with water from nearby Forest Lake. Wash water was discharged to the ground surface on the site.

Boreholes not completed as monitoring wells were immediately backfilled using the excavated soil.

A.3 MONITOR WELL INSTALLATION

Monitor wells were installed in nine of the boreholes. The monitor wells included three shallow wells (MWS1, MWS2, MWS3) and three well nests each consisting of one shallow and one deep well (MWN1A, MWN1B, MWN2A, MWN2B, MWN3A, MWN3B). Locations of the wells are shown on Figure 3. Construction details of each well are given in the borehole logs, Appendix C.

Wells were constructed of 5 cm (2 inch) inside diameter, flush-threaded, schedule 40 PVC. Well screens were composed of machine slotted PVC. The well materials were cleaned by the manufacturer and delivered to the site in sealed plastic bags to prevent contamination in transit.

After auguring to the required depth, the well screen and riser pipe were installed through the hollow axis of the augers. Where flowing sand conditions existed, water was forced down the well screen and pipe during installation. The augers were pulled from the borehole and the native sand was allowed to collapse around the well screen and riser pipe. In most cases, bentonite seals were placed around the riser pipe several metres above the well screen, and also placed at ground surface. The riser pipes were protected at surface by casings of 10 cm (4 inch) ABS pipe and locking caps.

A.4 WELL DEVELOPMENT AND GROUNDWATER SAMPLING

Each monitoring well was developed in order to: (1) remove the fine material from the sand pack and develop a good filter area around the well screen; (2) remove water and sediment introduced into the well by the drilling operations; (3) ensure that representative groundwater samples could be obtained. Initial well development was done using a gasoline-powered centrifugal pump, which removed in excess of ten well volumes of water from each well. A well volume is the volume of water contained in the well screen, stand pipe, and the sand pack or disturbed area around the well. The monitoring wells were further developed by surging and purging the water in the wells using dedicated well samplers (Waterra pumps).

After well development, groundwater samples were collected using dedicated well sampling devices. All monitoring wells except MWS3 and MWN3B were sampled. The groundwater samples were collected directly into the appropriate sample containers provided by the laboratory, and clearly identified as to well location, well number, date and time, analyses required, and sampler signature. During sampling the pH, conduc-

tivity, and temperature of the groundwater was measured and recorded. All groundwater samples were placed in refrigerated storage onsite immediately after sampling, and were kept refrigerated during transport to the laboratory. Groundwater samples were analyzed for polycyclic aromatic hydrocarbons (PAHs), benzene, toluene, xylene, and ethyl benzene (BTXE), and phenolic compounds.

A.5 HYDRAULIC CONDUCTIVITY TESTING

Following groundwater sampling, hydraulic response or "bail" tests were performed on all monitor wells. The bail test consisted of removing a volume of groundwater from the well using a PVC bailer. A down-hole pressure transducer and automatic data logger recorded the water level response during the test. At many of the monitor well locations, no significant water level response was recorded during bail testing. This was presumably due to very large values of hydraulic conductivity of the subsurface materials at those locations.

Three borehole samples, chosen to represent the range of subsurface material encountered during drilling, were submitted for grain size analyses. The grain size analyses also provide an estimate of hydraulic conductivity.

A.6 WATER LEVEL MONITORING

All onsite monitor wells, as well as the South River municipal wells, were surveyed to determine a reference elevation for water level measurements. The water surface of Forest Lake was also included in the elevation survey. The survey was not tied-in to a geodetic benchmark, therefore a reference elevation of 100 m was assumed for the floor of the South River municipal well #1 pump house.

Water levels in all monitor wells were measured on August 17, 1990, August 20, 1990, and August 30, 1990.

A.7 DIVING INSPECTION AND LAKE SEDIMENT SAMPLING

Aquatic Sciences Incorporated performed a diving inspection in Forest Lake on August 13, 1990. Visual inspection of the lake bottom was carried out along a transect approximately 10 m out from shore. The inspection extended to a minimum of 3 m on either side of the transect line. The diver collected sediment samples at intervals of approximately 20 m along the transect line. Observations were reported over a two-way radio and were recorded by personnel on shore. Samples were collected directly into clean glass jars. At one location, a Shelby tube sampler was pushed by hand into the lake bottom to collect a shallow core of sediment. Recovery of sediment was extremely poor and this sampling method was not repeated.

The extent of tar contamination on the lake bottom was delineated during the visual inspection. The diver collected several samples of tar from the lake bottom. To minimize the amount of tar removed from the site, the interval between sampling locations was increased in the area where tar covered the lake bottom.

All lake sediment samples were examined in the field and classified as NC, TC, or VC, using the same classification criteria as for the borehole soil samples. A representative sample of each of the classified groups was selected for analysis including one contingency sample. The lake sediment samples were analyzed for PAHs and phenolic compounds.

A.8 COLLECTION OF SURFACE WATER SAMPLES

Two surface water samples were collected from Forest Lake adjacent to the study site. Each sample was collected in a different location from approximately .2 to .3 m below the lake water surface. Both locations were approximately 3 m out from shore, where the total water depth was .6 to .8 m. Sampling locations are shown on Figure 3.

Surface water samples were collected directly into the appropriate sample containers provided by the laboratory and clearly identified as to sampling location, date and time, analyses required, and sampler signature. During sampling the temperature, pH, and conductivity of the lake water was measured and recorded. Samples were placed in refrigerated storage onsite immediately after sampling and were kept refrigerated during transport to the laboratory. The lake water samples were analyzed for PAHs and phenolics.

A.9 COLLECTION OF TAR SAMPLES

Tar samples were collected both from ground surface onsite and from lake bottom surface in Forest Lake. Samples were collected directly into precleaned glass containers, which were tightly sealed, enclosed in two plastic bags, and kept isolated from water and soil samples to prevent cross-contamination. Tar samples were analyzed for PAHs, BTXE, and phenolics.

Appendix B

METHODS OF LABORATORY ANALYSIS AND QA/QC METHODS

B.1 SUMMARY OF LABORATORY ANALYTICAL METHODS

All analytical methods for PAH, Phenolic compounds (coal tar acids), BTXE, and Base Neutral Acid Extractable compounds (BNA) consisted of high resolution gas chromatography/mass spectrometry (HR GC/MS). The analytical procedure is a liquid extraction, gel permeation clean up (modified US EPA SW846). These procedures were performed at Canviro Analytical Laboratories.

The analytical method for determining the organic carbon content of soils (f_{oc}) was: acid wash of soil, followed by combustion and analysis with a carbon dioxide specific infra-red detector. This procedure was performed at the Organic Geochemistry Laboratory, University of Waterloo.

B.2 QA/QC TECHNIQUES

Sampling Program

A field sampling QA/QC program was used to achieve representative and reliable water quality data.

All groundwater samples were obtained using recognized sampling protocols. This included the use of laboratory pre-cleaned sample containers, dedicated sampling devices, and proper well purging techniques.

A duplicate groundwater sample was obtained from well MWS1. The sample and duplicate sample from this well were labelled MWS1A and MWS1B. Excellent agreement of analytical results were obtained between these two samples.

A travel blank water sample was prepared onsite, transported with the other groundwater samples, and analyzed. This sample was labelled MWS4. The results (Table 4, Appendix E) show trace levels of phenol, naphthalene, benzybutylphthalate, and di-n-butylphthalate. These results indicate that trace levels of these compounds reported in other groundwater samples are not significant and may not be representative of the groundwater quality.

No duplicate or travel blank samples were prepared for soil, lake sediment or tar samples. Typically these types of samples are fairly heterogeneous by nature. Analytical results for different sub-samples of the same sample can be expected to vary by a significant amount. Therefore, duplicate samples are of limited value. There is considerable difficulty in preparing a "clean" travel blank soil sample which has a similar matrix to actual soil samples. Generally, travel blanks are not used for soil and sediment samples.

Laboratory Program

A laboratory QA/QC program was used to establish the precision and reliability of the analytical results.

Laboratory blanks were analyzed along with the samples for all analyses, to estimate the accuracy of the results and also as a check on sources of contamination in the laboratory.

All samples were spiked in the laboratory with known amounts of surrogate compounds before extraction and analysis. The analytically determined concentration of the surrogates is then compared to the known values, as a check on the extraction and analytical techniques.

Also, a laboratory "standard" sample, or spike, containing known amounts of the parameters under analysis, is analyzed along with the soil, sediment and water samples. The analytically determined concentration of the spike is then compared to the known values, as a check on the analytical methods.

Finally, for every sample, a number of PAH and phenolic compounds underwent duplicate analyses. These compounds were analyzed both as a part of the PAH or Phenolics analysis and as a part of the BNA scan. The same extract was used for the original and the duplicate analysis. This provides an estimation of the reproducibility of the analytical method.

The results of the laboratory QA/QC program are summarized below.

The analytical results from the laboratory blanks were good. Only trace levels of two compounds: chloroform and Di-n-butylphthalate, were detected in the laboratory blanks. Similar levels of these compounds detected in samples are not significant, as they may not be representative of the sample itself.

The repeatability of PAH and Phenolics analyses was generally very good. Replicate analyses were normally within a factor of 2 of the original analysis. The analyses of contaminated samples which required dilutions generally had a poorer repeatability, which is to be expected.

The recovery of surrogate compounds and of the spike sample was generally fair. In many cases the recovery of the surrogate or the spike was less than 80%. This indicates that some under-estimation of similar compounds may have occurred for that sample. In cases where the recovery of the surrogate or spike was over 120%, some over-estimation of similar compounds may have occurred for that sample.

Appendix C

BOREHOLE LOGS AND WELL CONSTRUCTION DETAILS

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/07
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE: 97.788
-TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		G1			<u>Topsoil</u> - dk. brown, sandy, loamy, rootlets, moist, coal bits, NC	
		C1	30		<u>Sand</u> - brown, mottled, moist, medium to coarse, NC	
2						
		C2	0			
3						
		SS1	32	3,3,5,6	Sand - lt. brown, fine to medium, saturated, NC	
4						
5					END OF HOLE	
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/07

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.31

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE:

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
				0" - 0" - 0" (N)	NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	32	2,4,4,3	<u>Topsoil</u> - black, rootlets, loamy, moist, NC	
		SS2	38	2,3,6,14	<u>Sand</u> - brown, mottled, some oxidation, medium to coarse, moist, NC, coal bits	
2		SS3	36	4,14,14,15	<u>Sand</u> - red, medium, moist, NC	
		SS4	30	5,11,13,14	<u>Sand</u> - brown, medium, moist, NC	
3		SS5	24	8,8,8,8	NC	
		SS6	29	4,5,6,6	<u>Sand</u> - brown, mottled, medium to coarse, saturated, NC	
5		SS7	31	9,6,9,6	NC	
					END OF HOLE	
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/10

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE:

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE:

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	27	1,2,2,1	<u>Sand</u> - black, rootlets, loamy, moist, NC	
		SS2	30	7,9,11,10	<u>Sand</u> - brown, mottled, some oxidation, medium to coarse, dry to moist, coal bits, NC	
2		SS3	18	1,1,3,7.	NC	
		SS4	39	5,7,9,10	NC	
3		SS5	29	5,7,8,8	<u>Sand</u> - lt. brown, occasional red streak, medium to coarse, moist, NC	
4		SS6	26	1,6,7,6	NC	
5		SS7	19	2,4,6,7	<u>Sand</u> - saturated END OF HOLE	
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/10
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE:
-TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	29	1,3,4,5	Topsoil - black, sandy, loamy, fibrous, brick/concrete frags, coal bits, damp, NC	
		SS2	39	5,7,11,11	- possibly fill material	
2		SS3	37	7,5,15,12	Sand - brown, mottled, medium to coarse, damp, NC	
3		SS4	35	7,9,14,12	NC	
		SS5	34	9,10,8,14	NC	
4		SS6	23	4,8,8,9	Sand - saturated, NC	
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/10
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE: 99.534 m
-TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 5" - 5" - 5" (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	34	3,5,3,9	<u>Topsoil</u> -black, sandy, rootlets, loamy, damp, NC	
		SS2	35	2,3,4,4	<u>Sand</u> - reddish, mediom to coarse, coal bits, NC	
2		SS3	36	8,9,9,10	<u>Sand</u> - lt. brown, mottled, medium to coarse, moist, NC	
3		SS4	35	6,7,7,8	NC	
		SS5	34	3,6,7,9	<u>Sand</u> - saturated, NC	
4						
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
 CLIENT: Former Standard Chemical Site
 LOCATION: South River, Ontario
 DRILLING CONTRACTOR: Longyear
 DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount


DATE: 90/08/10
 LOGGER: Tim MacGillivray
 ELEVATION: -GROUND SURFACE:
 -TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
				0" - 0" - 0" (N)	NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	34	1,2,7,11	<u>Topsoil</u> -black, sandy, rootlets, loamy, damp, coal frags, NC	
2		SS2	39	8,11,9,9	<u>Sand</u> - lt. brown, mottled, medium to coarse, damp, NC	
3		SS3	39	10,12,14,11	NC	
4		SS4	41	15,17,20,15	NC	
5		SS5	24	6,6,6,7	<u>Sand</u> - saturated	
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/11
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE:
-TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL & GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	34	3,5,3,9	<u>Topsoil</u> -black, sandy, rootlets, loamy, damp, concrete/brick frags, coal bits, NC	
		SS2	35	2,3,4,4	<u>Sand</u> - lt. brown, mottled, trace silt, coal frags, gravel frags, moist, NC	
2		SS3	36	8,9,9,10	Sand - dk. brown, mottled, trace silt, moist, black streaks, coal/brick frags, faint odour, TC	
3		SS4	35	6,7,7,8	<u>Sand</u> - dk. brown, with black streaks, fine to coarse, moist, odour, TC/VC	
		SS5	34	3,6,7,9	<u>Sand</u> - rusty colour, black streaks, medium to coarse, odour, saturated, TC/VC	
4						
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/11

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.382 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE:

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	28	1,3,4,3	<u>Topsoil</u> - black, sandy, rootlets, loamy, damp,, coal bits, NC	
		SS2	38	10,20,20,17	<u>Sand</u> - red, medium, coal frags, moist, NC	
2		SS3	33	6,17,28,19	<u>Sand</u> - brown, mottled, moist, NC	
3		SS4	34	9,14,12,14	NC	
		SS5	31	14,10,12,13	NC	
4		SS6	24	14,9,8,9	<u>Sand</u> - brown, mottled, saturated, NC	
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill, B - 57 Track Mount

DATE: 90/08/11
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE: 99.696 m
-TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	28	1,3,4,3	<u>Topsoil</u> -black, sandy, rootlets, <u>loamy, damp</u> , coal bits, NC	
		SS2	38	10,20,20,17	<u>Sand</u> - red, medium, coal frags, moist, NC	
2		SS3	33	6,17,28,19	<u>Sand</u> - brown, mottled, moist, NC	
		SS4	34	9,14,12,14	NC	
3		SS5	31	14,10,12,13	NC	
4		SS6	24	14,9,8,9	<u>Sand</u> - brown, mottled, saturated, NC	
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
 CLIENT: Former Standard Chemical Site
 LOCATION: South River, Ontario
 DRILLING CONTRACTOR: Longyear
 DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/11
 LOGGER: Tim MacGillivray
 ELEVATION: -GROUND SURFACE:
 -TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	28	2,2,2,7	<u>Topsoil</u> - black, sandy, rootlets, <u>loamy, damp</u> , coal bits, NC <u>Sand</u> - lt. brown, mottled, brick frags, coal bits, NC	
		SS2	33	8,10,14,19		
2		SS3	39	9,14,17,17	NC	
		SS4	31	14,19,18,16	NC	
3		SS5	32	19,18,11,8	NC	
4		SS6	24	12,9,9,10	<u>Sand</u> - brown, mottled, saturated, NC	
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
 CLIENT: Former Standard Chemical Site
 LOCATION: South River, Ontario
 DRILLING CONTRACTOR: Longyear
 DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DATE: 90/08/11
 LOGGER: Tim MacGillivray
 ELEVATION: -GROUND SURFACE:
 -TOP OF RISER PIPE:

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS σ ₁ - σ ₂ - σ ₃ (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	17	1,2,2,4	<u>Topsoil</u> -black, sandy, rootlets, loamy, damp,, coal bits, NC	
		SS2	26	4,8,11,13	<u>Sand</u> - red, black, mottled, medium to coarse, damp, NC	
2		SS3	29	5,9,9,13	<u>Sand</u> - lt. brown, mottled, moist, faint odour, TC	
		SS4	25	13,17,19,24	strong odour, TC - VC	
3		SS5	32	17,9,12,12	strong odour, TC - VC	
4		SS6	34	19,17,11,19	TC - VC, saturated	
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/10

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.452 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 100.276 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	- locking cap - protective casing
1		SS1	39	1,5,5,4	Topsoil - black, rootlets, loamy	bentonite seal
2		SS2	18	5,9,11,11	Sand - lt. brown, mottled, medium to coarse, trace pebbles, moist, coal bits	
3		SS3	22	7,12,13,13	Sand - lt. brown, mottled, medium to coarse, moist, NC	riser pipe
4		SS4	31	6,9,11,14	NC	bentonite seal
5		SS5	29	9,6,6,10	NC	native sand
6		SS6	32	7,8,8,12	Sand - grey, mottled, medium to coarse, saturated, NC	
7		SS7	30	1,2,5,8	NC	well screen
8		SS8	23	5,11,12,9	NC	
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/11

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.493 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 100.173 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	- locking cap - protective casing
1		SS1	32	4,20,18,17	Topsoil - black, rootlets, loamy, coal frags, NC	- bentonite seal
		SS2	34	17,15,18,20	Sand -dk. brown, coal/brick frags, loamy, damp, NC	
2		SS3	31	2,2,2,4	Sand - lt. brown, mottled, medium to coarse, moist, brick frags. NC	- riser pipe
		SS4	29	3,6,6,8	Sand - red, medium , moist, NC	
3		SS5	27	7,10,10,10	Sand - brown, medium to coarse, trace pebbles, moist, NC	- bentonite seal
4						- native sand
5		SS6	22	3,4,3,4	Sand - brown, mottled, medium to coarse, saturated, trace gravel, NC	
6						
7		SS7	20	4,8,9,12	NC	- well screen
8		SS8	39	10,11,12,15	NC	
9		SS9	22	14,14,10,11	NC	
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/11

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray












LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.910 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 100.590 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill, B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
1		SS1	.28	1,3,7,11	<u>Topsoil</u> - black, rootlets, loamy, coal frags, NC	
2		SS2	44	14,11,17,17	<u>Sand</u> - lt. brown, mottled, medium to coarse, moist, NC	
3		SS3	39	11,17,15,16	NC	
4						
5		SS4	34	7,4,3,3	Sand - brown, mottled, medium to coarse, saturated, trace gravel, NC	
6		SS5	29	17,12,9,10	NC	
7						
8		SS6	31	15,11,17,21	NC	
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/07

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.033 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 99.763 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.	
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)				
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	locking cap protective casing	
		SS1	43	1,2,3,4	Topsoil - black, rootlets, loamy	bentonite seal	
1		SS2			Sand - brown, mottled, medium to coarse, trace pebbles, moist, NC	riser pipe	
2		SS3	38	5,8,8,9	- some oxidation, NC		
3		SS4	39	5,6,6,8	NC		
4		SS5	34	3,4,4,4	- wet, NC		
5		SS6	32	4,5,6,12	grey, mottled, medium, saturated, NC		
6		SS7	23	7,7,8,12	NC		
7		SS8	20	4,9,7,8	NC		
8		SS9	29	8,7,8,11	NC		
9		SS10	0				
10		SS11	31	7,9,11,11	NC		
		SS12	30	4,8,9,14	NC		
		SS13	24	5,9,14,16	Sand - grey, mottled, medium to coarse, saturated, faint odour, TC		

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Standard Chemical Plant Hydrogeologic Investigation

DATE: 90/08/07

CLIENT: M.O.E.

LOGGER: T. MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.033 m

DRILLING CONTRACTOR: Longyear Canada

-TOP OF RISER PIPE: 99.763 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill, B - 57 track mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION		WELL CONSTRUCTION	
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.		CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.	
11		SS14	29	6,27,90	Sand - grey, mottled, medium, saturated, odour, TC			bentonite seal
12		SS15	36	20,9,>100/ 6"	NC			
13								
14		SS16	31		NC			native sand
15								
16		SS17	34		NC			riser pipe
17		SS18	21					
18					Sand - dk. gray, brown mottled, medium, saturated, strong odour, TC -VC			well screen
19		SS19	22		soils appear darker, possible change noted by driller			
20								
22								

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/07

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray



LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.348

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 100.028

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL METRE	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	 - locking cap - protective casing
1	not sampled				<u>Topsoil</u> - black, loamy, rootlets, <u>Sand</u> - brown, mottled, medium, moist, saturated,	 - riser pipe - native sand - well screen
2						
3						
4						
5						
6						
7						
8						
9						
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/07

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray

LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.698 m

DRILLING CONTRACTOR: Longyear

-TOP OF RISER PIPE: 100.538 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 0" - 0" - 0" (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	locking cap protective casing
1		SS1	39	4,8,8,10	Topsoil - black, rootlets, loamy	bentonite seal
		SS2	18	5,5,6,4	Sand - lt. brown, mottled, medium to coarse, trace pebbles, moist, concrete frags, coal bits, faint odour, NC-TC	
2		SS3	18	8,11,10,10	NC	
		SS4	37	2,5,5,7	NC	riser pipe
3		SS5	27	3,5,6,5	- wet, NC	native sand
4		SS6	32	2,3,4,4	Sand - grey, mottled, medium, saturated, NC	
5		SS7	29	3,4,5,7	NC	
6		SS8	24	9,9,11	NC	
		SS9	27	4,5,8,7	NC	
7		SS10	20	6,6,7,19	NC	
8		SS11	27	6,5,7,7	NC	
9		SS12	28	5,3,5,11	NC	
		SS13	0			
10		SS14	21	6,6,9,15	NC	

PROJECT NUMBER
ONT29344.AO

WELL NUMBER
MWN2A

PAGE 2 OF 2

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Standard Chemical Plant Hydrogeologic Investigation

DATE: 90/08/08

CLIENT: M.O.E.

LOGGER: T. MacGillivray


LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 99.698 m

DRILLING CONTRACTOR: Longyear Canada

-TOP OF RISER PIPE: 100.538 m




DRILLING METHOD AND EQUIPMENT: Mobile Drill, B - 57 track mount

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS $\sigma' - \sigma'' - \sigma'''$ (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL & GRADATION, GROUT INTERVAL, ETC.	
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)				
11	I	SS15	10	3,4,4,8	Sand - grey, mottled, medium, saturated, odour, NC		bentonite seal
		SS16	0				
12	I	SS17	25	4,8,9,9	NC		
13	I	SS18	39	5,6,9,6	NC		
14	I	SS19	56	10,12,9,8,	NC		
15	I	SS20	34		NC		
16	I						
17	I	SS21	28		NC		
18	I	SS22	30		NC		
19	I						
20	I						
22	I						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount




DATE: 90/08/08
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE: 99.631 m
-TOP OF RISER PIPE: 100.511 m

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS $\sigma' - \sigma' - \sigma'$ (N)	SOIL DESCRIPTION	WELL CONSTRUCTION
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)		NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	
					Topsoil - black, loamy, rootlets	
1		not sampled			Sand - brown, mottled, medium, moist	
2						
3						
4					saturated	
5						
6						
7						
8						
9					Sand - brown, mottled, fine to coarse, saturated, odour, TC (auger bit sample)	
10						

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation
CLIENT: Former Standard Chemical Site
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear
DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount








DATE: 90/08/09
LOGGER: Tim MacGillivray
ELEVATION: -GROUND SURFACE: 99.543 m
-TOP OF RISER PIPE: 100.343 m

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVAL, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	 - locking cap - protective casing
		SS1	29	1,3,5,5	Topsoil - black, rootlets, loamy	 - bentonite seal
1		SS2	39	3,5,5,7	<u>Sand</u> - red, mottled, medium to coarse, trace pebbles, dry to damp, NC	
2		SS3	40	5,10,15,18	<u>Sand</u> - lt. brown, mottled, medium to coarse, moist, NC	
3		SS4	36	7,8,8,9	NC	- riser pipe
4		SS5	37	6,8,8,10	NC	- native sand
5		SS6	33	5,6,10,10	<u>Sand</u> - grey, mottled, medium, NC saturated	
6		SS7	29	5,8,11,15	NC	
7		SS8	22	5,7,10,9	NC	
8		SS9	25	2,3,4,7	NC	
9		SS10	23	6,7,7,11	NC	 bentonite seal
10		SS11	12	5,4,3,5	<u>Sand</u> - black lenses, fine to medium, saturated, NC	

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Standard Chemical Plant Hydrogeologic Investigation
CLIENT: M.O.E.
LOCATION: South River, Ontario
DRILLING CONTRACTOR: Longyear Canada
DRILLING METHOD AND EQUIPMENT: Mobile Drill, B - 57 track mount

DATE: 90/08/09
LOGGER: T. MacGillivray
ELEVATION: -GROUND SURFACE: 99.543 m
-TOP OF RISER PIPE: 100.343 m

DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS 6" - 6" - 6" (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.		
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)					
11		SS12	12	5,4,3,5	<u>Sand</u> - grey, mottled, medium, saturated, NC			
12		SS13	51	9,8,8,11	<u>Sand</u> - black lens, fine to coarse, NC			
13								
14		SS14	32	15,17,19,21	<u>Sand</u> - grey, mottled, medium, saturated , NC			native sand
15								
16		SS15	29	16,23,34,28	NC			riser pipe
17		SS16						
18		SS17						well screen
19								
20								
22								

MONITORING WELL DRILLING & CONSTRUCTION LOG

PROJECT: Hydrogeologic Investigation

DATE: 90/08/09

CLIENT: Former Standard Chemical Site

LOGGER: Tim MacGillivray


LOCATION: South River, Ontario

ELEVATION: -GROUND SURFACE: 100.297 m

DRILLING CONTRACTOR: Longyear


-TOP OF RISER PIPE: 100.392 m

DRILLING METHOD AND EQUIPMENT: Mobile Drill , B - 57 Track Mount


DEPTH BELOW SURFACE (METRES)	SAMPLE			STANDARD PENETRATION TEST RESULTS " - " - " (N)	SOIL DESCRIPTION NAME, COLOR, SOIL STRUCTURE, PARTICLE SIZE DISTRIBUTION, MOISTURE CONTENT, MINERALOGY, GRADATION OR PLASTICITY, RELATIVE DENSITY OR CONSISTENCY, ETC.	WELL CONSTRUCTION CASING, DIAMETER, SCREEN INTERVAL, SLOT SIZE, GRAVEL PACK INTERVALS, GRADATION, GROUT INTERVAL, ETC.
	INTER- VAL (METRE)	TYPE AND NUM- BER	RE- COV- ERY (CM)			
					NC - no contamination TC - trace contamination (faint odour) VC - very contaminated (sheen and strong odour)	- locking cap - protective casing
		SS1	29	1,3,5,5	Topsoil - black, rootlets, loamy	 bentonite seal
1		SS2	39	3,5,5,7	Sand - red, mottled, medium to coarse, trace pebbles, dry to damp, NC	
2		SS3	40	5,10,15,18	Sand - lt. brown, mottled, medium to coarse, moist, NC	
3		SS4	36	7,8,8,9	NC	
4		SS5	37	6,8,8,10	NC	
5		SS6	33	5,6,10,10	Sand - grey, mottled, medium, NC saturated	
6		SS7	29	5,8,11,15	NC	
7		SS8	22	5,7,10,9	NC	
8		SS9	25	2,3,4,7	NC	
9		SS10	23	6,7,7,11	NC	
10		SS11	12	5,4,3,5	Sand - black lenses, fine to medium, saturated, NC	


Appendix D

SLUG TEST RESULTS




MWJN2A





MWJN1B



Appendix E
CHEMICAL ANALYSES

SAMPLE IDENTIFICATION	
Sample #	Sample Name
5178-01	Lake sediment 0 + 00 (scoop sample)
5178-02	Lake sediment 0 + 40 (scoop sample)
5178-03	Lake sediment 1 + 20 (scoop sample)
5178-04	Core of Lake Sediment 1 + 60
5178-05	Lake sediment 2 + 00 (scoop sample)
5178-06	Tar - surface crust 2 + 40
5178-07	Lake sediment 2 + 80 (scoop sample)
5178-08	Tar - fluid tar under crust 3 + 60
5178-09	Lake Sediment 2 + 40 (scoop sample)
5178-10	Tar - from ground surface near MWN1
5178-11	Soil Samples - BHS7-SS3
5178-12	Soil Samples - MWN3A-SS16
5178-13	Soil Samples - BHS11-SS5
5178-14	Soil Samples - BHS6-SS5
5178-15	Soil Samples - MWN3B-SS7

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	MDL
IDENTIFICATION NO.		5178-01	5178-02	5178-03	5178-04	5178-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
1	Camphene	<	<	<	(118)	<	368
2	bis(2-chloroethyl)ether	<	<	<	<	<	57.6
3	o-Cresol	<	<	<	<	<	1.6
4	m-Cresol	<	<	<	<	<	1.6
5	p-Cresol	<	<	<	<	<	1.6
6	bis(2-chloroisopropyl) ether	<	<	<	<	<	14.4
7	Phenol	<	<	<	<	<	9.6
8	Nitrosodi-n-propylamine	<	<	<	<	<	1.6
9	bis(2-chlorethoxy)methane	<	<	<	<	<	1.6
10	Naphthalene	193	290	7.16	18.1	687	1.6
11	2-Chlorophenol	<	<	<	<	<	4.8
12	2,4-Dimethylphenol	<	<	<	<	<	12.8
13	Indole	<	<	<	<	<	3.2
14	2-methylnaphthalene	353	437	10.7	13.2	1140	3.2
15	1-Methylnaphthalene	215	227	8.82	13.2	908	3.2
16	4-chloro-3-methylphenol	<	<	<	<	<	3.2
17	2-chloronaphthalene	<	<	<	<	<	3.2
18	1-chloronaphthelene	<	<	<	<	<	3.2
19	2,6-dichlorophenol	<	<	<	<	<	3.2

() - reported at < MDL, all identification criteria were satisfied

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	MDL
IDENTIFICATION NO.		5178-01	5178-02	5178-03	5178-04	5178-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
20	2,4-dichlorophenol	<	<	<	<	<	3.2
21	Diphenyl ether	<	<	<	<	<	3.2
22	2,4,6-trichlorophenol	<	<	<	<	<	4.8
23	Acenaphthylene	70.9	<	5.52	<	50.8	3.2
24	2,4-dinitrophenol	<	<	<	<	<	44.8
25	2,6-dinitrotoluene	<	<	<	<	<	91.2
26	4-nitrophenol	<	<	<	<	<	192
27	Acenaphthene	63.2	<	<	14.0	16.3	3.2
28	2,3,5-trichlorophenol	<	<	<	<	<	3.2
29	2,4,5-trichlorophenol	<	<	<	<	<	6.4
30	2,3,4-trichlorophenol	<	<	<	<	<	3.2
31	2,4-dinitrotoluene	<	<	<	<	<	97.6
32	Fluorene	190	112	7.90	31.5	425	3.2
33	4-chlorophenyl phenyl ether	<	<	<	<	<	3.2
34	4,6-dinitro-o-cresol	<	<	<	<	<	1500
35	Total Diphenylamine	<	<	<	<	<	3.2
36	2,3,5,6-tetrachlorophenol	<	<	<	<	<	3.2
37	2,3,4,6-tetrachlorophenol	<	<	<	<	<	3.2
38	2,3,4,5-tetrachlorophenol	<	<	<	<	<	3.2
39	4-bromophenyl phenyl ether	<	<	<	<	<	3.2

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	MDL
IDENTIFICATION NO.		5178-01	5178-02	5178-03	5178-04	5178-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
40	Phenanthrene	430	164	40.5	10.2	993	1.6
41	Anthracene	96.2	29.6	7.62	<	156	1.6
42	Pentachlorophenol	<	<	<	<	<	1.6
43	Biphenyl	100	166	<	7.51	149	3.2
44	Fluoranthene	519	92.3	71.3	5.73	924	1.6
45	Pyrene	557	107	74.7	10.3	850	1.6
46	Benzylbutylphthalate	56.8	44.5	72.4	35.7	26.6	3.2
47	Benzo (a) anthracene	214	33.0	30.2	<	344	1.6
48	Chrysene	253	41.8	32.2	<	377	17.6
49	bis(2-ethylhexyl)phthalate	<	<	<	<	<	1.6
50	Di-n-butylphthalate	88.3	113	95.9	79.7	81.4	3.2
51	Benzo (b) fluoranthene	277	35.2	40.2	<	381	3.2
52	Benzo (k) Fluoranthene	238	27.1	38.8	<	306	1.6
53	Benzo (a) pyrene	195	25.4	34.1	<	336	1.6
54	Perylene	82.2	9.18	12.2	296	123	1.6
55	5-Nitroacenaphthene	<	<	<	<	<	1.6
56	Indeno(1,2,3-cd)pyrene	237	21.8	40.7	<	305	1.6
57	Dibenzo(ah)anthracene	31.9	<	<	<	31.6	1.6
58	Benzo(ghi)perylene	305	36.3	33.5	<	323	1.6
% RECOVERY OF SURROGATES							
d6-Phenol		ND	ND	ND	ND	ND	
d8-Naphthalene		28	22	41	41	67	
d12-Chrysene		97	98	73	73	79	

NOTE: Samples have NOT been corrected for laboratory blank.

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	TAR NEAR MUN1	MDL
IDENTIFICATION NO.		5178-06*	5178-07*	5178-08*	5178-09*	5178-10*	
NO	COMPOUND	mg/L	mg/L	mg/L	mg/L	mg/L	ug/L
1	Camphene	<	<	<	<	<	368
2	bis(2-chloroethyl)ether	<	<	<	<	<	57.6
3	o-Cresol	<	<	<	<	1350	1.6
4	m-Cresol	<	<	<	<	1300	1.6
5	p-Cresol	<	<	<	<	1100	1.6
6	bis(2-chloroisopropyl) ether	<	<	<	<	<	14.4
7	Phenol	<	<	<	<	<	9.6
8	Nitrosodi-n-propylamine	<	<	<	<	<	1.6
9	bis(2-chlorethoxy)methane	<	<	<	<	<	1.6
10	Naphthalene	47.2	70.1	7.77	39.8	26.4	1.6
11	2-Chlorophenol	<	<	<	<	<	4.8
12	2,4-Dimethylphenol	<	<	<	<	<	12.8
13	Indole	<	<	<	<	<	3.2
14	2-methylnaphthalene	186	24.9	28.8	156	65.1	3.2
15	1-Methylnaphthalene	134	17.4	19.5	110	47.8	3.2
16	4-chloro-3-methylphenol	<	<	<	<	<	3.2
17	2-chloronaphthalene	<	<	<	<	<	3.2
18	1-chloronaphthalene	<	<	<	<	<	3.2
19	2,6-dichlorophenol	<	<	<	<	<	3.2

* due to the nature of the matrix, the following samples have higher MDL's

5178-06: 112 x higher 5178-09: 184 x higher

5178-07: 60 x higher 5178-10: 144 x higher

5178-08: 24 x higher

BASE NEUTRAL ACID EXTRACTABLES (CONT.)

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	TAR NEAR MWN1	MDL
IDENTIFICATION NO.		5178-06*	5178-07*	5178-08*	5178-09*	5178-10*	
NO	COMPOUND	mg/L	mg/L	mg/L	mg/L	mg/L	ug/L
20	2,4-dichlorophenol	<	<	<	<	<	3.2
21	Diphenyl ether	<	<	<	<	<	3.2
22	2,4,6-trichlorophenol	<	<	<	<	<	4.8
23	Acenaphthylene	14.2	<	1.91	9.25	<	3.2
24	2,4-dinitrophenol	<	<	<	<	<	44.8
25	2,6-dinitrotoluene	<	<	<	<	<	91.2
26	4-nitrophenol	<	<	<	<	<	192
27	Acenaphthene	24.7	31.6	3.57	20.9	<	3.2
28	2,3,5-trichlorophenol	<	<	<	<	<	3.2
29	2,4,5-trichlorophenol	<	<	<	<	<	6.4
30	2,3,4-trichlorophenol	<	<	<	<	<	3.2
31	2,4-dinitrotoluene	<	<	<	<	<	97.6
32	Fluorene	152	207	13.5	132	45.8	3.2
33	4-chlorophenyl phenyl ether	<	<	<	<	<	3.2
34	4,6-dinitro-o-cresol	<	<	<	<	<	1500
35	Total Diphenylamine	<	<	<	<	<	3.2
36	2,3,5,6-tetrachlorophenol	<	<	<	<	<	3.2
37	2,3,4,6-tetrachlorophenol	<	<	<	<	<	3.2
38	2,3,4,5-tetrachlorophenol	<	<	<	<	<	3.2
39	4-bromophenyl phenyl ether	<	<	<	<	<	3.2

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	TAR NEAR MUN1	MDL
IDENTIFICATION NO.		5178-06*	5178-07*	5178-08*	5178-09*	5178-10*	
NO	COMPOUND	mg/L	mg/L	mg/L	mg/L	mg/L	ug/L
40	Phenanthrene	82.5	98.5	<	68.8	33.6	1.6
41	Anthracene	37.5	46.8	<	30.7	<	1.6
42	Pentachlorophenol	<	<	<	<	<	1.6
43	Biphenyl	26.8	35.2	37.0	23.0	<	3.2
44	Fluoranthene	19.0	21.2	<	16.2	10.5	1.6
45	Pyrene	29.0	32.6	1.53	24.5	12.2	1.6
46	Benzybutylphthalate	3.7	<	<	4.75	4.42	3.2
47	Benzo (a) anthracene	8.0	9.1	<	<	<	1.6
48	Chrysene	9.0	9.6	<	<	<	17.6
49	bis(2-ethylhexyl)phthalate	<	<	<	<	<	1.6
50	Di-n-butylphthalate	<	<	1.65	<	<	3.2
51	Benzo (b) fluoranthene	<	<	<	<	<	3.2
52	Benzo (k) Fluoranthene	<	<	<	<	<	1.6
53	Benzo (a) pyrene	<	7.04	<	<	<	1.6
54	Perylene	<	<	<	<	<	1.6
55	5-Nitroacenaphthene	<	<	<	<	<	1.6
56	Indeno(1,2,3-cd)pyrene	<	<	<	<	<	1.6
57	Dibenzo(ah)anthracene	<	<	<	<	<	1.6
58	Benzo(ghi)perylene	<	<	<	<	<	1.6
% RECOVERY OF SURROGATES							
d6-Phenol		ND	ND	ND	ND	ND	
d8-Naphthalene		**	**	**	**	**	
d12-Chrysene		**	**	**	**	**	

NOTE: Samples have NOT been corrected for laboratory blank.

** recoveries not possible due to required dilution

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		SOIL BHS7-SS3	SOIL MLN3A-SS6	SOIL BHS11-SS5	SOIL BHS6-SS5	SOIL MLN3-SS7	MDL
IDENTIFICATION NO.		5178-11	5178-12	5178-13	5178-14	5178-15	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
1	Camphene	<	<	<	<	<	368
2	bis(2-chloroethyl)ether	<	<	<	<	<	57.6
3	o-Cresol	<	<	<	<	<	1.6
4	m-Cresol	<	<	<	<	<	1.6
5	p-Cresol	<	<	<	<	<	1.6
6	bis(2-chloroisopropyl) ether	<	<	<	<	<	14.4
7	Phenol	<	<	<	<	<	9.6
8	Nitrosodi-n-propylamine	<	<	<	<	<	1.6
9	bis(2-chloroethoxy)methane	<	<	<	<	<	1.6
10	Naphthalene	200	<	87.5	<	<	1.6
11	2-Chlorophenol	<	<	<	<	<	4.8
12	2,4-Dimethylphenol	<	<	<	<	<	12.8
13	Indole	<	<	<	<	<	3.2
14	2-methylnaphthalene	1520	<	134	<	<	3.2
15	1-Methylnaphthalene	693	<	105	<	<	3.2
16	4-chloro-3-methylphenol	<	<	<	<	<	3.2
17	2-chloronaphthalene	<	<	<	<	<	3.2
18	1-chloronaphthalene	<	<	<	<	<	3.2
19	2,6-dichlorophenol	<	<	<	<	<	3.2

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		SOIL BHS7-SS3	SOIL MUN3A-SS6	SOIL BHS11-SS5	SOIL BHS6-SS5	SOIL MUN3-SS7	MDL
IDENTIFICATION NO.		5178-11	5178-12	5178-13	5178-14	5178-15	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
20	2,4-dichlorophenol	<	<	<	<	<	3.2
21	Diphenyl ether	<	<	<	<	<	3.2
22	2,4,6-trichlorophenol	<	<	<	<	<	4.8
23	Acenaphthylene	33.3	<	9.55	<	<	3.2
24	2,4-dinitrophenol	<	<	<	<	<	44.8
25	2,6-dinitrotoluene	<	<	<	<	<	91.2
26	4-nitrophenol	<	<	<	<	<	192
27	Acenaphthene	83.2	<	11.6	<	<	3.2
28	2,3,5-trichlorophenol	<	<	<	<	<	3.2
29	2,4,5-trichlorophenol	<	<	<	<	<	6.4
30	2,3,4-trichlorophenol	<	<	<	<	<	3.2
31	2,4-dinitrotoluene	<	<	<	<	<	97.6
32	Fluorene	388	<	20.0	<	<	3.2
33	4-chlorophenyl phenyl ether	<	<	<	<	<	3.2
34	4,6-dinitro-o-cresol	<	<	<	<	<	1500
35	Total Diphenylamine	<	<	<	<	<	3.2
36	2,3,5,6-tetrachlorophenol	<	<	<	<	<	3.2
37	2,3,4,6-tetrachlorophenol	<	<	<	<	<	3.2
38	2,3,4,5-tetrachlorophenol	<	<	<	<	<	3.2
39	4-bromophenyl phenyl ether	<	<	<	<	<	3.2

BASE NEUTRAL ACID EXTRACTABLES (CONT.)

IDENTIFICATION		SOIL BHS7-SS3	SOIL MWN3A-SS6	SOIL BHS11-SS5	SOIL BHS6-SS5	SOIL MWN3-SS7	MDL
IDENTIFICATION NO.		5178-11	5178-12	5178-13	5178-14	5178-15	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
40	Phenanthrene	481	15.2	122	5.06	9.50	1.6
41	Anthracene	148	<	16.4	<	<	1.6
42	Pentachlorophenol	<	<	<	<	<	1.6
43	Biphenyl	139	<	16.4	<	<	3.2
44	Fluoranthene	268	<	100	<	<	1.6
45	Pyrene	376	28.0	108	12.4	23.1	1.6
46	Benzybutylphthalate	69.7	50.4	30.9	28.6	15.9	3.2
47	Benzo (a) anthracene	143	<	42.7	<	<	1.6
48	Chrysene	173	<	57.4	<	<	17.6
49	bis(2-ethylhexyl)phthalate	<	<	<	<	<	1.6
50	Di-n-butylphthalate	115	59.3	49.2	43.3	45.5	3.2
51	Benzo (b) fluoranthene	149	<	60.6	<	<	3.2
52	Benzo (k) Fluoranthene	123	<	58.3	<	<	1.6
53	Benzo (a) pyrene	129	<	38.0	<	<	1.6
54	Perylene	42.4	<	11.5	<	<	1.6
55	5-Nitroacenaphthene	<	<	<	<	<	1.6
56	Indeno(1,2,3-cd)pyrene	132	<	43.0	<	<	1.6
57	Dibenzo(ah)anthracene	30.8	<	<	<	<	1.6
58	Benzo(ghi)perylene	180	<	54.4	<	<	1.6
% RECOVERY OF SURROGATES							
d6-Phenol		ND	ND	ND	ND	ND	
d8-Naphthalene		53	31	57	45	34	
d12-Chrysene		90	83	82	77	82	

NOTE: Samples have NOT been corrected for laboratory blank.

** recoveries not possible due to required dilution

BASE NEUTRAL ACID EXTRACTABLES BY "GC/MS"

IDENTIFICATION		LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.			%	
NO	COMPOUND	ug/L		ug/L
1	Camphene	<	62	368
2	bis(2-chloroethyl) ether	<	79	57.6
3	o-Cresol	<	63	1.6
4	m-Cresol	<	73	1.6
5	p-Cresol	<	70	1.6
6	bis(2-chloroisopropyl) ether	<	44	14.4
7	Phenol	<	101	9.6
8	Nitrosodi-n-propylamine	<	102	1.6
9	bis(2-chlorethoxy) methane	<	43	1.6
10	Naphthalene	<	43	1.6
11	2-Chlorophenol	<	135	4.8
12	2,4-Dimethylphenol	<	324	12.8
13	Indole	<	55	3.2
14	2-methylnaphthalene	<	64	3.2
15	1-Methylnaphthalene	<	66	3.2
16	4-chloro-3-methylphenol	<	191	3.2
17	2-chloronaphthalene	<	71	3.2
18	1-chloronaphthelene	<	77	3.2
19	2,6-dichlorophenol	<	138	3.2



BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.			%	
NO	COMPOUND	ug/L		ug/L
20	2,4-dichlorophenol	<	120	3.2
21	Diphenyl ether	<	70	3.2
22	2,4,6-trichlorophenol	<	129	4.8
23	Acenaphthylene	<	68	3.2
24	2,4-dinitrophenol	<	105	44.8
25	2,6-dinitrotoluene	<	60	91.2
26	4-nitrophenol	<	60	192
27	Acenaphthene	<	61	3.2
28	2,3,5-trichlorophenol	<	74	3.2
29	2,4,5-trichlorophenol	<	78	6.4
30	2,3,4-trichlorophenol	<	80	3.2
31	2,4-dinitrotoluene	<	53	97.6
32	Fluorene	<	107	3.2
33	4-chlorophenyl phenyl ether	<	56	3.2
34	4,6-dinitro-o-cresol	<	65	1500
35	Total Diphenylamine	<	49	3.2
36	2,3,5,6-tetrachlorophenol	<	76	3.2
37	2,3,4,6-tetrachlorophenol	<	84	3.2
38	2,3,4,5-tetrachlorophenol	<	67	3.2
39	4-bromophenyl phenyl ether	<	54	3.2



BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.			%	
NO	COMPOUND	ug/L		ug/L
40	Phenanthrene	<	43	1.6
41	Anthracene	<	53	1.6
42	Pentachlorophenol	<	54	1.6
43	Biphenyl	<	78	3.2
44	Fluoranthene	<	66	1.6
45	Pyrene	<	67	1.6
46	Benzybutylphthalate	<	58	3.2
47	Benzo (a) anthracene	<	57	1.6
48	Chrysene	<	58	17.6
49	bis(2-ethylhexyl)phthalate	<	75	1.6
50	Di-n-butylphthalate	0.26	71	3.2
51	Benzo (b) fluoranthene	<	48	3.2
52	Benzo (k) Fluoranthene	<	103	1.6
53	Benzo (a) pyrene	<	75	1.6
54	Perylene	<	87	1.6
55	5-Nitroacenaphthene	<	54	1.6
56	Indeno(1,2,3-cd)pyrene	<	76	1.6
57	Dibenzo(ah)anthracene	<	75	1.6
58	Benzo(ghi)perylene	<	74	1.6
% RECOVERY OF SURROGATES				
d6-Phenol		ND	ND	
d8-Naphthalene		32	42	
d12-Chrysene		51	56	

NOTE: Samples have NOT been corrected for laboratory blank.



POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT
IDENTIFICATION NO.	5178-01	5178-02	5178-03	5178-04	5178-05
	ppb	ppb	ppb	ppb	ppb
Naphthalene	194	248	(10.2)	(17.6)	776
Acenaphthylene	67.2	<	7.70	<	66.0
Acenaphthene	45.1	<	<	15.5	139
Fluorene	127	70.6	(5.6)	22.4	285
Phenanthrene	362	134	36.0	10.3	842
Anthracene	94	30.8	9.90	<	165
Fluoranthene	536	117	78.4	13.6	975
Pyrene	672	127	98.9	<	1060
Benzo (a) anthracene	256	38.4	40.8	<	399
Chrysene	281	47.5	42.4	<	405
Benzo (b) fluoranthene	280	35.8	43.5	<	370
Benzo (k) fluoranthene	225	25.6	34.8	<	265
Benzo (a) pyrene	214	25.1	35.5	<	319
Indeno (1,2,3-cd) pyrene	258	24.7	37.1	<	292
Dibenzo (a,h) anthracene	35.9	<	<	<	19.7
Benzo (ghi) perylene	234	19.5	29.3	<	224
% Recovery Surrogates					
D8-Naphthalene	83	29	55	38	67
D12-Chrysene	133	83	107	105	90

() qualifiers were satisfied

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	TAR NEAR MUN1
IDENTIFICATION NO.	5178-06	5178-07	5178-08	5178-09	5178-10
	ppm	ppm	ppm	ppm	ppm
Naphthalene	43.0	59.1	8.84	39.0	22.3
Acenaphthylene	14.3	<	1.74	13.4	<
Acenaphthene	17.2	23.8	2.53	16.3	<
Fluorene	72.2	97.1	8.28	68.5	34.0
Phenanthrene	57.0	70.7	<	50.1	<
Anthracene	27.9	6.79	<	24.8	<
Fluoranthene	17.0	20.0	<	14.9	5.87
Pyrene	115	37.8	2.02	28.1	12.0
Benzo (a) anthracene	95.6	10.3	<	<	<
Chrysene	8.08	11.1	<	<	<
Benzo (b) fluoranthene	<	<	<	<	<
Benzo (k) fluoranthene	<	<	<	<	<
Benzo (a) pyrene	<	4.80	<	<	<
Indeno (1,2,3-cd) pyrene	<	<	<	<	<
Dibenzo (a,h) anthracene	<	<	<	<	<
Benzo (ghi) perylene	<	<	<	<	<
% Recovery Surrogates					
D8-Naphthalene	**	**	**	**	**
D12-Chrysene	**	**	**	**	**

** = due to nature of the matrix, the following samples have higher MDL's

5178-06: 112 x higher 5178-09: 184 x higher

5178-07: 60 x higher 5178-10: 144 x higher

5178-08: 21 x higher

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	SOIL BHS7-SS3	SOIL MWN3A-SS6	SOIL BHS11-SS5	SOIL BMS6-SS5	SOIL MWN3-SS7
IDENTIFICATION NO.	5178-11	5178-12	5178-13	5178-14	5178-15
	ppb	ppb	ppb	ppb	ppb
Naphthalene	234	<	82.8	<	<
Acenaphthylene	54.8	<	19.6	<	<
Acenaphthene	74.1	<	11.4	<	<
Fluorene	288	<	21.8	<	<
Phenanthrene	456	12.6	119	7.18	12.0
Anthracene	156	<	23.1	<	<
Fluoranthene	300	<	118	<	<
Pyrene	498	32.8	151	18.5	27.3
Benzo (a) anthracene	176	<	53.9	<	<
Chrysene	208	<	66.1	<	<
Benzo (b) fluoranthene	189	<	70.0	<	<
Benzo (k) fluoranthene	115	<	51.7	<	<
Benzo (a) pyrene	148	<	44.0	<	<
Indeno (1,2,3-cd) pyrene	183	<	54.4	<	<
Dibenzo (a,h) anthracene	25.3	<	<	<	<
Benzo (ghi) perylene	173	<	50.4	<	<
% Recovery Surrogates					
D8-Naphthalene	95	33	78	59	46
D12-Chrysene	127	89	115	93	83

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.		%	
	ppb	ppb	ppb
Naphthalene	<	63	24
Acenaphthylene	<	62	9.6
Acenaphthene	<	64	9.6
Fluorene	<	53	9.6
Phenanthrene	<	73	3.2
Anthracene	<	59	4.8
Fluoranthene	<	67	8.0
Pyrene	<	111	8.3
Benzo (a) anthracene	<	117	33.6
Chrysene	<	109	33.6
Benzo (b) fluoranthene	<	120	22.4
Benzo (k) fluoranthene	<	104	22.4
Benzo (a) pyrene	<	67	19.2
Indeno (1,2,3-cd) pyrene	<	108	24.0
Dibenzo (a,h) anthracene	<	103	19.2
Benzo (ghi) perylene	<	94	19.2
% Recovery Surrogates			
D8-Naphthalene	102	99	
D12-Chrysene	168	173	

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT
IDENTIFICATION NO.	5178-01	5178-02	5178-03	5178-04	5178-05	5178-06*
	ppb	ppb	ppb	ppb	ppb	ppb
Phenol	<	<	<	<	<	<
o - Cresol	<	<	<	<	<	<
m - Cresol	<	<	<	<	<	<
p - Cresol	<	<	<	<	<	<
2,6 - Dimethyl phenol	<	<	<	<	<	<
2,5 - Dimethyl phenol	<	<	<	<	<	<
2,4 - Dimethyl phenol	<	<	<	<	<	<
3,5 - Dimethyl phenol	<	<	<	<	<	<
2,3 - Dimethyl phenol	<	<	<	<	<	<
3,4 - Dimethyl phenol	<	<	<	<	<	<
Resorcinol	<	<	<	<	<	<

- * due to the nature of the matrix these samples have higher MDL's
 5178-06: 112 x higher
 5178-07: 60 x higher
 5178-08: 21 x higher
 5178-09: 184 x higher
 5178-10: 144 x higher

** sample 5178-10 is reported in ppm

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	LAKE SEDIMENT	LAKE SEDIMENT	LAKE SEDIMENT	TAR NEAR MUN1	SOIL BHS7-SS3	SOIL MUN3A-SS6
IDENTIFICATION NO.	5178-07*	5178-08*	5178-09*	5178-10*	5178-11	5178-12
	ppb	ppb	ppb	ppb	ppb	ppb
Phenol	<	<	<	278	<	<
o - Cresol	<	<	<	214	<	<
m - Cresol	<	<	<	414	<	<
p - Cresol	<	<	<	385	<	<
2,6 - Dimethyl phenol	<	<	<	<	<	<
2,5 - Dimethyl phenol	<	<	<	75.3	<	<
2,4 - Dimethyl phenol	<	<	<	110	<	<
3,5 - Dimethyl phenol	<	614	<	45.7	<	<
2,3 - Dimethyl phenol	<	<	<	<	<	<
3,4 - Dimethyl phenol	<	885	<	99.1	<	<
Resorcinol	<	<	<	64.6	<	<

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	SOIL BHS11-SS5	SOIL BHS6-SS5	SOIL MWN3-SS7	MDL
IDENTIFICATION NO.	5178-13	5178-14	5178-15	
	ppb	ppb	ppb	ppb
Phenol	<	<	<	8.0
o - Cresol	<	<	<	8.0
m - Cresol	<	<	<	8.0
p - Cresol	<	<	<	8.0
2,6 - Dimethyl phenol	<	<	<	8.0
2,5 - Dimethyl phenol	<	<	<	8.0
2,4 - Dimethyl phenol	<	<	<	8.0
3,5 - Dimethyl phenol	<	<	<	8.0
2,3 - Dimethyl phenol	<	<	<	8.0
3,4 - Dimethyl phenol	<	<	<	8.0
Resorcinol	<	<	<	8.0

VOLATILE ORGANIC COMPOUNDS

IDENTIFICATION	LAB BLANK	LAKE SEDIMENT	TAR	HEAR MUNIT	MDL
IDENTIFICATION NO.		5178-08*	5178-10*		
NO	COMPOUND	ppb	ppb	ppb	ppb
1	Chloromethane	NA	NA	NA	3.6
2	Vinyl chloride	NA	NA	NA	5.0
3	Bromomethane	NA	NA	NA	2.0
4	Chloroethane	NA	NA	NA	1.6
5	Trichlorofluoromethane	<	<	<	3.5
6	Acrolein	<	<	<	2.2
7	1,1-Dichloroethylene	<	<	<	1.6
8	Methylene Chloride	<	3300	3360	1.8
9	Acrylonitrile	<	<	<	2.1
10	trans-1,2-Dichloroethylene	<	<	<	0.7
11	1,1-Dichloroethane	<	<	<	0.5
12	Methyl ethyl ketone	<	4700	7260	1.1
13	Chloroform	1.2	1750	1620	0.4
14	Bromochloromethane	<	<	<	0.2
15	1,1,1-Trichloroethane	<	<	<	0.5
16	Carbon tetrachloride	<	<	<	0.7
17	1,2-Dichloroethane	<	<	<	0.3
18	Benzene	<	<	3380	0.4
19	Trichloroethylene	<	<	<	1.9
20	1,2-Dichloropropane	<	<	<	0.2
21	Bromodichloromethane	<	<	<	0.2
22	2-Chloroethylvinyl ether	<	<	<	0.4
23	trans-1,3-Dichloropropylene	<	<	<	0.3
24	cis-1,3-Dichloropropylene	<	<	<	0.5
25	Toluene	<	1060	25800	0.7
26	1,1,2-Trichloroethane	<	<	<	0.3
27	Tetrachloroethylene	<	<	<	0.8
28	Dibromochloromethane	<	<	<	0.2
29	Ethylene dibromide	<	<	<	0.6
30	Chlorobenzene	<	<	<	0.2
31	m & p Xylene	<	5130	28750	0.6
32	Ethyl benzene	<	2100	17450	2.6
33	Styrene	<	<	<	0.4
34	o-Xylene	<	2880	22700	0.4
35	Bromoform	<	<	<	0.3
36	1,1,2,2-Tetrachloroethane	<	<	<	0.5
37	1,3-Dichlorobenzene	<	<	<	0.2
38	1,4-Dichlorobenzene	<	<	<	0.1
39	1,2-Dichlorobenzene	<	<	<	0.4
% RECOVERY OF SURROGATES					
d5-Bromoethane	101	67	62		
d4-1,2-Dichloroethane	95	89	83		
d8-Toluene	94	71	66		
Bromochloropropane	95	82	117		
d10-Ethylbenzene	97	70	64		

NOTE: Samples have NOT been corrected for laboratory blank.

NA - Not Analyzed

* samples required dilutions therefore MDL's are 500 x those stated



BTXE ANALYSIS

IDENTIFICATION	LAB BLANK	MWN1A *	MWN1B	MWN2A	MWN2B	MWN3A
IDENTIFICATION NO.		5168-01	5168-02	5168-03	5168-04	5168-05
COMPOUND	ppb	ppb	ppb	ppb	ppb	ppb
Benzene	<	215	<	<	<	<
Toluene	<	570	<	<	<	<
m & p Xylene	<	330	<(0.5)	<	<	<
Ethyl benzene	<	210	<(1.0)	<	<	<
o-Xylene	<	155	0.5	<	<	<
% RECOVERY OF SURROGATES						
d5-Bromethane	89	80	95	86	95	89
d4-1,2-Dichloroethane	86	97	92	85	97	91
d8-Toluene	84	88	91	85	92	86
Bromochloropropane	86	122	94	90	94	90
d10-Ethylbenzene	81	90	91	83	90	83

IDENTIFICATION	MWS1A	MWS1B	MWS2	MWS4	TOWN WELL #2	MDL
IDENTIFICATION NO.	5168-06	5168-07	5168-08	5168-09	5168-12	
COMPOUND	ppb	ppb	ppb	ppb	ppb	ppb
Benzene	<	<	<	<	<	0.4
Toluene	<	<	<	<	<	0.7
m & p Xylene	<	<	<	<	<	0.6
Ethyl benzene	<	<	<	<	<	2.6
o-Xylene	<	<	<	<	<	0.4
% RECOVERY OF SURROGATES						
d5-Bromethane	92	92	77	80	100	
d4-1,2-Dichloroethane	91	87	79	86	102	
d8-Toluene	89	86	76	79	97	
Bromochloropropane	90	90	78	83	98	
d10-Ethylbenzene	86	83	74	75	97	

<() Positive identification but below MDL

* Sample required dilution, therefore MDL's are 10x those stated.

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		* MWN1A	MWN1B	MWN2A	MWN2B	MWN3A	MDL
IDENTIFICATION NO.		5168-01	5168-02	5168-03	5168-04	5168-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
1	Camphene	<	<	<	<	<	2.3
2	bis(2-chloroethyl)ether	<	<	<	<	<	0.36
3	o-Cresol	***	***	***	***	***	0.01
4	m-Cresol	***	***	***	***	***	0.01
5	p-Cresol	***	***	***	***	***	0.01
6	bis(2-chloroisopropyl) ether	<	<	<	<	<	0.09
7	Phenol	1470	0.49	8.45	0.92	0.48	0.06
8	Nitrosodi-n-propylamine	<	<	<	<	<	0.01
9	bis(2-chloroethoxy)methane	<	<	<	<	<	0.01
10	Naphthalene	10.6	3.56	<	<	<	0.01
11	2-Chlorophenol	<	<	<	<	<	0.03
12	2,4-Dimethylphenol	(18000)	2.00	0.44	0.56	<	0.08
13	Indole	<	<	<	<	<	0.02
14	2-methylnaphthalene	3.05	<	0.03	0.02	<	0.02
15	1-Methylnaphthalene	2.55	1.88	<	<	<	0.02
16	4-chloro-3-methylphenol	<	<	<	<	<	0.02
17	2-chloronaphthalene	<	<	<	<	<	0.02
18	1-chloronaphthalene	<	<	<	<	<	0.02
19	2,6-dichlorophenol	<	<	<	<	<	0.02

* MDL is 100x higher due to required dilution

*** See Coal Tar Acid analysis for results.

() Quantitation is approximate due to saturation of detector.

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		MWN1A	MWN1B	MWN2A	MWN2B	MWN3A	MDL
IDENTIFICATION NO.		5168-01	5168-02	5168-03	5168-04	5168-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
20	2,4-dichlorophenol	<	<	<	<	<	0.02
21	Diphenyl ether	<	<	<	<	<	0.02
22	2,4,6-trichlorophenol	<	<	<	<	<	0.03
23	Acenaphthylene	<	<	<	<	<	0.02
24	2,4-dinitrophenol	<	<	<	<	<	0.28
25	2,6-dinitrotoluene	<	<	<	<	<	0.57
26	4-nitrophenol	<	<	<	<	<	1.2
27	Acenaphthene	<	0.25	<	<	<	0.02
28	2,3,5-trichlorophenol	<	<	<	<	<	0.02
29	2,4,5-trichlorophenol	<	<	<	<	<	0.04
30	2,3,4-trichlorophenol	<	<	<	<	<	0.02
31	2,4-dinitrotoluene	<	<	<	<	<	0.61
32	Fluorene	<	0.44	<	<	<	0.02
33	4-chlorophenyl phenyl ether	<	<	<	<	<	0.02
34	4,6-dinitro-o-cresol	<	<	<	<	<	9.4
35	Total Diphenylamine	<	0.04	0.14	0.04	<	0.02
36	2,3,5,6-tetrachlorophenol	<	<	<	<	<	0.02
37	2,3,4,6-tetrachlorophenol	<	<	<	<	<	0.02
38	2,3,4,5-tetrachlorophenol	<	<	<	<	<	0.02
39	4-bromophenyl phenyl ether	<	<	<	<	<	0.02

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION	* MW1A	MW1B	MW2A	MW2B	MW3A	MDL
IDENTIFICATION NO.	5168-01	5168-02	5168-03	5168-04	5168-05	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L
40	Phenanthrene	<	<	<	<	0.01
41	Anthracene	<	<	<	<	0.01
42	Pentachlorophenol	<	<	<	<	0.01
43	Biphenyl	<	0.64	<	<	0.02
44	Fluoranthene	<	<	<	<	0.01
45	Pyrene	<	<	<	<	0.01
46	Benzylbutylphthalate	<	0.93	1.16	1.05	0.48
47	Benzo (a) anthracene	<	<	<	<	0.01
48	Chrysene	<	<	<	<	0.11
49	bis(2-ethylhexyl)phthalate	<	<	<	<	0.01
50	Di-n-butylphthalate	9.77	0.38	0.43	0.28	0.26
51	Benzo (b) fluoranthene	<	<	<	<	0.02
52	Benzo (k) Fluoranthene	<	<	<	<	0.01
53	Benzo (a) pyrene	<	<	<	<	0.01
54	Perylene	<	<	<	<	0.01
55	5-Nitroacenaphthene	<	<	<	<	0.01
56	Indeno(1,2,3-cd)pyrene	<	<	<	<	0.01
57	Dibenzo(ah)anthracene	<	<	<	<	0.01
58	Benzo(ghi)perylene	<	<	<	<	0.01
% RECOVERY OF SURROGATES						
d6-Phenol	**	86	94	65	87	
d8-Naphthalene	**	60	71	33	38	
d12-Chrysene	**	110	116	94	95	

** Recoveries not possible due to matrix interference and dilutions.

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		MWS1A	MWS1B	MWS2	MWS4	RIVER NEAR MUN1	MDL
IDENTIFICATION NO.		5168-06	5168-07	5168-08	5168-09	5168-10	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
1	Camphene	<	<	<	<	<	2.3
2	bis(2-chloroethyl)ether	<	<	<	<	<	0.36
3	o-Cresol	***	***	***	***	***	0.01
4	m-Cresol	***	***	***	***	***	0.01
5	p-Cresol	***	***	***	***	***	0.01
6	bis(2-chloroisopropyl) ether	<	<	<	<	<	0.09
7	Phenol	0.31	0.31	0.86	0.34	0.67	0.06
8	Nitrosodi-n-propylamine	<	<	<	<	<	0.01
9	bis(2-chlorethoxy)methane	<	<	<	<	<	0.01
10	Naphthalene	<	<	<	<	<	0.01
11	2-Chlorophenol	<	<	<	<	<	0.03
12	2,4-Dimethylphenol	<	<	<	<	0.73	0.08
13	Indole	<	<	<	<	<	0.02
14	2-methylnaphthalene	<	<	<	<	0.02	0.02
15	1-Methylnaphthalene	<	<	<	<	<	0.02
16	4-chloro-3-methylphenol	<	<	<	<	<	0.02
17	2-chloronaphthalene	<	<	<	<	<	0.02
18	1-chloronaphthalene	<	<	<	<	<	0.02
19	2,6-dichlorophenol	<	<	<	<	<	0.02

*** See Coal Tar Acid analysis for results.

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		MWS1A	MWS1B	MWS2	MWS4	RIVER NEAR MWN1	MDL
IDENTIFICATION NO.		5168-06	5168-07	5168-08	5168-09	5168-10	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
20	2,4-dichlorophenol	<	<	<	<	<	0.02
21	Diphenyl ether	<	<	<	<	<	0.02
22	2,4,6-trichlorophenol	<	<	<	<	<	0.03
23	Acenaphthylene	<	<	<	<	<	0.02
24	2,4-dinitrophenol	<	<	<	<	<	0.28
25	2,6-dinitrotoluene	<	<	<	<	<	0.57
26	4-nitrophenol	<	<	<	<	<	1.2
27	Acenaphthene	<	<	<	<	<	0.02
28	2,3,5-trichlorophenol	<	<	<	<	<	0.02
29	2,4,5-trichlorophenol	<	<	<	<	<	0.04
30	2,3,4-trichlorophenol	<	<	<	<	<	0.02
31	2,4-dinitrotoluene	<	<	<	<	<	0.61
32	Fluorene	<	<	<	<	<	0.02
33	4-chlorophenyl phenyl ether	<	<	<	<	<	0.02
34	4,6-dinitro-o-cresol	<	<	<	<	<	9.4
35	Total Diphenylamine	<	<	<	<	<	0.02
36	2,3,5,6-tetrachlorophenol	<	<	<	<	<	0.02
37	2,3,4,6-tetrachlorophenol	<	<	<	<	<	0.02
38	2,3,4,5-tetrachlorophenol	<	<	<	<	<	0.02
39	4-bromophenyl phenyl ether	<	<	<	<	<	0.02

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		MWS1A	MWS1B	MWS2	MWS4	RIVER NEAR MWN1	MDL
IDENTIFICATION NO.		5168-06	5168-07	5168-08	5168-09	5168-10	
NO	COMPOUND	ug/L	ug/L	ug/L	ug/L	ug/L	ug/L
40	Phenanthrene	<	<	<	<	<	0.01
41	Anthracene	<	<	<	<	<	0.01
2	Pentachlorophenol	<	<	<	<	<	0.01
43	Biphenyl	<	<	<	<	<	0.02
44	Fluoranthene	<	<	<	<	<	0.01
45	Pyrene	<	<	<	<	<	0.01
46	Benzylbutylphthalate	0.67	0.44	0.49	0.33	0.23	0.02
47	Benzo (a) anthracene	<	<	<	<	<	0.01
48	Chrysene	<	<	<	<	<	0.11
49	bis(2-ethylhexyl)phthalate	<	<	<	<	<	0.01
50	Di-n-butylphthalate	0.47	0.29	0.23	0.21	0.51	0.02
51	Benzo (b) fluoranthene	<	<	<	<	<	0.02
52	Benzo (k) fluoranthene	<	<	<	<	<	0.01
53	Benzo (a) pyrene	<	<	<	<	<	0.01
54	Perylene	<	<	<	<	<	0.01
55	5-Nitroacenaphthene	<	<	<	<	<	0.01
56	Indeno(1,2,3-cd)pyrene	<	<	<	<	<	0.01
57	Dibenzo(ah)anthracene	<	<	<	<	<	0.01
58	Benzo(ghi)perylene	<	<	<	<	<	0.01
% RECOVERY OF SURROGATES							
d6-Phenol		84	79	78	75	74	
d8-Naphthalene		36	34	41	42	20	
d12-Chrysene		98	91	88	84	79	

BASE NEUTRAL EXTRACTABLES BY "GC/MS"

IDENTIFICATION		RIVER NEAR MWS1	TOWN WELL #2	LAB BLANK BLANK	RECOVERY SPIKE SPIKE	MDL MDL
IDENTIFICATION NO.		5168-11	5168-12			
NO	COMPOUND	ug/L	ug/L	ug/L	%	ug/L
1	Camphene	<	<	<	62	2.3
2	bis(2-chloroethyl)ether	<	<	<	79	0.36
3	o-Cresol	***	***	<	63	0.01
4	m-Cresol	***	***	<	73	0.01
5	p-Cresol	***	***	<	70	0.01
6	bis(2-chloroisopropyl) ether	<	<	<	44	0.09
7	Phenol	0.52	0.44	<	101	0.06
8	Nitrosodi-n-propylamine	<	<	<	102	0.01
9	bis(2-chloroethoxy)methane	<	<	<	43	0.01
10	Naphthalene	<	<	<	43	0.01
11	2-Chlorophenol	<	<	<	135	0.03
12	2,4-Dimethylphenol	<	<	<	324	0.08
13	Indole	<	<	<	55	0.02
14	2-methylnaphthalene	<	<	<	64	0.02
15	1-Methylnaphthalene	<	<	<	66	0.02
16	4-chloro-3-methylphenol	<	<	<	191	0.02
17	2-chloronaphthalene	<	<	<	71	0.02
18	1-chloronaphthalene	<	<	<	77	0.02
19	2,6-dichlorophenol	<	<	<	138	0.02

*** See Coal Tar Acid Analysis for results.

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		RIVER NEAR MWS1	TOWN WELL #2	LAB BLANK BLANK	RECOVERY SPIKE SPIKE	MDL MDL
IDENTIFICATION NO.		5168-11	5168-12			
NO	COMPOUND	ug/L	ug/L	ug/L	%	ug/L
20	2,4-dichlorophenol	<	<	<	120	0.02
21	Diphenyl ether	<	<	<	70	0.02
22	2,4,6-trichlorophenol	<	<	<	129	0.03
23	Acenaphthylene	<	<	<	68	0.02
24	2,4-dinitrophenol	<	<	<	105	0.28
25	2,6-dinitrotoluene	<	<	<	60	0.57
26	4-nitrophenol	<	<	<	60	1.2
27	Acenaphthene	<	<	<	61	0.02
28	2,3,5-trichlorophenol	<	<	<	74	0.02
29	2,4,5-trichlorophenol	<	<	<	78	0.04
30	2,3,4-trichlorophenol	<	<	<	80	0.02
31	2,4-dinitrotoluene	<	<	<	53	0.61
32	Fluorene	<	<	<	107	0.02
33	4-chlorophenyl phenyl ether	<	<	<	56	0.02
34	4,6-dinitro-o-cresol	<	<	<	65	9.4
35	Total Diphenylamine	<	<	<	49	0.02
36	2,3,5,6-tetrachlorophenol	<	<	<	76	0.02
37	2,3,4,6-tetrachlorophenol	<	<	<	84	0.02
38	2,3,4,5-tetrachlorophenol	<	<	<	67	0.02
39	4-bromophenyl phenyl ether	<	<	<	54	0.02

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		RIVER NEAR MWS1	TOWN WELL #2	LAB BLANK BLANK	RECOVERY SPIKE SPIKE	MDL MDL
IDENTIFICATION NO.		5168-11	5168-12			
NO	COMPOUND	ug/L	ug/L	ug/L	%	ug/L
40	Phenanthrene	<	<	<	43	0.01
41	Anthracene	<	<	<	53	0.01
42	Pentachlorophenol	<	<	<	54	0.01
43	Biphenyl	<	<	<	78	0.02
44	Fluoranthene	<	<	<	66	0.01
45	Pyrene	<	<	<	67	0.01
46	Benzybutylphthalate	0.30	0.12	<	58	0.02
47	Benzo (a) anthracene	<	<	<	57	0.01
48	Chrysene	<	<	<	58	0.11
49	bis(2-ethylhexyl)phthalate	<	<	<	75	0.01
50	Di-n-butylphthalate	0.66	0.47	0.26	71	0.02
51	Benzo (b) fluoranthene	<	<	<	48	0.02
52	Benzo (k) Fluoranthene	<	<	<	103	0.01
53	Benzo (a) pyrene	<	<	<	75	0.01
54	Perylene	<	<	<	87	0.01
55	5-Nitroacenaphthene	<	<	<	54	0.01
56	Indeno(1,2,3-cd)pyrene	<	<	<	76	0.01
57	Dibenzo(ah)anthracene	<	<	<	75	0.01
58	Benzo(ghi)perylene	<	<	<	74	0.01
% RECOVERY OF SURROGATES						
d6-Phenol		102	115	NS	NS	
d8-Naphthalene		18	33	32	42	
d12-Chrysene		88	88	51	56	

NS = Not spiked

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	MW1A *	MW1B	MW2A	MW2B	MW3A	MDL
IDENTIFICATION NO.	5168-01	5168-02	5168-03	5168-04	5168-05	
	ppb	ppb	ppb	ppb	ppb	ppb
Naphthalene	10.5	4.14	0.039	0.035	0.030	0.015
Acenaphthylene	<	<	<	<	<	0.006
Acenaphthene	<	0.32	<	<	<	0.006
Fluorene	<	0.38	<	<	<	0.006
Phenanthrene	<	<	<	<	<	0.002
Anthracene	<	<	<	<	<	0.003
Fluoranthene	<	<	<	<	<	0.005
Pyrene	<	<	<	<	<	0.005
Benzo (a) anthracene	<	<	<	<	<	0.021
Chrysene	<	<	<	<	<	0.021
Benzo (b) fluoranthene	<	<	<	<	<	0.014
Benzo (k) fluoranthene	<	<	<	<	<	0.014
Benzo (a) pyrene	<	<	<	<	<	0.012
Indeno (1,2,3-cd) pyrene	<	<	<	<	<	0.015
Dibenzo (a,h) anthracene	<	<	<	<	<	0.012
Benzo (ghi) perylene	<	<	<	<	<	0.012
% Recovery Surrogates						
D8-Naphthalene	**	65	72	53	73	
D12-Chrysene	**	161	166	141	169	

* MDL is 100x higher due to required dilution.

** Recovery not possible due to required dilution.

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION	MWS1A	MWS1B	MWS2	MWS4	RIVER NEAR MWN1	MDL MDL MDL
IDENTIFICATION NO.	5168-06	5168-07	5168-08	5168-09	5168-10	
	ppb	ppb	ppb	ppb	ppb	ppb
Naphthalene	<	<	0.038	0.078	0.060	0.015
Acenaphthylene	<	<	<	<	<	0.006
Acenaphthene	<	<	<	<	<	0.006
Fluorene	<	<	<	<	<	0.006
Phenanthrene	<	<	<	<	<	0.002
Anthracene	<	<	<	<	<	0.003
Fluoranthene	<	<	<	<	0.008	0.005
Pyrene	<	<	<	<	0.008	0.005
Benzo (a) anthracene	<	<	<	<	<	0.021
Chrysene	<	<	<	<	<	0.021
Benzo (b) fluoranthene	<	<	<	<	<	0.014
Benzo (k) fluoranthene	<	<	<	<	<	0.014
Benzo (a) pyrene	<	<	<	<	<	0.012
Indeno (1,2,3-cd) pyrene	<	<	<	<	<	0.015
Dibenzo (a,h) anthracene	<	<	<	<	<	0.012
Benzo (ghi) perylene	<	<	<	<	<	0.012
% Recovery Surrogates						
D8-Naphthalene	56	71	68	69	86	
D12-Chrysene	130	172	157	134	168	

POLYNUCLEAR AROMATIC HYDROCARBONS BY "GC/MS"

IDENTIFICATION NO.	RIVER NEAR MWS1	TOWN WELL #2	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.	5168-11	5168-12			
	ppb	ppb	ppb	%	ppb
Naphthalene	<	0.032	<	63	0.015
Acenaphthylene	<	<	<	62	0.006
Acenaphthene	<	<	<	64	0.006
Fluorene	<	<	<	53	0.006
Phenanthrene	<	<	<	73	0.002
Anthracene	<	<	<	59	0.003
Fluoranthene	0.010	<	<	67	0.005
Pyrene	0.010	<	<	111	0.005
Benzo (a) anthracene	<	<	<	117	0.021
Chrysene	<	<	<	109	0.021
Benzo (b) fluoranthene	<	<	<	120	0.014
Benzo (k) fluoranthene	<	<	<	104	0.014
Benzo (a) pyrene	<	<	<	67	0.012
Indeno (1,2,3-cd) pyrene	<	<	<	108	0.015
Dibenzo (a,h) anthracene	<	<	<	103	0.012
Benzo (ghi) perylene	<	<	<	94	0.012
% Recovery Surrogates					
D8-Naphthalene	69	82	102	99	
D12-Chrysene	155	168	168	173	

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	MW1A *	MW1B	MW2A	MW2B	MW3A	MDL
IDENTIFICATION NO.	5168-01	5168-02	5168-03	5168-04	5168-05	
	ppb	ppb	ppb	ppb	ppb	ppb
Phenol	638	0.35	0.53	0.68	0.29	0.07
o - Cresol	1820	0.62	0.07	0.33	<	0.07
m - Cresol	(2000)	0.14	<	0.42	<	0.07
p - Cresol	(3700)	0.19	0.12	0.28	<	0.07
2,6 - Dimethyl phenol	5520	1.47	<	<	<	0.07
2,5 - Dimethyl phenol	3420	<	<	0.11	<	0.07
2,4 - Dimethyl phenol	5750	<	<	0.11	<	0.07
3,5 - Dimethyl phenol	4360	2.54	<	0.16	<	0.07
2,3 - Dimethyl phenol	1450	<	<	<	<	0.07
3,4 - Dimethyl phenol	1180	<	<	0.08	<	0.07
Resorcinol	199	<	<	<	<	0.07
% Recovery Surrogate (2-Fluorophenol)	**	85	95	79	85	

* MDL is 100x higher due to required dilution

** Recoveries not possible due to required dilution

() quantitation is approximate due to saturation of detector

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	MWS1A	MWS1B	MWS2	MWS4	RIVER NEAR MWN1	MDL
IDENTIFICATION NO.	5168-06	5168-07	5168-08	5168-09	5168-10	
	ppb	ppb	ppb	ppb	ppb	ppb
Phenol	0.20	0.23	0.57	0.22	0.38	0.07
o - Cresol	<	<	<	<	0.14	0.07
m - Cresol	<	<	<	<	0.28	0.07
p - Cresol	<	<	<	<	0.14	0.07
2,6 - Dimethyl phenol	<	<	<	<	<	0.07
2,5 - Dimethyl phenol	<	<	<	<	0.09	0.07
2,4 - Dimethyl phenol	<	<	<	<	0.11	0.07
3,5 - Dimethyl phenol	<	<	<	<	0.25	0.07
2,3 - Dimethyl phenol	<	<	<	<	<	0.07
3,4 - Dimethyl phenol	<	<	<	<	<	0.07
Resorcinol	<	<	<	<	<	0.07
% Recovery Surrogate (2-Fluorophenol)	82	84	85	82	66	

COAL TAR ACIDS ANALYSIS BY "GC/MS"

IDENTIFICATION	RIVER NEAR MWS1	TOWN WELL #2	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.	5168-11	5168-12			
	ppb	ppb	ppb	%	ppb
Phenol	0.26	0.21	<	90	0.07
o - Cresol	<	<	<	123	0.07
m - Cresol	<	<	<	84	0.07
p - Cresol	<	<	<	91	0.07
2,6 - Dimethyl phenol	<	<	<	17	0.07
2,5 - Dimethyl phenol	<	<	<	51	0.07
2,4 - Dimethyl phenol	<	<	<	75	0.07
3,5 - Dimethyl phenol	0.53	<	<	85	0.07
2,3 - Dimethyl phenol	<	<	<	56	0.07
3,4 - Dimethyl phenol	<	<	<	91	0.07
Resorcinol	<	<	<	89	0.07
% Recovery Surrogate (2-Fluorophenol)	80	88	80	99	

ORGANIC GEOCHEMISTRY LABORATORY
UNIVERSITY OF WATERLOO

FRACTION ORGANIC CARBON
10/10/90

SAMPLE	FOC (%)
BHS3 SS7	0.023
MWS1 SS8	0.038

Appendix F

DESCRIPTION OF THE GROUNDWATER MODEL

F.1 DESCRIPTION OF THE COMPUTER CODE

Flowpath is a combined finite-difference and particle tracking model for the analysis of two-dimensional groundwater flow and time-related capture zones of pumping wells.

Flowpath can model unconfined, confined and leaky aquifers. It accounts for heterogeneous and isotropic aquifer materials, and spatially variable recharge or infiltration.

The model calculates the steady-state hydraulic head distribution, the groundwater velocity field, time-related paths of groundwater particles, and time-related capture zones for pumping wells. Dispersion and diffusion processes are not considered in the particle-tracking computation.

F.2 DESCRIPTION OF THE SOUTH RIVER MODEL

The two-dimension model of the South River aquifer was constructed based on the available geological information. The extent of the aquifer is thought to correspond to the extent of the buried bedrock valley (Section 3.2).

The modelled domain and the model grid are illustrated in Figure F1. The boundaries of the model were constructed as follows:

northeast and east: This corresponds to the shore of Forest Lake. It was modelled as a constant head boundary, with hydraulic head equal to the water elevation in Forest Lake.

northwest and south: This corresponds to the edge of the bedrock valley, and presumably of the aquifer. It was modelled as a "no-flow", or impermeable boundary.

west: this boundary was set as a "no-flow" boundary. It is located far from the areas of interest and is not expected to have significant effect on the model solution in the areas of interest.

The thickness of the aquifer was estimated from onsite monitor well logs, local water well records and geophysical resistivity survey information (see Section 3.2). Figure F2 shows the distribution of aquifer thickness used in the model.

Infiltration rates into the aquifer from precipitation were set at 20 cm/year. This is equivalent to 22% of the annual precipitation of 90 cm/year (Ontario Ministry of Natural Resources, 1984). This is a conservative infiltration value given the permeable nature of the soils onsite.

The pumping rate of the municipal well was calculated by dividing the total volume of water produced from September 1989 to August 1990 by the number of days in that

Figure F1:
Model Simulation Domain and Grid





Figure F2:
Base of Sand Aquifer
(meters below ground surface)



period. This resulted in an average pumping rate of 390 m³/day.

The aquifer was modelled as homogeneous and isotropic, with a hydraulic conductivity of 2×10^{-3} m/s (Section 3.3).


The results of the model are described elsewhere in this report (Section 5.2).

Appendix G

GRAIN SIZE ANALYSES

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN INCHES			U.S. STANDARD SIEVE No			HYDROMETER



SYMBOL	BORING	DEPTH (m)	LL (%)	PI (%)	DESCRIPTION
○	-				FINE TO MEDIUM SAND, TRACE COARSE GRAVEL

Remark : SAMPLE: 6-SS4-BH S4

Project No. 90C247


SOUTH RIVER

ENE

GRAIN SIZE DISTRIBUTION Figure No. 1

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN INCHES			U.S. STANDARD SIEVE No			HYDROMETER




SYMBOL	BORING	DEPTH (m)	LL (%)	PI (%)	DESCRIPTION
O	-				FINE TO MEDIUM SAND, TRACE GRAVEL

Remark : SAMPLE: 14-SS6-S9

Project No. 90C247	SOUTH RIVER
ENE	GRAIN SIZE DISTRIBUTION Figure No. 2

UNIFIED SOIL CLASSIFICATION

COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	
U.S. SIEVE SIZE IN INCHES			U.S. STANDARD SIEVE No.			HYDROMETER



SYMBOL	BORING	DEPTH (m)	LL (%)	PI (%)	DESCRIPTION
○	-				FINE TO MEDIUM SAND

Remark : SAMPLE 15-SS3-SH1

Project No. 90C247

SOUTH RIVER

ENE

GRAIN SIZE DISTRIBUTION Figure No. 3

Appendix H

SUMMARY OF CCME GUIDELINES

TABLE 1: "ABC" VALUES FOR PAH IN SOIL AND GROUNDWATER
AT COAL TAR WASTE SITES

PAH	Conc. in soil (mg/kg dry weight)			Conc. in Groundwater (ug/L)		
	A	B	C	A	B	C
Group 1						
Carcinogenic PAH						
benzo(a)anthracene	0.1	1	10	0.01	0.1	1
benzo(b)fluoranthene	0.1	1	10	0.01	0.1	1
benzo(k)fluoranthene	0.1	1	10	0.01	0.1	1
benzo(a)pyrene	0.1	1	10	0.01	0.1	1
dibenz(a,h)anthracene	0.1	1	10	0.01	0.1	1
indeno(1,2,3-cd)pyrene	0.1	1	10	0.01	0.1	1
Group 2						
Other PAH						
naphthalene	0.1	5	50	0.2	2	20
phenanthrene	0.1	5	50	0.2	2	20
pyrene	0.1	10	100	0.2	2	20

Value A: This value represents the approximate achievable detection limits for PAH in soil.
In groundwater, value A is based on drinking water criteria as described in the bold-faced paragraph on page 36.


Value A-B: The soil or groundwater is slightly contaminated. At this level of contamination, groundwater generally falls within the range of quality standards and criteria where they exist. However, it is worthwhile to investigate possible sources of contamination, especially in the case of groundwater to ascertain whether new contaminants continue to enter the water. This may lead to intervention focusing on the soil, particularly if the water is used for drinking. Usually at this level of soil or groundwater contamination, cleanup will not be necessary. However, should the land be redeveloped for especially sensitive purposes, e.g. residential or farming, it may be necessary to implement certain measures, such as the excavation of surficial layers of soil and/or the addition of a layer of clean soil.

Value B: This value is an intermediate value, approximately 5 to 10 times above value A.

Range B-C: The soil or groundwater is contaminated. At this level contamination of groundwater clearly exceeds drinking water standards where they exist and can no longer be used for that purpose.
Although the soil is contaminated, it will not automatically be cleaned up, unless the effect of contaminants on the groundwater necessitates such work.
However, restrictions on land use may be imposed when this level of contamination is observed in the soil. Restoration work may be necessary before the land is used for farming, residential or recreational purposes. Other less sensitive uses, e.g. industrial, commercial and so forth, may be contemplated without clean up being carried out. In all cases, the extent of the work required, e.g. the depth to which soil must be excavated and so on, will depend upon the nature of the contamination, ultimate land use and the impact on groundwater and the environment in general.

Value C: This value is considered to be the level at which contamination is significant.

Range Above C: The soil or groundwater is contaminated. Groundwater cannot be used for drinking. Unless the water is decontaminated, it will have to be monitored closely. Where the soil is contaminated, all uses of such land will be restricted. A thorough analysis must be conducted; in all likelihood, restoration will have to be undertaken before re-development occurs.



Appendix I

**ANALYTICAL RESULTS,
GROUNDWATER SAMPLES FROM MUNICIPAL WELLS
#1 AND #2,
NOVEMBER 1989**



Municipality/Project:

SOUTH RIVER

Submission: WR12134

TA-04-15-06

Sampling Date(s):

NOV 16, 1989

Program..... 0700801

Agency..... 0102011502

WATER TREATMENT RESEARCH
POLICY & ASSESSMENT UNIT

TECHNICAL ADVISORY

Sampled by: MATTHEW UZA

Date Submitted: 17/11/89,

Date Received: 17/11/89

Mail this copy to

PAULOWSKI, I
WASTE MANAGEMENT
5TH FLOOR, 40 ST CLAIR AVE W
TORONTO ONTARIO

Final reports to UZA, M.
PAULOWSKI, I

URB-DRINKING WATER
WASTE MANAGEMENT

Telephone: 416-235-5823
Telephone: 416-323-5183

Field Sample	Sampling Location	Sampling Location Description	Lab Sample#	Remarks	Sampling	
					Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1			16/11/89	13:35 5
Sample Description		Lab Sample# Remarks				
RAW WATER		M47-0069				
		M47-0077				
		M47-0466				
TESTS REQUESTED:		G+DWAPA				
		G+OPOUP				
		G+OWTRI				
		G+OAPAHX				
		+HGUT				
		G+DWAPA				
		G+OWOC				
		G+MBCOLI				
		+CCNAUR				
		+PHNOL				
		M47-0176				
		OP47-0089				

Sample Class: M

Metals in Water ITC

Results

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER	M47-0176		16/11/89	13:35 5
<hr/>						
Field Sample Number...		1				
Test Description	Units of Measure	M47-0176				
<hr/>						
URANIUM, UNF. TOTAL	UG/L as U (Uranium)	.06<T				
CUUT, UNF. TOTAL	UG/L as Cu (Copper)	.50<T				
NICKEL, UNF. TOTAL	UG/L as Ni (Nickel)	<.10<W				
LEAD, UNF. TOTAL	UG/L as Pb (Lead)	.07<T				
ZINC, UNF. TOTAL	UG/L as Zn (Zinc)	7.50				
IRON, UNF. TOTAL	UG/L as Fe (Iron)	4200.00				
MANGANESE, UNF. TOTAL	UG/L as Mn (Manganese)	76.00				
SILVER, UNF. TOTAL	UG/L as Ag (SILVER)	<.02<W				
ALUMINUM, UNF. TOTAL	UG/L as Al (Aluminum)	13.00				

Sample Class: M Metals in Water ITC
Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Results

Field Sample Number	1
Test Description	
Code, Units of Measure	M47-0176
Method	
ARSENIC, UNF. TOTAL ASUT, UG/L as As (Arsenic) 001CES	<.05<W
BARIUM, UNF. TOTAL BAUT, UG/L as Ba (Barium) 001CES	87.00
BORON, UNF. TOTAL BBUT, UG/L as B (Boron) 001CES	17.00<T
BERYLLIUM, UNF. TOTAL BEUT, UG/L as Be (Beryllium) 001CES	.03<T
CYANIDE, AVAIL., UNF. REACT CCNAUR, MG/L as CN (Cyanide) 303AC2	<.001<W
CADMIUM, UNF. TOTAL CDUT, UG/L as Cd (Cadmium) 001CES	<.05<W
COBALT, UNF. TOTAL COUT, UG/L as Co (Cobalt) 001CES	.39<T
CHROMIUM, UNF. TOTAL CRUT, UG/L as Cr (Chromium) 001CES	.84<T
MERCURY, UNF. TOTAL HGUT, UG/L as Hg (Mercury) 540AF1	<.01<W
MOLYBDENUM, UNF. TOTAL MOUT, UG/L as Mo (Molybdenum) 001CES	.07<T
ANTIMONY, UNF. TOTAL SBUT, UG/L as Sb (Antimony) 001CES	.31
SELENIUM, UNF. TOTAL SEUT, UG/L as Se (Selenium) 001CES	<1.00<W
STRONTIUM, UNF. TOTAL SRUT, UG/L as Sr (Strontium) 001CES	53.00
TITANIUM, UNF. TOTAL TIUT, UG/L as Ti (Titanium) 001CES	13.00
THALLIUM, UNF. TOTAL TLUT, UG/L as Tl (Thallium) 001CES	<.01<W

Sample Class M

Metals in Water

IIC

Results

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample Number...

1

Test Description

Code, Units of Measure

M47-0176

Method

VANADIUM, UNF, TOTAL
VVUT, UG/L as V (Vanadium)
001CES

1.50

Sample Class: W

WATER (GRND/DOMESTIC) WQ

Results

Inquiries at: MIKE RAULINGS
Telephone: 416-235-5880

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER	W47-0069		16/11/89	13:35 5

Field Sample Number...	1
Test Description	W47-0069
Code, Units of Measure	
Method	

CONDUCTIVITY 25C 105.

COND25,UMHO/CM at 25 D.CENT.
002BI2

HARDNESS, TOTAL 19.7

HARDT ,MG/L as CaCO3

CALCIUM, UNF REACTIVE

CAUR ,MG/L as Ca (Calcium)

002CA1

MAGNESIUM, UNF REACTIVE

MGUR ,MG/L as Mg Magnesium

001CA1

SODIUM, UNF REACT.

NAUR ,MG/L as Na (Sodium)

001EA1

ALKALINITY,TOTAL

ALKT ,MG/L as CaCO3

004AT6

PH (-LOG(M+CONCN)))

PH ,DIMENSIONLESS

003AI2

FLUORIDE, UNF REACTIVE

FFIDUR,MG/L as F (Fluoride)

003AC2

CHLORIDE, UNF REACTIVE

CLIDUR,MG/L as Cl- Chloride

004RC2

15.20

.04

6.52

12.8

8.9

1.60

5.2

19.7

105.

Sample Class: W

WATER (GRND/DOMESTIC) WQ

Results

Inquiries at: MIKE RAWLINGS
Telephone: 416-235-5880

Field Sample Number...	1
Test Description	
Code, Units of Measure	U47-0069
Method	

SULPHATE, UNF. REACT.	4.73
SS04UR, MG/L as SO4	
003A10	
TURBIDITY	7.20
TURB, FORMAZIN TURB. UNITS	
002A11	
COLOUR, TRUE	39.5
COLTR, TRUE COLOUR UNITS	
102BC9	
PHOSPHORUS, UNF. TOTAL	<.002(U
PPUT, MG/L as P Phosphorus	
504AC2	
PHOSPHATES, FRAC. REACT.	<.0005(U
PP04FR, MG/L as P Phosphorus	
103DC2	
NITR'N, TOTAL KJELD, UNF. R	.230
NNTKUR, MG/L as N (Nitrogen)	
004AC2	
AMMONIUM, TOTL, FRAC. REAC	.106
NNHTFR, MG/L as N (Nitrogen)	
103DC2	
NITRATES, TOTL, FRAC. REAC	1.700
NNOTFR, MG/L as N (Nitrogen)	
102DC2	
NITRITE, FRAC. REACT.	.0070
NN02FR, MG/L as N (Nitrogen)	
102DC2	
PHENOLICS (UNF. REACTIVE)	<.2(U
PHNOL, UG/L as PHENOL	
002BC2	

Sample Class: ##

DERIVED RESULTS

Results

Inquiries at: WATER QUALITY OFFICE
Telephone: 416-248-3512

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER		DR-CAL	16/11/89	13:35 S

Field Sample Number...	1
Test Description	
Code, Units of Measure	DR-CAL
Method	
LANGELIER'S INDEX	-3.0
LANGI,	

Sample Class: MW

DOMESTIC WATER MICROBIOLOGICAL

Results

Inquiries at: STEVE DEBRECENI/ROSA LEE
Telephone: 416-235-6011

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER	MU47-0466		16/11/89	13:35 5

Field Sample Number...	1
Test Description	
Code, Units of Measure	MU47-0466
Method	
TOTAL COLIFORM MF	0.
TCMF , COUNTS/100	
LF 22	
TOTAL COLIFORM MF BKGD	0.
TCMFBK, COUNTS/100	
LF 22	
FECAL COLIFORM MF	0.
FCMF , COUNTS/100	
TF1 24	

Results

Sample Class: OP

PRIORITY ORGANICS DUO

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER	OP47-0089		16/11/89	13:35 5

Field Sample Number... 1

Test Description
Code, Units of Measure OP47-0089

Method

1,1-DICHLOROETHYLENE X1001P,UG/L Microgram/Litre POC000	<.1<W
DICHLOROMETHANE X1002P,UG/L Microgram/Litre POC000	<.5<W
TRIS-1,2-DICHLOROETHYLENE X1003P,UG/L Microgram/Litre POC000	<.1<W
1,1-DICHLOROETHANE X1004P,UG/L Microgram/Litre POC000	<.1<W
CHLOROFORM X1005P,UG/L Microgram/Litre POC000	<.1<W
1,1,1-TRICHLOROETHANE X1006P,UG/L Microgram/Litre POC000	<.02<W
1,2-DICHLOROETHANE X1007P,UG/L Microgram/Litre POC000	<.05<W
CARBONITEPACHLORIDE X1008P,UG/L Microgram/Litre POC000	<.2<W
BENZENE B2001P,UG/L Microgram/Litre POC000	.05<T

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Sample Class: OP
PRIORITY ORGANICS DUO

Field Sample Number...	1	
Test Description	OP47-0039	
Code, Units of Measure	Method	
1,2-DICHLOROPROPANE X1009P,UG/L Microgram/Litre POC0D0	<.05<u	
TRICHLOROETHYLENE X1010P,UG/L Microgram/Litre POC0D0	<.1<u	
DICHLOROBROMOMETHANE X1011P,UG/L Microgram/Litre POC0D0	<.05<u	
TOLUENE B2002P,UG/L Microgram/Litre POC0D0	<.05<u	
1,1,2-TRICHLOROETHANE X1012P,UG/L Microgram/Litre POC0D0	<.05<u	
CHLORODIBROMOMETHANE X1013P,UG/L Microgram/Litre POC0D0	<.1<u	
TETRACHLOROETHYLENE X1014P,UG/L Microgram/Litre POC0D0	<.05<u	
CHLOROBENZENE X2001P,UG/L Microgram/Litre POC0D0	<.1<u	
TOTAL TRIHALOMETHANES X211TH,UG/L Microgram/Litre POC0D0	<.50<u	
ETHYLBENZENE B2003P,UG/L Microgram/Litre POC0D0	<.05<u	
ETHYLENE DIBROMIDE X2EDB,UG/L Microgram/Litre POC0D0	<.05<u	
P-XYLENE B2004P,UG/L Microgram/Litre POC0D0	<.1<u	
M-XYLENE B2005P,UG/L Microgram/Litre POC0D0	<.1<u	
BROMOFORM X1015P,UG/L Microgram/Litre POC0D0	<.2<u	
O-XYLENE B2006P,UG/L Microgram/Litre POC0D0	<.05<u	

Sample Class: OP

PRIORITY ORGANICS DUO

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Field Sample Number...		1
Test Description	Units of Measure	OP47-0089
Method		
1,1,2,2TETRACHLOROETHANE X1016P,UG/L Microgram/Litre POC00D0		<.05<W APS
1,4-DICHLOROBENZENE X2002P,UG/L Microgram/Litre POC00D0		<.1<W
1,3-DICHLOROBENZENE X2003P,UG/L Microgram/Litre POC00D0		<.1<W
1,2-DICHLOROBENZENE X2004P,UG/L Microgram/Litre POC00D0		<.05<W
STYRENE B2008P,UG/L Microgram/Litre POC00D0		<.05<W

Sample Class: OW

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO. 1 RAW WATER	0W47-0077		16/11/89	13:35 5

Field Sample Number... 1
Test Description
Code, Units of Measure 0W47-0077
Method

AMETRYNE	(50. <W
P2AMET,NG/L (Nanogram/Litre) W01P3V	
PROMETONE	(50. <W
P2PROM,NG/L (Nanogram/Litre) W01P3V	
PROPAZINE	(50. <W
P2PROP,NG/L (Nanogram/Litre) W01P3V	
ATRAZINE	(50. <W
P2ATRA,NG/L (Nanogram/Litre) W01P3V	
PROMETRYNE	(50. <W
P2PROY,NG/L (Nanogram/Litre) W01P3V	
SIMAZINE	(50. <W
P2SIM ,NG/L (Nanogram/Litre) W01P3V	
SENCOR	(100. <W
P2SENC,NG/L (Nanogram/Litre) W01P3V	
BLADEX	(100. <W
P2BLAD,NG/L (Nanogram/Litre) W01P3V	
ATRATONE	(50. <W
P2ATRO,NG/L (Nanogram/Litre) W01P3V	

Sample Class: OW

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number...	1
Test Description	
Code, Units of Measure	OW47-0077
Method	
DETHYLATED ATRAZINE P2DATR, NG/L (Nanogram/Litre) W01P3V	<200. <W
METALACHLOR POMET, NG/L (Nanogram/Litre) W01P3V	<500. <W
LASSO POLASS, NG/L (Nanogram/Litre) W01P3V	<500. <W
DIETHYL SIMAZINE P2DSIM, NG/L (Nanogram/Litre) W01P3V	<200. <W
HEXACHLOROETHANE X2HCE, NG/L (Nanogram/Litre) W04B1X	<1. <W
135-TRICHLOROBENZENE X2135, NG/L (Nanogram/Litre) W04B1X	<5. <W
124TRICHLOROBENZENE X2124, NG/L (Nanogram/Litre) W04B1X	<5. <W
HEXACHLOROBUTADIENE X1HCB0, NG/L (Nanogram/Litre) W04B1X	<1. <W
123TRICHLOROBENZENE X2123, NG/L (Nanogram/Litre) W04B1X	<5. <W
2,4,5-TRICHLOROTOLUENE X2T245, NG/L (Nanogram/Litre) W04B1X	<5. <W
2,6-TRICHLOROTOLUENE X2T236, NG/L (Nanogram/Litre) W04B1X	<5. <W
1235TETRACHLOROBENZENE X21235, NG/L (Nanogram/Litre) W04B1X	<1. <W
1245 TETRACHLOROBENZENE X21245, NG/L (Nanogram/Litre) W04B1X	<1. <W
2,6,8-TRICHLOROTOLUENE X2T26A, NG/L (Nanogram/Litre) W04B1X	<5. <W
1234TETRACHLOROBENZENE X21234, NG/L (Nanogram/Litre) W04B1X	<1. <W

Results
Inquiries at: DAVID HALL
Telephone: 416-235-5910

Sample Class: OW
ORGANIC WATER DUS

Field Sample Number...	1
Test Description	
Code, Units of Measure	OW47-0077
Method	
PENTACHLOROBENZENE	(1. (U
X2PNCB, NG/L (Nanogram/Litre)	
U04B1X	
PCB, TOTAL	(20. (U
P1PCBT, NG/L (Nanogram/Litre)	
U04B1X	
HEXACHLOROBENZENE	(1. (U
X2HCB, NG/L (Nanogram/Litre)	
U04B1X	
HEPTACHLOR	(1. (U
P1HEPT, NG/L (Nanogram/Litre)	
U04B1X	
ALDRIN	(1. (U
P1ALDR, NG/L (Nanogram/Litre)	
U04B1X	
PP-DDE	(1. (U
P1PPDE, NG/L (Nanogram/Litre)	
U04B1X	
MIREX	(5. (U
P1MIRX, NG/L (Nanogram/Litre)	
U04B1X	
A-BHC HEXACHLOROCYCLOHEX	(1. (U
P1BHCA, NG/L (Nanogram/Litre)	
U04B1X	
B-BHC HEXACHLOROCYCLOHEX	(1. (U
P1BHCB, NG/L (Nanogram/Litre)	
U04B1X	
G-BHC HEXACHLOROCYCLOHEX	(1. (U
P1BHCG, NG/L (Nanogram/Litre)	
U04B1X	
A-CHLORDANE	(2. (U
P1CHLA, NG/L (Nanogram/Litre)	
U04B1X	
G-CHLORDANE	(2. (U
P1CHLG, NG/L (Nanogram/Litre)	
U04B1X	
OXYCHLORDANE	(2. (U
P1OCHL, NG/L (Nanogram/Litre)	
U04B1X	
OP-DDT	(5. (U
P1OPDT, NG/L (Nanogram/Litre)	
U04B1X	
PP-DDD	(5. (U
P1PPDD, NG/L (Nanogram/Litre)	
U04B1X	

Sample Class: OW

ORGANIC WATER

DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number...	1
Test Description	
Code, Units of Measure	0U47-0077
Method	
PP-DDT	<5. <U
P1PPDT, NG/L (Nanogram/Litre)	
W04B1X	
DMDT METHOXYCHLOR	<5. <U
P1DMDT, NG/L (Nanogram/Litre)	
W04B1X	
HEPTACHLOREPOXIDE	<1. <U
P1HEPE, NG/L (Nanogram/Litre)	
W04B1X	
ENDOSULFAN I	<2. <U
P1END1, NG/L (Nanogram/Litre)	
W04B1X	
DIELDRIN	<2. <U
P1DIEL, NG/L (Nanogram/Litre)	
W04B1X	
ENDRIN	<5. <U
P1ENDR, NG/L (Nanogram/Litre)	
W04B1X	
ENDOSULFAN II	<5. <U
P1END2, NG/L (Nanogram/Litre)	
W04B1X	
ENDOSULFAN SULPHATE	<5. <U
P1ENDS, NG/L (Nanogram/Litre)	
W04B1X	
OCTACHLOROSTYRENE	<1. <U
X20CST, NG/L (Nanogram/Litre)	
W04B1X	
TOXAPHENE	<500. <U
P1TOX , NG/L (Nanogram/Litre)	
W04B1X	
PHENANTHRENE	<10. <U
B3001X, NG/L (Nanogram/Litre)	
X3H1D1	
ANTHRACENE	<1. <U
B3002X, NG/L (Nanogram/Litre)	
X3H1D1	
FLUORANTHENE	<20. <U
B3003X, NG/L (Nanogram/Litre)	
X3H1D1	
PYRENE	<20. <U
B3004X, NG/L (Nanogram/Litre)	
X3H1D1	
BENZ(A)ANTHRACENE	<20. <U
B3005X, NG/L (Nanogram/Litre)	
X3H1D1	

Sample Class: OW

ORGANIC WATER DUS

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Results

Field Sample Number... 1

Test Description
Code, Units of Measure

0047-0077

Method

CHRYSENE	(50. <U
B3006X,NG/L (Nanogram/Litre)	
X3H1D1	
DIMETH BENZ(A)ANTHRACENE	(5. <U
B3007X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(E)PYRENE	(50. <U
B3008X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(B)FLUORANTHENE	(10. <U
B3010X,NG/L (Nanogram/Litre)	
X3H1D1	
PERYLENE	(10. <U
B3011X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(K)FLUORANTHENE	(1. <U
B3012X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(A)PYRENE	(5. <U
B3013X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(G,H,I)PERYLENE	(20. <U
B3014X,NG/L (Nanogram/Litre)	
X3H1D1	
DIBENZ(A,H)ANTHRACENE	(10. <U
B3015X,NG/L (Nanogram/Litre)	
X3H1D1	
INDENO(1,2,3-C,D)PYRENE	(20. <U
B3016X,NG/L (Nanogram/Litre)	
X3H1D1	
BENZO(B)CHRYSENE	(2. <U
B3017X,NG/L (Nanogram/Litre)	
X3H1D1	
CORONENE	(10. <U
B3019X,NG/L (Nanogram/Litre)	
X3H1D1	

REMARK CODE EXPLANATIONS

RMK

DESCRIPTION

(T A MEASURABLE TRACE AMOUNT: INTERPRET WITH CAUTION
(W NO MEASURABLE RESPONSE (ZERO): (REPORTED VALUE
APS ADDITIONAL PEAK, SMALL, NOT PRIORITY POLLUTANT

*** END OF REPORT ***

Submission: U R 1 2 1 3 5

Municipality/Project: SOUTH RIVER

Sampling Date(s): NOV 16, 1989

Program: 0700301
 Agency: 0102011502

Sampled by: MATTHEW UZA

WATER TREATMENT RESEARCH
 POLICY & ASSESSMENT UNIT

Date Submitted: 17/11/89, Date Received: 17/11/89

Mail this copy to

PAULOWSKI, I
 WASTE MANAGEMENT
 5th FLOOR, 40 ST CLAIR AVE W
 TORONTO ONTARIO

Final reports to UZA, M.
 PAULOWSKI, I

URB-DRINKING WATER
 WASTE MANAGEMENT

Telephone: 416-235-5823
 Telephone: 416-323-5183

Field Sample	Sampling Location	Sampling Location Description	Sampling		
			Date	Time	Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2	16/11/89	14:00	5
Sample Description		Lab Sample#	Remarks	Lab Sample#	Remarks
RAU WATER					
		W47-0067		M47-0174	
		OW47-0075		OP47-0087	
		MJ47-0464			

TESTS REQUESTED: G+DUAPA
 G+OPPOPUP
 G+OUTRI
 G+OAPAHX
 +HGUT

G+DUAPD
 G+OWOC
 G+MBCOLI
 +CCNAUR
 +PINOL

TA-04-15-06

Sample Class: M

Results

Metals in Water ITC

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2 RAW WATER	M47-0174		16/11/89	14:00 5

Field Sample Number...	1
Test Description	M47-0174
Code, Units of Measure	Method
URANIUM, UNF. TOTAL	.03<T
UUUT, UG/L as U (Uranium)	
001CES	
COPPER, UNF. TOTAL	.40<T
CUUT, UG/L as Cu (Copper)	
001CES	
NICKEL, UNF. TOTAL	.11<T
NIUT, UG/L as Ni (Nickel)	
001CES	
LEAD, UNF. TOTAL	.07<T
PBUT, UG/L as Pb (Lead)	
001CES	
ZINC, UNF. TOTAL	6 00
ZNUT, UG/L as Zn (Zinc)	
001CES	
IRON, UNF. TOTAL	3000.00
FEUT, UG/L as Fe (Iron)	
001CES	
MANGANESE, UNF. TOTAL	120.00
MNUT, UG/L as Mn (Manganese)	
001CES	
SILVER, UNF. TOTAL	<.02<W
AGUT, UG/L as Ag (SILVER)	
001CES	
ALUMINIUM, UNF. TOTAL	13.00
ALUT, UG/L as Al (Aluminum)	
001CES	

Sample Class: M

Results

Metals in Water

ITC

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample Number... 1

Test Description
Code, Units of Measure M47-0174
Method

ARSENIC, UNF. TOTAL ASUT ,UG/L as As (Arsenic) 001CES	<.05<W
BARIUM, UNF. TOTAL BAUT ,UG/L as BA (BARIUM) 001CES	71.00
BORON, UNF. TOTAL BBUT ,UG/L as B (Boron) 001CES	19.00<T
BERYLLIUM, UNF. TOTAL BEUT ,UG/L as BE (BERYLLIUM) 001CES	<.01<W
CYANIDE, UNF. REACT CCNAUR, MG/L as CN (Cyanide) 303ACE	<.001<W
CADMIUM, UNF. TOTAL CDUT ,UG/L as Cd (Cadmium) 001CES	<.05<W
COBALT, UNF. TOTAL COUT ,UG/L as Co (Cobalt) 001CES	.47<T
CHROMIUM, UNF. TOTAL CRUT ,UG/L as Cr (Chromium) 001CES	.52<T
MERCURY, UNF. TOTAL HGUT ,UG/L as Hg (Mercury) 540AF1	<.01<W
MOLYBDENUM, UNF. TOTAL MOUT ,UG/L as Mo Molybdenum 001CES	<.02<W
ANTIMONY, UNF. TOTAL SBUT ,UG/L as Sb (Antimony) 001CES	.29
SELENIUM, UNF. TOTAL SEUT ,UG/L as Se (Selenium) 001CES	<1.00<W
STRONTIUM, UNF. TOTAL SRUT ,UG/L as Sr (STRONTIUM) 001CES	49.00
TITANIUM, UNF. TOTAL TIUT ,UG/L as Ti (TITANIUM) 001CES	10.00
THALLIUM, UNF. TOTAL TLUT ,UG/L as Tl (THALLIUM) 001CES	<.01<W

Environment Ontario
FINAL REPORT

UR12135

SOUTH RIVER

Page 4
Printed 18/12/89

Sample Class: M

Metals in Water

ITC

Results

Inquiries at: RAY MEVICARS
Telephone: 416-235-5860

Field Sample Number... 1
Test Description
Code, Units of Measure
Method
VANADIUM, UNF, TOTAL
VVUT ,UG/L as V (Vanadium)
001CES

M47-0174

.43<T

Inquiries at: MIKE RAWLINGS
Telephone: 416-235-5880

Field Sample Number...	1
Test Description	
Code, Units of Measure	U47-0067
Method	
CONDUCTIVITY 25C	101.
COND25,UMHO/CM at 25 D.CENT.	
0028I2	
HARDNESS, TOTAL	20.2
HARDT ,MG/L as CaCO3	
CALC01	
CALCIUM, UNF. REACTIVE	5.4
CAUR ,MG/L as Ca (Calcium)	
002CA1	
MAGNESIUM, UNF. REACTIVE	1.65
MGUR ,MG/L as Mg	
001CA1	
SODIUM, UNF. REACT.	7.4
NAUR ,MG/L as Na (Sodium)	
001EA1	
ALKALINITY, TOTAL	9.3
ALKT ,MG/L as CaCO3	
004AT6	
PH (-LOG(H+(CONCN)))	6.55
PH ,DIMENSIONLESS	
003AI2	
FLUORIDE, UNF. REACTIVE	.04
FFIDUR,MG/L as F (Fluoride)	
003AC2	
CHLORIDE, UNF. REACTIVE	15.90
CLIDUR,MG/L as Cl- Chloride	
004RC2	

Sample Class: W

WATER (GRND/DOMESTIC) WQ

Results

Inquiries at: MIKE RAWLINGS
Telephone: 416-235-5880

Field Sample Number...	1
Test Description	
Code, Units of Measure	U47-0067
Method	
SULPHATE, UNF.REACT. Sulphate	
SS04UR,MG/L as SO4 003A10	7.82
TURBIDITY	
TURB ,FORMAZIN TURB. UNITS	4.90
COLOUR, TRUE	
COLTR ,TRUE COLOUR UNITS	50.5
PHOSPHORUS, UNF.TOTAL	
PPUT ,MG/L as P Phosphorus	<.002<U
504AC2	
PHOSPHATES, FRAC.REACT.	
PP04FR,MG/L as P Phosphorus	<.0005<U
103DC2	
NITR'N,TOTAL KJELD,UNF.R	.100
NNTKUR,MG/L as N (Nitrogen)	
004AC2	
AMMONIUM,TOTL, FRAC.REAC	.044
NNHTFR,MG/L as N (Nitrogen)	
103DC2	
NITRATES TOTL, FRAC.REAC	1.120
NNOTFR,MG/L as N (Nitrogen)	
102DC2	
NITRITE, FRAC.REACT.	.0070
NN02FR,MG/L as N (Nitrogen)	
102DC2	
PHENOLICS (UNF.REACTIVE)	.6<T
PHNOL ,UG/L as PHENOL	
002BC2	

Sample Class: ##
DERIVED RESULTS

Results

Inquiries at: WATER QUALITY OFFICE
Telephone: 416-248-3512

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2 RAW WATER		DR-CAL	16/11/89	14:00 5

Field Sample Number... 1
Test Description
Code, Units of Measure Method
DR-CAL

-3.1

LANGELIER'S INDEX
LANGI ,

Sample Class: MW

Results

DOMESTIC WATER MICROBIOL

Inquiries at: STEVE DEBRECENI/ROSA LEE
Telephone: 416-235-6011

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2 RAW WATER	MW47-0464		16/11/89	14:00 5

Field Sample Number...	1
Test Description	
Code, Units of Measure	MW47-0464
Method	

TOTAL COLIFORM MF	0.
TCMF ,COUNTS/100	
LF 22	
TOTAL COLIFORM MF BKGD	0.
TCMFBK,COUNTS/100	
LF 22	
FECAL COLIFORM MF	0.
FCMF ,COUNTS/100	
TF1 24	

Sample Class: OP

PRIORITY ORGANICS DUO

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2 RAU WATER	OP47-0087		16/11/89	14:00 5

Field Sample Number...

Test Description	Code	Units of Measure	Method
1,1-DICHLOROETHYLENE	X1001P, No Units available		ILA
DICHLOROMETHANE	X1002P, No Units available		ILA
TRS-1,2-DICHLOROETHYLENE	X1003P, No Units available		ILA
1,1-DICHLOROETHANE	X1004P, No Units available		ILA
CHLOROFORM	X1005P, No Units available		ILA
1,1,1-TRICHLOROETHANE	X1006P, No Units available		ILA
1,2-DICHLOROETHANE	X1007P, No Units available		ILA
CARBON TETRACHLORIDE	X1008P, No Units available		ILA
BENZENE	B2001P, No Units available		ILA

Sample Class: OP

PRIORITY ORGANICS DWQ

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

1

Field Sample Number...	1
Test Description	
Code, Units of Measure	OP47-0087
Method	

1,2-DICHLOROPROPANE
X1009P, No Units available

ILA

TRICHLOROETHYLENE
X1010P, No Units available

ILA

DICHLOROBROMOMETHANE
X1011P, No Units available

ILA

TOLUENE
B2002P, No Units available

ILA

1,1,2-TRICHLOROETHANE
X1012P, No Units available

ILA

CHLORODIBROMOMETHANE
X1013P, No Units available

ILA

TETRACHLOROETHYLENE
X1014P, No Units available

ILA

CHLOROBENZENE
X2001P, No Units available

ILA

TOTAL TRIHALOMETHANES
X21THM, No Units available

ILA

ETHYLBENZENE
B2003P, No Units available

ILA

ETHYLENE DIBROMIDE
X2EDB, No Units available

ILA

P-XYLENE
B2004P, No Units available

ILA

M-XYLENE
B2005P, No Units available

ILA

BROMOFORM
X1015P, No Units available

ILA

O-XYLENE
B2006P, No Units available

ILA

Sample Class: OP

PRIORITY ORGANICS

DWO

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Field Sample Number...	1
Test Description	
Code, Units of Measure	OP47-0087
Method	
1,1,2,2-TETRACHLOROETHANE X1016P, No Units available	ILA
1,4-DICHLOROBENZENE X2002P, No Units available	ILA
1,3-DICHLOROBENZENE X2003P, No Units available	ILA
1,2-DICHLOROBENZENE X2004P, No Units available	ILA
STYRENE B2008P, No Units available	ILA

Sample Class: OW

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time	Zone
1	CODE NOT GIVEN	SOUTH RIVER WELL NO.2 RAW WATER	0W47-0075		16/11/89	14:00	5

Field Sample Number...	1
Test Description	0W47-0075
Code, Units of Measure	
Method	

AMETRYNE	(50. (W
P2AHET, NG/L (Nanogram/Litre)	
W01P3V	
PROMETONE	(50. (W
P2PRON, NG/L (Nanogram/Litre)	
W01P3V	
PROPACINE	(50. (W
P2PROP, NG/L (Nanogram/Litre)	
W01P3V	
ATRAZINE	(50. (W
P2ATRA, NG/L (Nanogram/Litre)	
W01P3V	
PROMETRYNE	(50. (W
P2PROY, NG/L (Nanogram/Litre)	
W01P3V	
SIMAZINE	(50. (W
P2SIM , NG/L (Nanogram/Litre)	
W01P3V	
SENCOR	(100. (W
P2SENC, NG/L (Nanogram/Litre)	
W01P3V	
BLADAX	(100. (W
P2BLAD, NG/L (Nanogram/Litre)	
W01P3V	
ATRATONE	(50. (W
P2ATRO, NG/L (Nanogram/Litre)	
W01P3V	

Sample Class: OW

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number...	1
Test Description	OU47-0075
Code, Units of Measure	Method
DETHYLATED ATRAZINE	
P20ATR,NG/L (Nanogram/Litre)	(200. <u
W01P3V	
METALACHLOR	
P0MET ,NG/L (Nanogram/Litre)	(500. <u
W01P3V	
LASSO	
POLASS,NG/L (Nanogram/Litre)	(500. <u
W01P3V	
DIETHYL SIMAZINE	
P2DSIM,NG/L (Nanogram/Litre)	(200. <u
W01P3V	
HEXACHLOROETHANE	
X2HCE ,NG/L (Nanogram/Litre)	(1. <u
W04B1X	
135-TRICHLOROBENZENE	
X2135 ,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
124TRICHLOROBENZENE	
X2124 ,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
HEXACHLOROBUTADIENE	
X1HCBD,NG/L (Nanogram/Litre)	(1. <u
W04B1X	
123TRICHLOROBENZENE	
X2123 ,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
2,4,5-TRICHLOROTOLUENE	
X21245,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
2,3,6-TRICHLOROTOLUENE	
X21236,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
1235TETRACHLOROBENZENE	
X21235,NG/L (Nanogram/Litre)	(1. <u
W04B1X	
1245 TETRACHLOROBENZENE	
X21245,NG/L (Nanogram/Litre)	(1. <u
W04B1X	
2,6,a-TRICHLOROTOLUENE	
X2126A,NG/L (Nanogram/Litre)	(5. <u
W04B1X	
1234TETRACHLOROBENZENE	
X21234,NG/L (Nanogram/Litre)	(1 <u
W04B1X	

Sample Class: OW

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number...	1
Test Description	
Code, Units of Measure	OW47-0075
Method	
PENTACHLOROBENZENE	(1. (W
X2PNCB, NG/L (Nanogram/Litre)	W04B1X
PCB, TOTAL	(20. (W
PIPCBT, NG/L (Nanogram/Litre)	W04B1X
HEXACHLOROBENZENE	(1. (W
X2HCB, NG/L (Nanogram/Litre)	W04B1X
HEPTACHLOR	(1. (W
PIHEPT, NG/L (Nanogram/Litre)	W04B1X
ALDRIN	(1. (W
PIALDR, NG/L (Nanogram/Litre)	W04B1X
PP-DDE	(1. (W
PIPPDE, NG/L (Nanogram/Litre)	W04B1X
MIREX	(5. (W
PIMIRX, NG/L (Nanogram/Litre)	W04B1X
A-BHC HEXACHLOROCYCLOHEX	(1. (W
PIBHCA, NG/L (Nanogram/Litre)	W04B1X
B-BHC HEXACHLOROCYCLOHEX	(1. (W
PIBHCB, NG/L (Nanogram/Litre)	W04B1X
G-BHC HEXACHLOROCYCLOHEX	(1. (W
PIBHCG, NG/L (Nanogram/Litre)	W04B1X
A-CHLORDANE	(2. (W
PICHLA, NG/L (Nanogram/Litre)	W04B1X
G-CHLORDANE	(2. (W
PICHLG, NG/L (Nanogram/Litre)	W04B1X
OXYCHLORDANE	(2. (W
PIOCHL, NG/L (Nanogram/Litre)	W04B1X
OP-DDT	(5. (W
PIOPDT, NG/L (Nanogram/Litre)	W04B1X
PP-DDD	(5. (W
PIPPDD, NG/L (Nanogram/Litre)	W04B1X

Sample Class: OW DWS Results Inquiries at: DAVID HALL
ORGANIC WATER Telephone: 416-235-5910

Field Sample Number... 1

Test Description
Code, Units of Measure 0U47-0075

Method

PP-DDT PIPPDT,NG/L (Nanogram/Litre) U04B1X	<5.<U
DMDT METHOXYCHLOR PIDMDT,NG/L (Nanogram/Litre) U04B1X	<5.<U
HEPTACHLOREPOXIDE PIHEPE,NG/L (Nanogram/Litre) U04B1X	<1.<U
ENDOSULFAN I PIENDI,NG/L (Nanogram/Litre) U04B1X	<2.<U
DIELDRIN PIDIEL,NG/L (Nanogram/Litre) U04B1X	<2.<U
ENDRIN PIENDR,NG/L (Nanogram/Litre) U04B1X	<5.<U
ENDOSULFAN II PIENDS,NG/L (Nanogram/Litre) U04B1X	<5.<U
ENDOSULFAN SULPHATE PIENDS,NG/L (Nanogram/Litre) U04B1X	<5.<U
OCTACHOROSTYRENE X2OCST,NG/L (Nanogram/Litre) U04B1X	<1.<U
TOXAPHENE PITOX,NG/L (Nanogram/Litre) U04B1X	<500.<U
PHENANTHRENE B3001X,NG/L (Nanogram/Litre) X3H1D1	<10.<U
ANTHRACENE B3002X,NG/L (Nanogram/Litre) X3H1D1	<1.<U
FLUORANTHENE B3003X,NG/L (Nanogram/Litre) X3H1D1	<20.<U
PYRENE B3004X,NG/L (Nanogram/Litre) X3H1D1	<20.<U
BENZ(A)ANTHRACENE B3005X,NG/L (Nanogram/Litre) X3H1D1	<20.<U

Sample Class: 0W

ORGANIC WATER

DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number...		1
Test Description	Units of Measure	0W47-0075
Method		
CHRYSENE		<50. <W
B3006X, NG/L (Nanogram/Litre)	X3H1D1	
DIMETH. BENZ(A)ANTHRACENE		<5. <W
B3007X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(E)PYRENE		<50. <W
B3008X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(B)FLUORANTHENE		<10. <W
B3010X, NG/L (Nanogram/Litre)	X3H1D1	
PERYLENE		<10. <W
B3011X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(K)FLUORANTHENE		<1. <W
B3012X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(A)PYRENE		<5. <W
B3013X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(G, H, I)PERYLENE		<20. <W
B3014X, NG/L (Nanogram/Litre)	X3H1D1	
DIBENZ(A, H)ANTHRACENE		<10. <W
B3015X, NG/L (Nanogram/Litre)	X3H1D1	
INDENO(1, 2, 3-C, D)PYRENE		<20. <W
B3016X, NG/L (Nanogram/Litre)	X3H1D1	
BENZO(B)CHRYSENE		<2. <W
B3017X, NG/L (Nanogram/Litre)	X3H1D1	
CORONENE		<10. <W
B3019X, NG/L (Nanogram/Litre)	X3H1D1	

REMARK CODE EXPLANATIONS

RMK

DESCRIPTION

ILA NO DATA: SAMPLE SPOILED IN LABORATORY ACCIDENT.
(T A MEASURABLE TRACE AMOUNT: INTERPRET WITH CAUTION
(U NO MEASURABLE RESPONSE (ZERO): (REPORTED VALUE

*** END OF REPORT ***

Sample Class: M

Metals in Water ITC

Field Sample Sampling Location

Sampling Location Description

LAB Sample#

Remarks

Sampling Date

Time Zone

2 CODE NOT GIVEN

SOUTH RIVER
TREATED WATER USING WELL NO.2

M47-0175

16/11/89 14:30 5

Field Sample Number... 2

Test Description

Code, Units of Measure

M47-0175

Method

URANIUM, UNF TOTAL

.07CT

UUUT ,UG/L as U (Uranium)
00ICES

COPPER, UNF TOTAL

3.30

CUUT ,UG/L as Cu
(Copper)
00ICES

NICKEL, UNF TOTAL

.11CT

NIUT ,UG/L as Ni
(Nickel)
00ICES

LEAD, UNF TOTAL

.38

PBUT ,UG/L as Pb
(Lead)
00ICES

ZINC, UNF TOTAL

28.00

ZNUZ ,UG/L as Zn
(Zinc)
00ICES

IRON, UNF TOTAL

2900.00

FEUT ,UG/L as Fe
(Iron)
00ICES

MANGANESE, UNF TOTAL

120.00

MNUT ,UG/L as Mn
(Manganese)
00ICES

SILVER, UNF TOTAL

(.02CT

AGUT ,UG/L as Ag
(SILVER)
00ICES

ALUMINUM, UNF TOTAL

16.00

ALUT ,UG/L as Al
(Aluminum)
00ICES

Sample Class M

Metals in Water

ITC

Results

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample Number 2

Test Description Code, Units of Measure M47-0175

Method

ARSENIC, UNF TOTAL ASUT ,UG/L as As (Arsenic) 001CES	<.05<U
BARIUM, UNF TOTAL (BARIUM) BAUT ,UG/L as Ba 001CES	72.00
BORON, UNF TOTAL (Boron) BBUT ,UG/L as B 001CES	18.00<T
BERYLLIUM, UNF TOTAL (BERYLLIUM) BEUT ,UG/L as Be 001CES	.02<T
CYANIDE, AVAIL., UNF REACT (CYANIDE) CCNAUR, MG/L as CN 303AC2	<.001<U
CADMIUM, UNF TOTAL (Cadmium) CDUT ,UG/L as Cd 001CES	<.05<U
COBALT, UNF TOTAL (Cobalt) COUT ,UG/L as Co 001CES	.49<T
CHROMIUM, UNF TOTAL (Chromium) CRUT ,UG/L as Cr 001CES	.37<T
MERCURY, UNF TOTAL (Mercury) HGUT ,UG/L as Hg 540AF1	<.01<U
MOLYBDENUM, UNF TOTAL (Molybdenum) MOUT ,UG/L as Mo 001CES	.04<T
ANTIMONY, UNF TOTAL (Antimony) SBUT ,UG/L as Sb 001CES	.29
SELENIUM, UNF TOTAL (Selenium) SEUT ,UG/L as Se 001CES	<1.00<U
STRONTIUM, UNF TOTAL (Strontium) SPUT ,UG/L as Sr 001CES	47.00
TITANIUM, UNF TOTAL (Titanium) TIUT ,UG/L as Ti 001CES	14.00
THALLIUM, UNF TOTAL (Thallium) TLUT ,UG/L as Tl 001CES	<.01<U

Sample Class M

Metals in Water ITC

Results

Inquiries at: RAY McVICARS
Telephone: 416-235-5860

Field Sample Number... 2

Test Description
Code... Units of Measure Method M47-0175

VANADIUM, UNF, TOTAL .48CT

VVUT ,UG/L as V (Vanadium)
001CES

Sample Class W

Results

WATER (LAND/DOMESTIC) UQ

Inquiries at: MIKE RAWLINGS
Telephone: 416-235-5880

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
2	CODE NOT GIVEN	SOUTH RIVER TREATED WATER USING WELL NO 2	U47-0068		16/11/89	14:30 5
Field Sample Number	2					
Test Description	U47-0068					
Code	Units of Measure	Method				
CONDUCTIVITY 25C						
COND5,UMHO/CM at 25 D CENT						
002B12						
HARDNESS, TOTAL						
HARDY ,MG/L as CaCO3						
CALC01						
CALCIUM, UNF REACTIVE						
CAUP ,MG/L as Ca (Calcium)						
002CA1						
MAGNESIUM, UNF REACTIVE						
MGUP ,MG/L as Mg Magnesium						
001CA1						
SODIUM, UNF REACT						
NAUR ,MG/L as Na (Sodium)						
001EA1						
ALKALINITY, TOTAL						
ALKT ,MG/L as CaCO3						
004AT6						
PH (-LOG(H+(CONCH)))						
PH ,DIMENSIONLESS						
003AI2						
FLUORIDE, UNF REACTIVE						
FF1DUR,MG/L as F (Fluoride)						
003AC2						
CHLORIDE, UNF REACTIVE						
CL1DUR,MG/L as Cl- Chloride						
004BC2						

Sample Class W
WATER (GRND/DOMESTIC) WQ
Inquiries at: MIKE RAWLINGS
Telephone: 416-235-5880

Results

Field Sample Number 2

Test Description Code, Units of Measure Method U47-0068

SULPHATE, UNF REACT SS04UR, MG/L as SO4	7.67	Sulphate 003A10
TURBIDITY TURB, FORMAZIN TURB UNITS	1.40	002A11
COLOUR, TRUE COLTR, TRUE COLOUR UNITS	9.5	
PHOSPHORUS, UNF TOTAL PPUT, MG/L as P Phosphorus	< 0.002	102BC9
PHOSPHATES, FRAC REACT PPO4FR, MG/L as P Phosphorus	< 0.0005	504AC2
NITR-N, TOTAL KJELD, UNF R NNIKUR, MG/L as N (Nitrogen)	0.130	103BC2
AMMONIUM, TOTL, FRAC REAC NNHTFR, MG/L as N (Nitrogen)	0.026	004AC2
NITRATES, TOTL, FRAC REAC NNOTFR, MG/L as N (Nitrogen)	1.130	103DC2
NITRITE, FRAC REACT NNOSFR, MG/L as N (Nitrogen)	0.040	102DC2
PHENOLICS (UNF REACTIVE) PHNOL, MG/L as PHENOL	< 0.6	002BC2

Printed

SOUTH RIVER

UR12131

Environment Ontario
FINAL REPORT

Results

Inquiries at: WATER QUALITY OFFICE
Telephone: 416-248-3512

Sample Class **
DERIVED RESULTS

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
2	CODE NOT GIVEN	SOUTH RIVER TREATED WATER USING WELL NO.2	DR-CAL		16/11/89	14:30 S

Field Sample Number	2
Test Description	DR-CAL
Code, Units of Measure	
Method	-3.1
LANGELIER'S INDEX	
LANGI	

Sample Class MU

DOMESTIC WATER MICROBIOL

Results

Inquiries at: STEVE DEBRECENI/ROSA LEE
Telephone: 416-235-6011

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
2	CODE NOT GIVEN	SOUTH RIVER TREATED WATER USING WELL NO 2	MU47-0465		16/11/89	14:30 5

2

Field Sample Number.
Test Description,
Code, Units of Measure Method

MU47-0465

0.

TOTAL COLIFORM MF
TCMF, COUNTS/100 MILLILITRE
LF 22

0

TOTAL COLIFORM MF BKGD
TCMFBK, COUNTS/100 MILLILITRE
LF 22

2

STANDARD PLATE COUNT MF
HBSMF, COUNTS/MILLILITRE
SF 48

Environment Ontario
FINAL REPORT

Sample Class GP

PRIORITY ORGANIC DUO

UR12131

SOUTH RIVER

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Printed 15/01/90

Page 9

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
P CODE NOT GIVEN		SOUTH RIVER TREATED WATER USING WEIL NO 2	OP47-0088		16/11/89	14:30 5
Field Sample Number	2					
Test Description	OP47-0088					
Code, Units of Measure	Method					
1,1-DICHLOROETHYLENE						
X1001P, UG/L	Microgram/Litre					
	P0C0D0					
DICHLOROMETHANE						
X1002P, UG/L	Microgram/Litre					
	P0C0D0					
TRIS-1,2-DICHLOROETHYLENE						
X1003P, UG/L	Microgram/Litre					
	P0C0D0					
1,1-DICHLOROETHANE						
X1004P, UG/L	Microgram/Litre					
	P0C0D0					
CHLOROFORM						
X1005P, UG/L	Microgram/Litre					
	P0C0D0					
1,1,1-TRICHLOROETHANE						
X1006P, UG/L	Microgram/Litre					
	P0C0D0					
1,2-DICHLOROETHANE						
X1007P, UG/L	Microgram/Litre					
	P0C0D0					
CARBON TETRACHLORIDE						
X1008P, UG/L	Microgram/Litre					
	P0C0D0					
BENZENE						
B2001P, UG/L	Microgram/Litre					
	P0C0D0					

Sample Class OP
PRIOITY ORGANICS DUO
Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

Results

Field Sample Number	2
Test Description	
Code, Units of Measure	OP47-0088
Method	
1,2-DICHLOROPROPANE X1009P,UG/L Microgram/Litre POC000	< .05<W
TRICHLOROETHYLENE X1010P,UG/L Microgram/Litre POC000	< .1<W
DICHLORODIFLUOROMETHANE X1011P,UG/L Microgram/Litre POC000	< .05<W
TOLUENE B2002P,UG/L Microgram/Litre POC000	< .05<W
1,1,2-TRICHLOROETHANE X1012P,UG/L Microgram/Litre POC000	< .05<W
CHLORODIFLUOROMETHANE X1013P,UG/L Microgram/Litre POC000	< .1<W
TETRACHLOROETHYLENE X1014P,UG/L Microgram/Litre POC000	< .05<W
CHLOROBENZENE X200-P,UG/L Microgram/Litre POC000	< .1<W
TOTAL TRIHALOMETHANES X21THM,UG/L Microgram/Litre POC000	< .50<W
ETHYLBENZENE B2003P,UG/L Microgram/Litre POC000	< .05<W
ETHYLENE DIBROMIDE X2EDB,UG/L Microgram/Litre POC000	< .05<W
P-XYLENE B2004P,UG/L Microgram/Litre POC000	< .1<W
M-XYLENE B2005P,UG/L Microgram/Litre POC000	< .1<W
BROMOFORM X1015P,UG/L Microgram/Litre POC000	< .2<W
O-XYLENE B2006P,UG/L Microgram/Litre POC000	< .05<W

ENVIRONMENTAL ORGANIZATION
FINAL REPORT

Sample Class OP

PRIORITY ORGANICS DWQ

UR12131

SOUTH RIVER

Page 11
Printed 15/01/90

Results

Inquiries at: BILL BERG / WALTER OFFENBACHER 235-5908
Telephone: 416-235-5907

2

Field Sample Number

OP47-0088

Test Description

Code Units of Measure Method

1,1,2,2-TETRACHLOROETHANE		< .05 <u>u</u>
X1015P, 0.05/L Microgram/Litre		APS
p0C0D0		
1,4-DICHLOROBENZENE		< .1 <u>u</u>
X2002P, 0.05/L Microgram/Litre		
p0C0D0		
1,3-DICHLOROBENZENE		< .1 <u>u</u>
X2003P, 0.05/L Microgram/Litre		
p0C0D0		
1,2-DICHLOROBENZENE		< .05 <u>u</u>
X2004P, 0.05/L Microgram/Litre		
p0C0D0		
STYRENE		.05 <u>u</u>
B2003P, 0.05/L Microgram/Litre		UCS
p0C0D0		

Sample Class OU
ORGANIC WATER DUS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample	Sampling Location	Sampling Location Description	LAB Sample#	Remarks	Sampling Date	Time Zone
E CODE NOT GIVEN		SOUTH RIVER TREATED WATER USING WFL NO 2	0W47-0076		16/11/89	14:30 5

Field Sample Number	2
Test Description	0W47-0076
Code, Units of Measure	Method

AMETRYNE	(50. <U
P2AMET, NG/L (Nanogram/Litre)	
W01P3V	
PROMETONE	(50. <U
P2PROM, NG/L (Nanogram/Litre)	
W01P3V	
PROPAZINE	(50. <U
P2PROP, NG/L (Nanogram/Litre)	
W01P3V	
ATRAZINE	(50. <U
P2ATRA, NG/L (Nanogram/Litre)	
W01P3V	
PROMETRYNE	(50. <U
P2PROY, NG/L (Nanogram/Litre)	
W01P3V	
SIMAZINE	(50. <U
P2SIM , NG/L (Nanogram/Litre)	
W01P3V	
SENCOR	(100. <U
P2SENC, NG/L (Nanogram/Litre)	
W01P3V	
BLADEX	(100. <U
P2BLAD, NG/L (Nanogram/Litre)	
W01P3V	
ATRATONE	(50. <U
P2ATRO, NG/L (Nanogram/Litre)	
W01P3V	

Sample Class OW

ORGANIC WATER DUS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number.. 2

Test Description
Code, Units of Measure 0047-0076

Method

DETHYLATED ATRAZINE	(200. <U
P2DATR, NG/L (Nanogram/Litre)	
U01P3V	
METALACHLOR	(500. <U
POMET, NG/L (Nanogram/Litre)	
U01P3V	
LASSO	(500. <U
POLASS, NG/L (Nanogram/Litre)	
U01P3V	
DIETHYL SIMAZINE	(200. <U
P2DSIM, NG/L (Nanogram/Litre)	
U01P3V	
HEXACHLOROETHANE	(1. <U
X2HCE, NG/L (Nanogram/Litre)	
U04B1X	
135-TRICHLOROBENZENE	(5. <U
X2135, NG/L (Nanogram/Litre)	
U04B1X	
124TRICHLOROBENZENE	(5. <U
X2124, NG/L (Nanogram/Litre)	
U04B1X	
HEXACHLOROBUTADIENE	(1. <U
X1HCBD, NG/L (Nanogram/Litre)	
U04B1X	
123TRICHLOROBENZENE	(5. <U
X2123, NG/L (Nanogram/Litre)	
U04B1X	
2,4,5-TRICHLOROTOLUENE	(5. <U
X2T245, NG/L (Nanogram/Litre)	
U04B1X	
2,3,6-TRICHLOROTOLUENE	(5. <U
X2T236, NG/L (Nanogram/Litre)	
U04B1X	
1235TETRACHLOROBENZENE	(1. <U
X21235, NG/L (Nanogram/Litre)	
U04B1X	
1245 TETRACHLOROBENZENE	(1. <U
X21245, NG/L (Nanogram/Litre)	
U04B1X	
2,6-DIPICHLOROTOLUENE	(5. <U
X2T26A, NG/L (Nanogram/Litre)	
U04B1X	
1234TETRACHLOROBENZENE	(1. <U
X21234, NG/L (Nanogram/Litre)	
U04B1X	

Sample Class OW

ORGANIC WATER DUS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number 2

Test Description
Code, Units of Measure Method 0U47-0076

PENTACHLOROBENZENE X2PNCB, NG/L (Nanogram/Litre) U04B1X	<1. <U
PCB, TOTAL P1PCET, NG/L (Nanogram/Litre) U04B1X	<20. <U
HEXACHLOROBENZENE X2HCB, NG/L (Nanogram/Litre) U04B1X	<1. <U
HEPTACHLOR P1HEPT, NG/L (Nanogram/Litre) U04B1X	<1. <U
ALDRIN P1ALDR, NG/L (Nanogram/Litre) U04B1X	<1. <U
PP-DDE P1PPDE, NG/L (Nanogram/Litre) U04B1X	<1. <U
MIREX P1MIPX, NG/L (Nanogram/Litre) U04B1X	<5. <U
A-BHC HEXACHLOROCYCLOHEX P1BHCA, NG/L (Nanogram/Litre) U04B1X	<1. <U
B-BHC HEXACHLOROCYCLOHEX P1BHCB, NG/L (Nanogram/Litre) U04B1X	<1. <U
C-BHC HEXACHLOROCYCLOHEX P1BHCC, NG/L (Nanogram/Litre) U04B1X	<1. <U
A-CHLORDANE P1CHLA, NG/L (Nanogram/Litre) U04B1X	<2. <U
C-CHLORDANE P1CHLG, NG/L (Nanogram/Litre) U04B1X	<2. <U
OXYCHLORDANE P1OCHL, NG/L (Nanogram/Litre) U04B1X	<2. <U
OP-DDT P1OPDT, NG/L (Nanogram/Litre) U04B1X	<5. <U
PP-DDD P1PPDD, NG/L (Nanogram/Litre) U04B1X	<5. <U

Sample Class OW

DUS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number 2

Test Description
Code, Units of Measure

Method

PP-DDT	(5. <W
P1PPDT, NG/L (Nanogram/Litre)	
U04B1X	
DDT METHOXYCHLOR	(5. <W
P1MDT, NG/L (Nanogram/Litre)	
U04B1X	
HEPTACHLOREPOXIDE	(1. <W
P1HEPE, NG/L (Nanogram/Litre)	
U04B1X	
ENDOSULFAN I	(2. <W
P1END1, NG/L (Nanogram/Litre)	
U04B1X	
DIELDRIN	(2. <W
P1DIEL, NG/L (Nanogram/Litre)	
U04B1X	
ENDRIN	(5. <W
P1ENDR, NG/L (Nanogram/Litre)	
U04B1X	
ENDOSULFAN II	(5. <W
P1END2, NG/L (Nanogram/Litre)	
U04B1X	
ENDOSULFAN SULPHATE	(5. <W
P1ENDS, NG/L (Nanogram/Litre)	
U04B1X	
OCTACHOROSTYRENE	(1. <W
X20CST, NG/L (Nanogram/Litre)	
U04B1X	
TOXAPHENE	(500. <W
P1TOX, NG/L (Nanogram/Litre)	
U04B1X	
PHENANTHRENE	(10. <W
B3001X, NG/L (Nanogram/Litre)	
X3H1D1	
ANTHRACENE	(1. <W
B3002X, NG/L (Nanogram/Litre)	
X3H1D1	
FLUORANTHENE	(20. <W
B3003X, NG/L (Nanogram/Litre)	
X3H1D1	
PYRENE	(20. <W
B3004X, NG/L (Nanogram/Litre)	
X3H1D1	
BENZ(A)ANTHRACENE	(20. <W
B3005X, NG/L (Nanogram/Litre)	
X3H1D1	

Sample Class: OU

ORGANIC WATER DWS

Results

Inquiries at: DAVID HALL
Telephone: 416-235-5910

Field Sample Number... 2

Test Description
Code, Units of Measure 0U47-0076

Method

CHRYSENE	(50. <U
B3006X, NG/L (Nanogram/Litre) X3H1D1	
DIMETH. BENZ(A)ANTHRACENE	!QU
B3007X, No Units available	
BENZO(E)PYRENE	(50. <U
B3008X, NG/L (Nanogram/Litre) X3H1D1	
BENZO(B)FLUORANTHENE	(10. <U
B3010X, NG/L (Nanogram/Litre) X3H1D1	
PERYLENE	(10. <U
B3011X, NG/L (Nanogram/Litre) X3H1D1	
BENZO(K)FLUORANTHENE	(1. <U
B3012X, NG/L (Nanogram/Litre) X3H1D1	
BENZO(A)PYRENE	(5. <U
B3013X, NG/L (Nanogram/Litre) X3H1D1	
BENZO(C,H,I)PERYLENE	(20. <U
B3014X, NG/L (Nanogram/Litre) X3H1D1	
DIBENZ(A,H)ANTHRACENE	(10. <U
B3015X, NG/L (Nanogram/Litre) X3H1D1	
INDENO(1,2,3-C,D)PYRENE	(20. <U
B3016X, NG/L (Nanogram/Litre) X3H1D1	
BENZO(B)CHRYSENE	(2. <U
B3017X, NG/L (Nanogram/Litre) X3H1D1	
CORONENE	(10. <U
B3019X, NG/L (Nanogram/Litre) X3H1D1	

REMARK CODE EXPLANATIONS

RMK

DESCRIPTION

100 NO DATA: QUALITY CONTROLS UNACCEPTABLE.
(T A MEASURABLE TRACE AMOUNT: INTERPRET WITH CAUTION
(W NO MEASURABLE RESPONSE (ZERO)): <REPORTED VALUE
APS ADDITIONAL PEAK, SMALL, NOT PRIORITY POLLUTANT
UCS UNRELIABLE: CONTAMINATION SUSPECTED.

*** END OF REPORT ***

Appendix J

**CHEMICAL ANALYSES OF SOIL SAMPLES
FROM BURIED TAR POND WASTE AREA, JUNE 1991**

R E P O R T O F A N A L Y S I S

CLIENT CH2M Hill Engineering Ltd.

PROJECT NO. 91-06137

ATTENTION Ms. Tammy Middleton

RECEIVED June 17, 1991

ADDRESS 180 King Street, Suite 600
Waterloo, Ontario
N2J 1P8


REPORTED June 28, 1991

REISSUED July 4, 1991

Dear Ms. Middleton:

Please find attached your Base Neutral Extractables Reissued Results as per your request for analysis reported on a dry weight basis on samples submitted on June 17, 1991. If you have any further questions or problems with these please do not hesitate to call us.

Respectfully yours,



JEANINE WAUGH,
TRACE ORGANICS SUPERVISOR

THE LIABILITY OF CANVIRO ANALYTICAL LABORATORIES LTD. OR ASSOCIATED FIRMS, EXTENDS ONLY TO THE PRICE OF THE ANALYSIS.



BASE NEUTRAL ACID EXTRACTABLES BY "GC/MS"

IDENTIFICATION		#1 TRENCH 1 - 1m	#2 TRENCH 1 - 2m	#3 TRENCH 3 - 1m	MOL
IDENTIFICATION NO.		06137-01	06137-02	06137-03	
NO	COMPOUND	ug/kg	ug/kg	ug/kg	ug/kg
1	Camphene	<	<	<	9200
2	bis(2-chloroethyl)ether	<	<	<	1440
3	o-Cresol	<	<	<	40
4	m-Cresol	<	<	<	40
5	p-Cresol	<	<	<	40
6	bis(2-chloroisopropyl) ether	<	<	<	360
7	Phenol	<	<	<	240
8	Nitrosodi-n-propylamine	<	<	<	40
9	bis(2-chlorethoxy)methane	<	<	<	40
10	Naphthalene	417	<	7134	40
11	2-Chlorophenol	<	<	<	120
12	2,4-Dimethylphenol	<	<	<	320
13	Indole	<	<	<	80
14	2-methylnaphthalene	1210	<	15100	80
15	1-Methylnaphthalene	1140	<	10900	80
16	4-chloro-3-methylphenol	<	<	<	80
17	2-chloronaphthalene	<	<	<	80
18	1-chloronaphthelene	<	<	<	80
19	2,6-dichlorophenol	<	<	<	80

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		#1 TRENCH 1 - 1m	#2 TRENCH 1 - 2m	#3 TRENCH 3 - 1m	MDL
IDENTIFICATION NO.		06137-01	06137-02	06137-03	
NO	COMPOUND	ug/kg	ug/kg	ug/kg	ug/kg
20	2,4-dichlorophenol	<	<	<	80
21	Diphenyl ether	<	<	<	80
22	2,4,6-trichlorophenol	<	<	<	120
23	Acenaphthylene	<	<	<	80
24	2,4-dinitrophenol	<	<	<	1120
25	2,6-dinitrotoluene	<	<	<	2280
26	4-nitrophenol	<	<	<	4800
27	Acenaphthene	<	<	<	80
28	2,3,5-trichlorophenol	<	<	<	80
29	2,4,5-trichlorophenol	<	<	<	160
30	2,3,4-trichlorophenol	<	<	<	80
31	2,4-dinitrotoluene	<	<	<	2440
32	Fluorene	<	<	4020	80
33	4-chlorophenyl phenyl ether	<	<	<	80
34	4,6-dinitro-o-cresol	<	<	<	37600
35	Total Diphenylamine	<	<	<	80
36	2,3,5,6-tetrachlorophenol	<	<	<	80
37	2,3,4,6-tetrachlorophenol	<	<	<	80
38	2,3,4,5-tetrachlorophenol	<	<	<	80
39	4-bromophenyl phenyl ether	<	<	<	80

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		#1 TRENCH 1 - 1m	#2 TRENCH 1 - 2m	#3 TRENCH 3 - 1m	MDL
IDENTIFICATION NO.		06137-01	06137-02	06137-03	
NO	COMPOUND	ug/kg	ug/kg	ug/kg	ug/kg
40	Phenanthrene	400	<	28400	40
41	Anthracene	414	<	13000	40
42	Pentachlorophenol	<	<	<	40
43	Biphenyl	<	<	785	80
44	Fluoranthene	141	<	4840	40
45	Pyrene	274	<	8130	40
46	Benzybutylphthalate	<	<	<	80
47	Benzo (a) anthracene	67.6	<	1990	40
48	Chrysene	<	<	1750	440
49	bis(2-ethylhexyl)phthalate	458	463	4340	40
50	Di-n-butylphthalate	116	496	<	80
51	Benzo (b) fluoranthene	<	<	2230	80
52	Benzo (k) Fluoranthene	<	<	**	40
53	Benzo (a) pyrene	<	<	1340	40
54	Perylene	<	<	<	40
55	5-Nitroacenaphthene	<	<	<	40
56	Indeno(1,2,3-cd)pyrene	<	<	<	40
57	Dibenzo(ah)anthracene	<	<	<	40
58	Benzo(ghi)perylene	90.0	<	<	40
% RECOVERY OF SURROGATES					
d6-Phenol		*	*	*	
d8-Naphthalene		*	*	*	
d12-Chrysene		*	*	*	

* - Recovery not possible due to dilution and matrix interference.

** - Benzo (b) and (k) fluoranthene coeluted, therefore, result is reported as a total.

NOTE: Samples have NOT been corrected for laboratory blank.

BASE NEUTRAL ACID EXTRACTABLES BY "GC/MS"

IDENTIFICATION		#4 TRENCH 3 - 2m	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.		06137-04			
NO	COMPOUND	ug/kg	ug/kg	%	ug/kg
1	Camphene	<	<	40	9200
2	bis(2-chloroethyl)ether	<	<	98	1440
3	o-Cresol	<	<	80	40
4	m-Cresol	8800	<	71	40
5	p-Cresol	9010	<	87	40
6	bis(2-chloroisopropyl) ether	<	<	37	360
7	Phenol	61500	<	52	240
8	Nitrosodi-n-propylamine	<	<	75	40
9	bis(2-chlorethoxy)methane	<	<	61	40
10	Naphthalene	45900	<	69	40
11	2-Chlorophenol	<	<	83	120
12	2,4-Dimethylphenol	<	<	111	320
13	Indole	<	<	95	80
14	2-methylnaphthalene	90900	<	75	80
15	1-Methylnaphthalene	55500	<	76	80
16	4-chloro-3-methylphenol	<	<	87	80
17	2-chloronaphthalene	<	<	73	80
18	1-chloronaphthelene	<	<	85	80
19	2,6-dichlorophenol	<	<	90	80

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		#4 TRENCH 3 - 2m	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.		06137-04			
NO	COMPOUND	ug/kg	ug/kg	%	ug/kg
20	2,4-dichlorophenol	<	<	89	80
21	Diphenyl ether	<	<	83	80
22	2,4,6-trichlorophenol	<	<	98	120
23	Acenaphthylene	<	<	89	80
24	2,4-dinitrophenol	<	<	267	1120
25	2,6-dinitrotoluene	<	<	88	2280
26	4-nitrophenol	<	<	63	4800
27	Acenaphthene	<	<	82	80
28	2,3,5-trichlorophenol	<	<	97	80
29	2,4,5-trichlorophenol	<	<	109	160
30	2,3,4-trichlorophenol	<	<	97	80
31	2,4-dinitrotoluene	<	<	77	2440
32	Fluorene	18200	<	86	80
33	4-chlorophenyl phenyl ether	<	<	83	80
34	4,6-dinitro-o-cresol	<	<	152	37600
35	Total Diphenylamine	<	<	75	80
36	2,3,5,6-tetrachlorophenol	<	<	95	80
37	2,3,4,6-tetrachlorophenol	<	<	99	80
38	2,3,4,5-tetrachlorophenol	<	<	104	80
39	4-bromophenyl phenyl ether	<	<	93	80

BASE NEUTRAL ACID EXTRACTABLES (CONT)

IDENTIFICATION		#4 TRENCH 3 - 2m	LAB BLANK	RECOVERY SPIKE	MDL
IDENTIFICATION NO.		06137-04			
NO	COMPOUND	ug/kg	ug/kg	%	ug/kg
40	Phenanthrene	85200	<	67	40
41	Anthracene	49000	<	66	40
42	Pentachlorophenol	<	<	93	40
43	Biphenyl	10400	<	85	80
44	Fluoranthene	4670	<	73	40
45	Pyrene	1220	<	62	40
46	Benzybutylphthalate	<	0.05	66	80
47	Benzo (a) anthracene	5420	<	54	40
48	Chrysene	5060	<	53	440
49	bis(2-ethylhexyl)phthalate	22600	0.19	80	40
50	Di-n-butylphthalate	<	0.33	82	80
51	Benzo (b) fluoranthene	<	<	72	80
52	Benzo (k) Fluoranthene	<	<	74	40
53	Benzo (a) pyrene	<	<	56	40
54	Perylene	<	<	63	40
55	5-Nitroacenaphthene	<	<	66	40
56	Indeno(1,2,3-cd)pyrene	<	<	56	40
57	Dibenzo(ah)anthracene	<	<	51	40
58	Benzo(ghi)perylene	<	<	52	40
% RECOVERY OF SURROGATES					
d6-Phenol		*	30	48	
d8-Naphthalene		*	42	61	
d12-Chrysene		*	31	47	

* - Recovery not possible due to dilution and matrix interference.
NOTE: Samples have NOT been corrected for laboratory blank.

